

Arlington Conservation Commission

Date: Thursday, January 7, 2021

Time: 7:30 PM

Location: Conducted by Remote Participation

Please note: The listing of matters are those reasonably anticipated which may be discussed at the meeting. Not all items listed may in fact be discussed and other items not listed may be brought up for discussion to the extent permitted by law.

Agenda

Administrative

a. In accordance with the Governor's Order Suspending Certain Provisions of the Open Meeting Law, G. L. c. 30A, § 20 relating to the COVID-19 emergency, the January 7, 2021 public meeting of the Arlington Conservation Commission shall be physically closed to the public to avoid group congregation. The meeting shall instead be held virtually using Zoom.

Topic: Conservation Commission Meeting

Time: January 7, 2021 07:30 PM Eastern Time (US and Canada)

Register in advance for this meeting:

https://town-arlington-ma-us.zoom.us/meeting/register/tJEpcuCvqzMiH9Ewibvnx82ZXRBdNGuPB0Jg

Members of the public are strongly encouraged to send written comment regarding any of the hearings listed below to Conservation Agent Emily Sullivan at esullivan@town.arlington.ma.us.

Please read Governor Baker's Executive Order Suspending Certain Provision of Open Meeting Law for more information regarding virtual public hearings and meetings: https://www.mass.gov/doc/open-meeting-law-order-march-12- 2020/download

- b. Review draft 12/03/2020 minutes.
- c. Review draft 12/17/2020 minutes.
- d. Review draft 2020 annual report.
- e. Update on ZBA 1/5/2021 hearing on 1165R Mass Ave Comprehensive Permit.

2. Discussion

a. Discussion on proposed Warrant Article: Zoning Bylaw Amendment/Allow cemetery use in the open space district

3. Hearings

Notice of Intent

Notice of Intent: Arlington Reservoir Master Plan Phase 2, 210 Lowell Street Continued Hearing

MassDEP File #091-0327

This project consists of the second phase of implementation of the Arlington Reservoir Master Plan and includes the following activities: parking area and stormwater improvements; improvements to existing pathways to make them

7:45pm

stormwater improvements; improvements to existing pathways to make them accessible under the Americans with Disabilities Act (ADA); renovation and addition of new recreational facilities; shoreline bank stabilization; and upland habitat restoration and invasive species removal. Proposed project work is within the 100-ft Wetlands Buffer and Inland Bank area of the Arlington Reservoir. This project was first presented to the Commission at its 12/17/2020 meeting.

Request for Determination of Applicability

Request for Determination of Applicability: 59 Lowell Street Arlington File #A21.1

8:30pm

The project proposes to construct an above-ground exercise swim spa partially within the Wetlands 100-ft Buffer and Adjacent Upload Resource Area (AURA) of No Name Brook.



Town of Arlington, Massachusetts

Review draft 12/03/2020 minutes

Summary:

Review draft 12/03/2020 minutes.

ATTACHMENTS:

Type File Name Description

Minutes 12032020_Minutes_Conservation_Commission.pdf Draft 12/03/2020 Minutes



Arlington Conservation Commission

Date: December 3, 2020

Time: 7:30pm

Location: Conducted through Remote Participation using Zoom

Minutes

Attendance: Commission Members Susan Chapnick (Chair), Mike Gildesgame, Pam Heidell, Dave Kaplan, Nathaniel Stevens, Chuck Tirone (Vice Chair), and David White; Associate Commissioners Cathy Garnett and Doug Kilgour; and Conservation Agent Emily Sullivan. Representatives for the DPW NOI hearing included: Mike Rademacher (DPW), Jeff Alberti (Weston & Sampson), and Elena Compter (Weston & Sampson). Representatives for the Thorndike Place Working Session included: John Hession (BSC), Tood Undzis (BETA), Julia Stearns (BETA), Stephanie Kiefer (Smolak & Vaughn), Gwen Noyes (Oak Tree Development), Arthur Klipfel (Oak Tree Development), and Christian Klein (ZBA). Members of the public included: Adrienne Landry, Ann LeRoyer, Brian Rehrig, Dan Swanson, Mara Vatz, Patrick Hanlon, Tome Mason, Chris Vrotsos, Steve Revilak, Marina Popova, Mary Ellen Aronow, Kimberley Conant, Nancy Gray, Andy Forbes, David Barlow, Jennifer Griffith, Marci Shapiro-Ide, and Barbara Rowland.

11/19/2020 Meeting Minutes

The Commission discussed edits to the draft 11/19/2020 minutes. D. White motioned to approve the minutes as edited, P. Heidell seconded, all were in favor, motion approved. A roll call vote was taken. S Chapnick voted yes, M. Gildesgame voted yes, P. Heidell voted yes, D. Kaplan voted yes, C. Tirone voted yes, and D. White voted yes. N. Stevens had not yet joined the meeting.

General Updates

D. White updated the Commission that the DPW yard rezoning and capital requests had been passed at the recent Special Town Meeting.

Notice of Intent: 51 Grove Street, Arlington Department of Public Works MassDEP File #091-0326

Documents Reviewed:

- DPW Facility 51Grove Street NOI, prepared by Weston & Sampson, dated October 22, 2020
- Arlington Town Yard Facility 51 Grove Street NOI Plan Set, prepared by Weston & Sampson, dated October 21, 2020
- 3) Supplemental Materials for DPW Facility NOI, prepared by Weston & Sampson, dated 11242020

Resource Areas:

- 1) 100-ft Wetlands Buffer
- 2) Adjacent Upland Resource Area
- 3) 200-ft Riverfront Area
- 4) Floodplain and Floodway
- 5) Mill Brook

This project proposes a new/renovated Municipal Facility to support the Department of Public Works (DPW), Inspectional Services Department (ISD), Facilities, and IT departments at 51 Grove Street. The proposed site includes the current 4.4-acre parcel, used by DPW / ISD, and an adjacent 1.4-acre portion of Town-owned land for a total of 5.8 acres. The site has Activity and Use Limitations (AUL) as defined by MassDEP due to site contamination, and therefore has contact barriers and engineered barriers (mostly pavement) per MassDEP requirements to prevent exposure to underlying contaminated soil. Sections of the site are within the 100-ft Wetlands Buffer, AURA, and 200-ft Riverfront Area of Mill Brook, as well as floodway and floodplain.

The Conservation Commission had a working session for this project proposal during its August 20, 2020 meeting. The public hearing for this NOI began at the Commission's November 5, 2020 meeting. During the November 5, 2020 meeting, the Commission requested the following supplemental materials:

- 1) Stormwater: on sheet c-6 0-3, replace stormwater unit 4 with catch basin
- 2) Stormwater: consider proprietary separator/treatment unit between Building D and berm where existing stormwater system is
- 3) Stormwater: consider adding canopy to materials storage area
- 4) Stormwater: consider grading materials storage area so sheet flow does not enter stormwater system
- 5) Vegetation: reconsider proposed ash trees, or develop management plan
- 6) Stormwater: update stormwater calculations with NOAA Atlas 14 Plus
- 7) Stormwater: update stormwater calculations with NOAA Atlas 14 Plus Plus
- 8) Stormwater: update specification language
- 9) Impervious Area: breakout impervious surfaces calculations into 200-ft Riverfront Area and 100-ft Wetlands AURA/Buffer
- 10) Stormwater: consider making the 80% TSS reduction in new impervious area a 90% TSS reduction
- 11) Amenities: consider opportunities for educational signage regarding stormwater improvements
- 12) Vegetation: strengthen statements of vegetation survivability, replacement, and maintenance; consider longer maintenance period than three years
- 13) Vegetation: include invasive management plan
- 14) Stormwater: consider increasing the proposed 44% TSS reduction in existing impervious area

Jeff Alberti from Weston & Sampson presented the supplemental materials and subsequent changes made since the November 5, 2020 hearing. The changes included:

- The Grading and Drainage Plan (sheet C-603) had been revised as requested by the Commission. A new catch basin is proposed in place of previously shown SWTU-4, and water quality unit was instead moved downstream of catch basin.
- The Grading and Drainage Plan (Sheet 603) had been revised as requested by the Commission. A new water quality unit had been added on the downstream of the existing drainage network, prior to discharging into Mill Brook.
- One Ash tree previously proposed on site had been replaced with a Hackberry tree (Celtis Occidentalis) as a more resilient alternative.
- HydroCAD model has been updated with NOAA Atlas 14 Plus Plus rainfall depths. Revised comparison table and HydroCAD analysis was provided. An analysis using NOAA Atlas 12 Plus rainfall depths had also been completed, and rainfall comparison table was provided as well. The following rainfall depths were used for NOAA Plus and NOAA Plus Plus rainfall:

	NOAA+ Rainfall (in)	NOAA++Rainfall (in)
2 – Year Storm	3.63	4.04
10 – Year Storm	5.79	6.43
25 – Year Storm	7.49	8.32
50 – Year Storm	8.72	9.69
100 – Year Storm	10.45	11.5

- Educational signage will be developed and displayed in the areas of proposed rain gardens showcasing LID measures implemented on site.
- The typical warranty period for new plantings is one year. Project specifications were revised to increase this warranty period to two years. After the warranty period, the DPW will be responsible for evaluating the health of the landscape areas each planting season, in the spring and the fall. Any unhealthy plantings identified by the DPW will be evaluated and replaced if necessary.
- The initially proposed 44% TSS reduction was able to increase to 47%, however due to the physical and environmental constraints of the site, a higher reduction rate was not feasible.

This project proposes high reflectance roofs on the buildings to mitigate for heat island effects. The proposed plantings and trees are also to mitigate for heat island effects.

D. Kaplan asked whether the NOAA+ and NOAA++ analysis changed the sizing of the proposed stormwater system. E. Compter stated that the additional NOAA+ and NOAA++ analysis did not change the sizing or redesign the stormwater system. The system was designed to manage a 25-year storm. D. Kaplan asked whether there was capacity onsite to enlarge the stormwater system. J. Alberti stated the system could not be enlarged because of the contaminated site and barrier, and constraints from the high pressure gas main onsite.

P. Heidell asked whether the stormwater system could be sized larger than the 25-year storm due to climate change impacts on increased precipitation. E. Compter stated that

Arlington requires a 25-year storm capacity and that a larger capacity would be cost prohibitive.

- S. Chapnick asked for clarification on the proposed invasive removal method and whether the project was proposing to remove trees and grind down tree stumps.
- C. Garnett stated that stump grinding was not necessary unless the stumps were hazardous or in a high traffic area. C. Garnett recommended permitting the same invasive management methods that were permitted in the AHS permit, which included the cut-and-dab method.
- P. Heidell motioned to close the public hearing for 51 Grove Street, DPW Facility Renovation MassDEP File #091-0326, D. Kaplan seconded, all were in favor, motion approved. A roll call vote was taken. S Chapnick voted yes, M. Gildesgame voted yes, P. Heidell voted yes, D. Kaplan voted yes, C. Tirone voted yes, and D. White voted yes. N. Stevens had not yet joined the meeting.

The Commission discussed possible conditions and asked E. Sullivan to draft a permit for the Commission to deliberate during its December 17, 2020 meeting.

Thorndike Place Working Session

The Conservation Commission met with the Thorndike Place Applicant's Engineer (BSC Group) and the Town's Third-Party Reviewer (BETA) to review updated application materials related to wetland resources and stormwater in advance of the Zoning Board of Appeals' 12/10/2020 hearing. These updated materials included:

- Report on Existing Conditions (Section 3.2.6 of Arlington Comprehensive Permit Regulations)
- Architectural Drawings
 - o 3D Perspective View (1 sheet)
 - Floor Plans (4 sheets) Garage, Ground Floor, Typical 2nd/3rd, and 4th Floor
 - Exterior Elevations (3 sheets) showing all building sides with Material Legend and Type of Construction
 - Courtyard Section (1 sheet)
- Site Plans revised November 3, 2020 reflecting new building program presented at the October 13, 2020 public hearing
- Stormwater Report
- Wildlife Habitat and Vegetation Evaluation
- Updated wetlands delineation dated October 2020
- Updated waiver request list
- Statement of Compliance with Arlington's Master Plan, Housing Production Plan, and Open Space and Recreation Plan.
- D. White recused himself from the working session.

S. Chapnick presented opening remarks about the process of the 40B Comprehensive Permit review under the ZBA and the roles of the ZBA and other Town permitting boards, including the Conservation Commission. S. Chapnick clarified that this is a Thorndike Place Working Session, not a public hearing, and the goal is to discuss changes to the project since the Commission's October 1, 2020 working session. She noted that while there will be an opportunity for the public to provide feedback directly to the Conservation Commission at the end of the working session, members of the public are encouraged to send comments directly to the ZBA.

The Applicant's Representative J. Hession presented the updated project proposal, comparing the September 2020 proposal to the November 2020 proposal. These changes included an updated wetlands delineation which found that the two Isolated Vegetated Wetlands were no longer resource areas. The project also proposes 2:1 compensatory flood storage outside of resource areas.

The Town's Third-Party Reviewer, BETA, summarized their review of the Applicant's updated comprehensive permit application. T. Undzis, BETA's civil engineer, reviewed the proposed stormwater system and stated that the roof system did not include all pertinent information needed for a complete review. T. Undzis stated that the 2:1 compensatory flood storage proposal looked accurate.

- J. Stearns, BETA's wetlands specialist, stated that the wetlands delineation looked accurate. J. Stearns stated that the two areas identified as Isolated Vegetated Wetlands in the past currently did not meet the definition of Isolated Vegetated Wetlands due to lack of hydrologic characteristics and absence of wetlands vegetation. BETA did not conduct a subsoil assessment in these areas, but analyzed historic aerial photos and did not identify other filled wetlands.
- J. Stearns summarized that the wildlife on the site was minimal urban wildlife semi fragment from other open spaces (e.g. Spy Pond, Alewife Brook). J. Stearns stated that overall BETA agreed with BSC's wildlife evaluation and confirmed that the building footprint was outside of wetlands resource areas.
- S. Chapnick summarized the Commission's most recent comment letter, dated November 20, 2020. The letter made recommendations for five topic areas:
 - 1. Wetlands Delineation
 - 2. Floodplain and Compensatory Flood Storage
 - 3. Stormwater Management
 - 4. Evaluation of Wildlife Habitat and Vegetation
 - 5. Conservation Restriction for Undeveloped of the Mugar Parcel
- S. Chapnick stated that the isolated vegetated wetlands delineation did not have a thorough soils assessment and referenced the Town Engineer's comment letter dated December 3, 2020 recommending a more thorough soil assessment.

- J. Hession stated that the wetlands delineation was conducted per MassDEP and Army Corps of Engineers standards. A request from the Commission to conduct additional soil assessment would go beyond industry standards and the requirements of a comprehensive permit application.
- S. Chapnick stated that she was concerned with the location go the compensatory flood storage, and that the current homeless encampment area may be a better location.
- S. Chapnick referenced future flood modeling conducted by the City of Cambridge, as well as Woods Hole Group. These models suggest flooding in this area will become worse due to climate change.
- P. Heidell asked whether additional precautions should be taken onsite given the modeling.
- T. Undzis stated that the proposed location of the compensatory flood storage area was agreeable due to its upland location. The homelessness encampment area is closer to the Adjacent Upland Resource Area (AURA) and compensatory flood storage there would have a greater resource area impact. T. Undzis stated that the Applicant had sufficiently proven that 2:1 storage was feasible.
- S. Chapnick stated that the Commission could recommend that the ZBA condition the permit for this project with a condition requiring the Applicant to re-vegetate or restore the compensatory flood storage area to add habitat value. J. Hession stated that the landscape plan calls out restoration and re-vegetation in the compensatory flood storage area. The planting plan would be developed with the Commission's guidance.
- S. Chapnick stated that the rooftop stormwater system did not include enough information for review.
- S. Chapnick stated that the existing ground water levels onsite need to be verified.
- P. Heidell stated that ground water is usually highest in March and April. Given the specific schedule of 40B Comprehensive Permits, how would the water levels be accurately verified. P. Heidell asked how stormwater infiltration units could be sited without knowing the ground water level.
- J. Hession stated that test pit assessments were conducted last week and confirmed that the proposed stormwater unit locations were appropriate. J. Hession stated that the soil drains better than the conditions the stormwater system was designed to.
- S. Chapnick stated that the proposed stormwater system meets current State requirements for nutrient removal, but that the State will be updating the standards sometime in 2021. J. Hession stated that the stormwater system meets the current stormwater standards, but the Applicant may consider higher standards if there are no significant financial or logistical implications to the higher standards. S. Chapnick and P.

Heidell stated that the State will likely update the Stormwater Handbook to require that NOAA Atlas 14+ is used for stormwater calculations.

- S. Chapnick stated that the ZBA's comprehensive permit regulations include a general statement about climate change, but does not include any climate change standards that could be applied to this project.
- S. Kiefer stated that the Applicant may look at NOAA Atlas 14+ to recalculate the stormwater calculations, but ultimately the proposal has to comply with existing standards which do not require NOAA Atlas 14+.
- N. Stevens stated that the ZBA has not granted any local waivers at this time, and that Arlington's local regulations require that the Cornell Method be used for stormwater calculations, not TP40 as required by the State Stormwater Handbook. J. Hession stated that the stormwater calculations used the Cornell Method.
- S. Chapnick stated that the total number and size of trees impacted by the proposal had not been enumerated yet. S. Chapnick stated that the local regulations specify tree replacement quantities.
- S. Chapnick recommended that the Applicant consider conservation stewardship mechanisms for the remaining open space onsite to ensure protection. An example of such a mechanism is a conservation restriction, similar to the Symmes Conservation Restriction.
- C. Tirone asked whether the parking area in the western part of the site, close to homes, could be reduced. J. Hession stated that the setback in that area had been increased to provide more buffer between the neighborhood homes and that vegetative screening would be planted. J. Hession stated that area will be graded so no stormwater runoff enters the adjacent parcels. J. Hession stated that parking minimums are required for zoning, which determine the size of the parking areas.
- C. Tirone asked for clarification on the lighting of the site. J. Hession stated that the lighting had not been designed yet, but that there are standards the lighting plan will follow given the proximity to neighboring homes.
- C. Tirone asked about the site's sewer easement. J. Hession stated that the sewer easement will be protected during construction.
- M. Gildesgame asked if the roof rain capture volumes had been calculated. J. Hession stated that those volumes had not been calculated yet and that the roof stormwater system is still under design.

The Working Session was opened for public comment.

Nancy Gray asked how the public could access the Mugar site. The Commission stated that the site is private and that without explicit permission from the property owner the public cannot access the site.

Brian Rehrig asked how the proposal was factoring in future flood risk. B. Rehrig stated that previously the Commission has rejected FEMA floodplain delineations and urged the Commission to review the validity of the floodplain.

Chris Vrotsos asked for examples of similar projects that protected or enhanced the environment and resource areas.

M. Gildesgame motioned to close the Commission meeting, N. Stevens seconded, all were in favor, motioned approved.

Meeting adjourned at 10:40pm.





Town of Arlington, Massachusetts

Review draft 12/17/2020 minutes

Summary:

Review draft 12/17/2020 minutes.

ATTACHMENTS:

Type File Name Description

Minutes 12172020_Minutes_Conservation_Commission.pdf Draft 12/17/2020 Minutes



Arlington Conservation Commission

Date: December 17, 2020

Time: 7:30pm

Location: Conducted through Remote Participation using Zoom

Minutes

Attendance: Commission Members Susan Chapnick (Chair), Mike Gildesgame, Pam Heidell, Dave Kaplan, Nathaniel Stevens, Chuck Tirone (Vice Chair), and David White; Associate Commissioners Cathy Garnett and Doug Kilgour; and Conservation Agent Emily Sullivan. Representatives for the Arlington Reservoir NOI hearing included: Joe Connelly (Recreation Department), Leslie Mayer (Park & Recreation Commission), Danielle Desilets (KZLA), Brad Mustain (Woodard & Curran), Denise Cameron (Woodard & Curran), and Mikey Marcus (SWCA). Members of the public included: Jeff Alberti, Ann LeRoyer, David Barlow, Johanna Meyer, Stephan Miller, and Susan Kendall.

Conservation Offset

The Commission reviewed the proposed \$7,192 offset for the Conservation Agent's salary. N. Stevens motioned to approve the offset from the Commission's Conservation Commission Fees account, D. White seconded, all were in favor, motion approved. A roll call vote was taken. S Chapnick voted yes, M. Gildesgame voted yes, P. Heidell voted yes, D. Kaplan voted yes, N. Stevens voted yes, C. Tirone voted yes, and D. White voted yes.

Water Bodies Working Group Update

D. White updated the Commission on the Water Bodies Working Group. The Working Group met on December 10, 2020 to review the Reservoir Report submitted by Solitude Lake Management. The Working Group is still waiting for the Spy Pond and Hill's Pond Reports to be submitted. Once all reports are received, the Working Group will meet again to discuss priorities for 2021.

Notice of Intent: 210 Lowell Street, Arlington Reservoir Master Plan Phase 2
MassDEP File #091-0327

Documents Reviewed:

- 1) Arlington Reservoir Renovation Project Phase 2 NOI, prepared by SWCA, dated December 3, 2020
- 2) Arlington Reservoir Phase 2 NOI Plan Set, prepared Kyle Zick Landscape Architecture Inc, stamped by Kyle Zick RLA# 1163, dated November 13, 2020

3) Arlington Reservoir Phase 2 Stormwater Management Report, prepared by Woodard & Curran, stamped by Denis L Cameron PE# 56348, dated October 2020

Resource Areas:

- 1) 100-ft Wetlands Buffer
- 2) Adjacent Upland Resource Area
- 3) Inland Bank
- 4) Arlington Reservoir

This project consists of the second phase of implementation of the Arlington Reservoir Master Plan and includes the following activities: parking area and stormwater improvements; improvements to existing pathways to make them accessible under the Americans with Disabilities Act (ADA); renovation and addition of new recreational facilities; shoreline bank stabilization; and upland habitat restoration and invasive species removal.

Mickey Marcus and Danielle Desilets presented the project proposal. The project includes elevating the parking lot 16 inches and installing porous pavement as a stormwater best management practice. The stormwater management system meets the water quality standards of the State Stormwater Handbook, but does not meet with water quantity standards because there is no place to store water onsite.

The project proposes to stabilize approximately 2,000 linear feet of bank in Arlington, and slightly more in Lexington using coir fascine and native plantings.

- M. Gildesgame asked for more information on the proposed stabilized granite pathway. D. Desilets stated that the stabilized granite material is a material preferred by the Lexington Conservation Commission. It uses a binder and has a gravel sub-base. It is a porous material.
- P. Heidell asked if the stabilize granite material had the same drainage characteristics as the porous pavement pilot path. D. Desilets stated that they have similar drainage characteristics.
- C. Garnett stated that she was concerned with the stabilized granite material because of her experience with the Neponset River pathway. C. Garnett asked for more information on the material.

Leslie Mayer clarified that the stabilized granite material would mostly be installed in Lexington, and that the Arlington pathway would be touched up using its current surface material. The Arlington pathway was resurfaced when the Reservoir dam was reconstructed. The pathway is in great shape and needs minor touch ups.

S. Chapnick asked that the stormwater calculations be recalculated using NOAA Atlas 14+.

- S. Chapnick reminded the Recreation Department and the Park & Recreation Commission that the Order of Conditions for Phase 1 was still open and would eventually need to be closed. Phase 2 permitting could proceed without requesting a Certificate of Compliance for Phase 1.
- C. Tirone asked for clarification on the parking lot stormwater system. C. Tirone asked if every grate inlet was attached to a catch basin. B. Mustain clarified that overflow runoff will only occur at or above a 100-year storm, and that the porous pavement parking lot material will manage other storm events if maintained properly. No sheet flow will enter the grates, and water that falls into the grates will be conveyed straight to the Reservoir.
- C. Tirone asked if the parking lot above the boat ramp is porous pavement. B. Mustain stated that the parking lot above the boat ramp was not porous, and that the porous pavement only extended from the Reservoir entrance to the sidewalk in the parking lot.
- D. Kaplan recommended that a regenerative air sweeper replace the industrial vacuum in the porous pavement parking lot Operations & Maintenance Plan. D. Kaplan how the porosity of the parking lot would be monitored. B. Mustain stated that the parking lot would be visually inspected for porosity.
- D. Kaplan asked for clarification on the various invasive treatments proposed as part of the project. M. Marcus clarified that both cut-and-dab and spray application was proposed. M. Marcus stated that Buckthorn is recommended for cut-and-dab treatment, but Japanese knotweed, Phragmites, and Multiflora rose are recommended for spray treatment. D. Kaplan stated that cut-and-dab was preferred over spray treatment. C. Garnett stated that cut-and-dab treatment was an effective method.

The hearing was opened for public comment.

John Verderese asked what was the capacity of the parking lot. The Applicant stated the capacity was essentially the same. John Verderese asked whether DPW would still use the parking lot as a snow storage area. The Applicant stated that snow storage was not recommended and that the Recreation Director would confirm with DPW that the parking lot wouldn't be used for snow storage.

The Commission requested the following supplemental information and materials:

- 1) Information on Lexington's stabilized granite requirements
- 2) Recalculate stormwater calculations using NOAA Atlas 14+
- 3) Review removal/replacement of trees
- 4) Add erosion controls (silt sack) around turf area in parking lot to prevent siltation
- 5) Propose alternatives to glyphosate invasive treatment
- 6) Coordinate with DPW to ensure parking lot is not a snow dump
- 7) Revise parking lot O&M Plan to include regenerative air sweeper
- 8) Revise invasive management to include as much cut-and-dab, not spray, as possible
- 9) Update plan set with changes (erosion controls, plan has erosion control matting near flared end but rip rap might be better)

N. Stevens motioned to continue the public hearing for the Reservoir Phase 2 NOI to the Commission's January 7, 2021 meeting, D. White seconded, all were in favor, motion approved. A roll call vote was taken. S Chapnick voted yes, P. Heidell voted yes, D. Kaplan voted yes, M. Gildesgame voted yes, N. Stevens voted yes, C. Tirone voted yes, and D. White voted yes.

Deliberation: Notice of Intent: 51 Grove Street, Arlington Department of Public Works

MassDEP File #091-0326

Documents Reviewed:

- 4) DPW Facility 51Grove Street NOI, prepared by Weston & Sampson, dated October 22, 2020
- 5) Arlington Town Yard Facility 51 Grove Street NOI Plan Set, prepared by Weston & Sampson, dated October 21, 2020
- 6) Supplemental Materials for DPW Facility NOI, prepared by Weston & Sampson, dated 11242020

Resource Areas:

- 5) 100-ft Wetlands Buffer
- 6) Adjacent Upland Resource Area
- 7) 200-ft Riverfront Area
- 8) Floodplain and Floodway
- 9) Mill Brook

This project proposes a new/renovated Municipal Facility to support the Department of Public Works (DPW), Inspectional Services Department (ISD), Facilities, and IT departments at 51 Grove Street. The proposed site includes the current 4.4-acre parcel, used by DPW / ISD, and an adjacent 1.4-acre portion of Town-owned land for a total of 5.8 acres. The site has Activity and Use Limitations (AUL) as defined by MassDEP due to site contamination, and therefore has contact barriers and engineered barriers (mostly pavement) per MassDEP requirements to prevent exposure to underlying contaminated soil. Sections of the site are within the 100-ft Wetlands Buffer, AURA, and 200-ft Riverfront Area of Mill Brook, as well as floodway and floodplain.

The Conservation Commission had a working session for this project proposal during its August 20, 2020 meeting. The public hearing for this NOI began at the Commission's November 5, 2020 meeting and was continued to the December 3, 2020 meeting. The public hearing was closed on December 3, 2020.

The Commission reviewed a draft Order of Conditions for the project. The Commission discussed edits to the draft. P. Heidell motioned to approve the project under the Wetlands Protection Act and Arlington Regulations for Wetlands Project with the discussed conditions, D. White seconded, all were in favor, motion approved. A roll call vote was taken. S Chapnick voted yes, M. Gildesgame voted yes, P. Heidell voted yes, D. Kaplan voted yes, C. Tirone voted yes, and D. White voted yes. N. Stevens missed a prior hearing on this project and was not eligible to vote.

Thorndike Place Update

- D. White recused himself from the discussion.
- S. Chapnick updated the Commission on the status of the Thorndike Place Comprehensive 40B Permit. During the December 3, 2020 working session, the Commission stated that it did not accept the wetlands delineation conducted by BSC Group. The Commission had requested additional soil assessment during the working session. S. Chapnick stated that the Town's Special Town Counsel recommended that the Commission assume the two isolated vegetated wetlands are jurisdictional.
- S. Chapnick clarified that Comprehensive Permits cannot be assessed at higher standards than other projects.

The Commission reviewed a draft comment letter addressed to the ZBA.

N. Stevens motioned to close the Commission meeting, M. Gildesgame seconded, all were in favor, motioned approved.

Meeting adjourned at 10:15pm.





Town of Arlington, Massachusetts

Review draft 2020 annual report

Summary:

D

Review draft 2020 annual report.

ATTACHMENTS:

Type File Name Description

Reference Material ACC_2020_Annual_Report_draft.pdf Draft 2020 Annual Report

Conservation Commission

The Arlington Conservation Commission ("ACC") is required by state and town laws to protect and preserve wetlands, waterways, and their surrounding areas. The ACC is comprised of seven volunteer Commissioners and two volunteer Associate Commissioners, who are appointed by the Town Manager with the approval of the Select Board, and supported by the full-time professional Environmental Planner & Conservation Agent at bimonthly meetings and onsite visits. The ACC is mandated to protect wetlands, waterways, water supplies, fisheries, wildlife, and wildlife habitat as well as regulate floodplain activities through its administration of the Massachusetts Wetlands Protection Act and the Arlington Bylaw for Wetlands Protection.

In 2020, the ACC held 24 public meetings, and provided coordination, monitoring, permit review, and consultation on numerous residential, commercial, and municipal projects around Town. The ACC reviewed 21 applications. Of the 21 applications, the Commission issued 10 Permits/Orders of Conditions, 5 Determinations of Applicability, and six Certificates of Compliance. The ACC and its Agent conducted over 60 site visits/inspections.

The ACC also protects and manages the Town's Conservation Lands and natural resources through collaboration with other entities and grants from various sources, as described below.

Spy Pond Shoreline Protection Project Completion

The goals of this project included preserve, stabilize, and strengthen the pond's banks to control erosion; protect and enhance wildlife habitat; prevent unauthorized paths; broaden and strengthen constituency groups; improve water quality and recreational opportunities; and improve stormwater infiltration. Construction elements of this project included a new porous pathway through the park, a new timber overlook, a rain garden/vegetated detention basin, and native plantings along the pond banks. The project was completed in Fall 2020. Various funding sources funded this project, including a Community Preservation Act grant (\$552,900), a Land and Water Conservation Fund grant from the Massachusetts Executive Office of Energy and Environmental Affairs (\$40,040), a Community Development Block grant (\$94,000), a Mass Audubon's Judy Record Fund grant (\$10,000), and a donation from the Friends of Spy Pond Park (\$5,000).



The Spy Pond Project included constructing a biobasin next to Scannell Field to improve stormwater quality before entering Spy Pond. (credit: Arlington Conservation Commission)

Wellington Park & Mill Brook

In 2018, Arlington received one of the first Executive Office of Energy and Environmental Affairs Municipal Vulnerability Preparedness MVP action grants, in the amount of almost \$400,000 to increase flood storage capacity in Wellington Park, along Mill Brook. This increased flood storage capacity is approximately 70 cubic yards. Project construction included building the flood storage channel, removing invasive plant species, building a boardwalk, installing a porous asphalt pathway, and installing educational signage. In 2020, Arlington and the Mystic River Watershed Association (MyRWA) led the design effort for the last phase of this project, to improve the recreational amenities of the park. The final design includes extending the porous asphalt pathway through the park to the existing bridge over Mill Brook, the construction of an exploration play area, the installation of a biobasin, and replanting of native riverine plants along Mill Brook. The final phase of this project will begin construction in 2021.

Water Bodies Oversight

The ACC, through its Water Bodies Working Group, continued monitoring important water bodies in town, including Spy Pond, the Arlington Reservoir, and Hill's Pond in Monotony Rocks Park.

Conservation Land Stewards

The ACC's citizen-volunteer organization, Arlington Land Stewards (ALS), assists in managing 28 Townowned conservation lands comprising approximately 53 acres. Land Stewards monitor, coordinate, and maintain conservation land of their choice, with guidance from the ACC.

Arlington Great Meadows

Arlington's Great Meadows (AGM) are comprised of 193 acres, making it Arlington's largest open space parcel, although located in East Lexington. AGM is mostly wetlands, but contain many upland trails that make connections to the Arlington Reservoir and the Whipple Hill conservation area through the ACROSS Trail System. The Friends of Arlington's Great Meadows (FoAGM) are active in increasing Arlington's awareness of this wonderful area. In 2020, FoAGM organized multiple walks at AGM and boardwalk restoration events.

FoAGM volunteers maintain the trails and boardwalks at the Meadows. This includes removing invasive plants, consisting primarily of Japanese Knotweed, along the Minuteman Bikeway. More information on FoAGM can be found at: www.FoAGM.org.

A current concern is the redevelopment of the former nursing site off Emerson Garden Road that will affect a popular access point. Officials in Arlington and Lexington are committed to maintaining public access at this location.

Goals and Beyond

The ACC will continue to encourage, support, and assist the various volunteer and environmental advocacy groups that are dedicated to preserving the Town's valued conservation lands and other open spaces. These groups include, among others: Arlington Land Stewards, Arlington Land Trust, Open Space Committee, Friends of Arlington's Great Meadows, Friends of Spy Pond Park, Friends of Menotomy Rock Park, and the Mystic River Watershed Association. Additional specific goals include the following:

- Host additional collaborative community clean-up and educational events
- Strengthen and update regulations for performance standards, permitting efficiency, and process clarity
- Improve the stewardship of conservation lands and other town open spaces
- Improve communication and educational outreach to residents in resource areas

Acknowledgments

ACC sincerely thanks all individuals and organizations that contributed directly or indirectly to the activities of its 55th year. Many special thanks go to the active citizenry that attended hearings and informed the Commission's discussions and the scores of volunteers who came out for clean-up projects, assisted as land stewards, or participated in the many Friends groups that work to preserve the Town's natural resources and conservation lands.

Warrant Article Submission Form

PETITION OF TEN REGISTERED VOTERS FOR INSERTION OF ARTICLE INTO THE WARRANT FOR THE ANNUAL (SPECIAL) TOWN MEETING.

File Completed Form with the Office of the Select Board no later than Friday, January 29, 2021, 12:00/Noon.

We, the undersigned registered voters (10 for Annual, 100 for Special) of the Town of Arlington, hereby petition the Select Board pursuant to MGL c. 39, § 10 to insert the following article(s) into the warrant for the Annual (Special) Town Meeting.

ARTICLE

Proposed Title:

ZONING BYLAW AMENDMENT/ALLOW CEMETERY USE IN THE OPEN SPACE DISTRICT

Subject Matter:

OPEN SPACE AND CEMETARY USE

To see if the Town will vote to amend the Zoning Bylaw in Articles 5, 6, and 11 and elsewhere as may by required, to allow cemetery use solely for cremated remains on land under the jurisdiction of the Conservation Commission by special permit subject to Environmental Design Review, or take any action related thereto.

Requested by:

Allan Tosti

Watermili Place, Unit 419, Arlington, MA 02476

781 820-1580

abtosti@outlook.com



Town of Arlington, Massachusetts

Notice of Intent

Summary:

Notice of Intent: Arlington Reservoir Master Plan Phase 2, 210 Lowell Street

Continued Hearing
MassDEP File #091-0327

This project consists of the second phase of implementation of the Arlington Reservoir Master Plan and includes the following activities: parking area and stormwater improvements; improvements to existing pathways to make them accessible under the Americans with Disabilities Act (ADA); renovation and addition of new recreational facilities; shoreline bank

7:45pm Disabilities Act (ADA); renovation and ad

stabilization; and upland habitat restoration and invasive species removal. Proposed project work is within the 100-ft Wetlands Buffer and Inland Bank area of the Arlington Reservoir. This project was first presented to the Commission at its 12/17/2020 meeting.

ATTACHMENTS:

Type	File Name	Description
Notice of Intent	Arlington_Reservoir_Phase_2_NOI_12032020.pdf	Res Phase 2 NOI
Notice of Intent	Arlington_Reservoir_Phase_2_NOI_Plans_12032020.pdf	Res Phase 2 NOI Plans
Notice of Intent	Arlington_Reservoir_Phase_2_Stormwater_Report_12032020.pdf	Res Phase 2 Stormwater Report
Notice of Intent	Arlington_Reservoir_Phase_2_Supplemental_KZLA_Memo_12302020.pdf	NEW_Res Phase 2 Supplemental KZLA Memo
Notice of Intent	Arlington_Reservoir_Phase_2_Supplemental_SWCA_Memo_12312020.pdf	NEW_Res Phase 2 Supplemental SWCA Memo
Notice of Intent	Arlington_Reservoir_Phase_2_Tree_Planting_Plans_Revised.pdf	NEW_Res Phase 2 Revised Tree Planting Plan
Notice of Intent	Arlington_Reservoir_Phase_2_Parking_Lot_Plans_Revised.pdf	NEW_Res Phase 2 Revised Parking Lot Plan
Notice of Intent	Arlington_Reservoir_Phase_2_Stormwater_Report_Revised.pdf	NEW_Res Phase 2 Revised Stormwater Report
	Notice of Intent	Notice of Intent Notice of Intent Notice of Arlington_Reservoir_Phase_2_NOI_12032020.pdf Notice of Intent Notice of Intent Notice of Arlington_Reservoir_Phase_2_Stormwater_Report_12032020.pdf Notice of Intent Notice of Arlington_Reservoir_Phase_2_Supplemental_KZLA_Memo_12302020.pdf Notice of Intent Notice of Arlington_Reservoir_Phase_2_Supplemental_SWCA_Memo_12312020.pdf Notice of Intent Notice of Arlington_Reservoir_Phase_2_Tree_Planting_Plans_Revised.pdf Notice of Intent Notice of Arlington_Reservoir_Phase_2_Parking_Lot_Plans_Revised.pdf Notice of Arlington_Reservoir_Phase_2_Parking_Lot_Plans_Revised.pdf



Notice of Intent:

Arlington Reservoir Renovation Project – Phase 2 Arlington/Lexington, Massachusetts

December 2020

PREPARED FOR

Arlington Parks & Recreation Commission Arlington, Massachusetts

PREPARED BY

SWCA Environmental Consultants Kyle Zick Landscape Architecture, Inc.

SWCA Project No.: 60780



Amherst Office 15 Research Drive Amherst, Massachusetts 01002 Tel 413.256.0202 Fax 413.256.1092

December 3, 2020

Arlington Conservation Commission 730 Mass Ave. Annex Arlington, MA 02476

Re: Arlington Reservoir Project Notice of Intent Arlington & Lexington, MA

Dear Members of the Conservation Commission:

On behalf of the Town of Arlington ("Applicant"), SWCA Environmental Consultants ("SWCA") and Kyle Zick Landscape Architecture (KZLA) have prepared this Notice of Intent ("NOI") application for work within regulated resource areas and buffer zone associated with the Bathing Beach Improvements to the Arlington Reservoir in Arlington and Lexington, Massachusetts. This NOI is being submitted pursuant to the Massachusetts Wetlands Protection Act ("WPA") (M.G.L. Ch. 31 s. 40) and its implementing regulations at 310 CMR 10.00, the Arlington Wetlands Protection Bylaw ("Arlington Bylaw") and the Lexington Wetlands Protection Bylaw ("Lexington Bylaw"). The Project consists of improvements to the reservoir's existing walking path, bank stabilization, and upland habitat restoration to manage invasive species.

The Project will require work on Inland Bank, and the 100-foot buffer zone to Inland Bank, as regulated under the WPA and the Bylaws. Work being proposed in the buffer zone is within a previously developed, recreational area and is intended to improve recreational access to the public. Some work along the pond bank will require minimal encroachment into the pond for the purposes of bank stabilization and establishment of native plants; however, the encroachment will consist of biodegradable stacked coir logs and native plants to establish an aquatic shelf to help stabilize the bank. The area along the bank above the created aquatic shelf will be regraded and restored with native plantings (please refer to the attached Design Development Set prepared by SWCA for details). The project team has met with members of both the Arlington and Lexington Conservation Commissions on-site and discussed the proposed work and have concurred that the proposal is the least impacting alternative to achieve the goals of: improved public access, bank stabilization, and upland restoration. Although many of the proposed activities meet the Limited Project provisions at 310 CMR 10.53(3) and (4), the Project has been designed to meet the performance standards for all wetland resource areas to the maximum extent practicable.

Notification has been made on this date to abutters. A copy of the abutter notification form is provided in Appendix A. As a municipal project, the work is exempt from State and Local filing fees.

SWCA respectfully requests that the Arlington Conservation Commission finds the Project adequately protective of the interests of the WPA and Bylaw and issue an Order of Conditions allowing the Project to proceed as described in this NOI. We look forward to presenting this Project to the Conservation Commission.

An NOI is being submitted separately to the Lexington Conservation Commission in mid-December. Since work at the Res spans the Towns of Arlington and Lexington, we request that the Conservation Commissions coordinate language in the Orders of Conditions so that the site contractors may work with one set of Conditions. If you have any questions regarding this application or would like to set up a site walk, please do not hesitate to contact me at 413-531-7156.

Sincerely,

Mickey Marcus, PWS

cc. MassDEP, Northeast Regional Office
Town of Arlington Parks and Recreation Commission
Kyle Zick Landscape Architecture
Woodard & Curran Engineering

WPA FORM 3

Arlington



Bureau of Resource Protection - Wetlands

WPA Form 3 - Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number

Arlington City/Town

Important:
When filling out
forms on the
computer, use
only the tab key
to move your
cursor - do not
use the return
key.





Note: Before completing this form consult your local Conservation Commission regarding any municipal bylaw or ordinance.

A. General Information

210 Lowell Street	Arlingto	on 02476		
a. Street Address	b. City/To			
Latitude and Longitude:	42.428			
	d. Latitud	le e. Longitude		
Map 61 Block 1 f. Assessors Map/Plat Number	Lot 4	/Lot Number		
Applicant:	g. 7 5(55)			
Joseph	Con	nelly		
a. First Name		st Name		
Town of Arlington Parks &	A40, 544			
c. Organization				
422 Summer Street				
d. Street Address	- / / / / / /			
Arlington	Massachus			
e. City/Town	f. State	g. Zip Code		
781-316-3880		town.arlington.ma.us		
h. Phone Number i. F	ax Number j. Email Addre	555		
a. First Name	b. La	st Name		
c. Organization				
d. Street Address				
e. City/Town	f. State	g. Zip Code		
h. Phone Number i. F	ax Number j. Email addre	SS		
Representative (if any):				
Mickey	Mar	cus		
a. First Name	b. La	st Name		
SWCA Environmental Inc				
c. Company				
15 Research Drive d. Street Address				
Amherst	MA	01002		
e. City/Town	f. State	g. Zip Code		
413-531-7156	mmarcus@			
h. Phone Number i. F	ax Number j, Email addre	ess		
Total WPA Fee Paid (from	NOI Wetland Fee Transmittal Fo	orm):		
N/A	N/A	N/A		
	b. State Fee Paid	c, City/Town Fee Paid		



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands

WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

MassDEP	File Number
Documen	

A. General Information (continued)

6.	General Project Description:				
	The Arlington Parks and Recreation Commission Project Phase II, which includes parking area important pathways, new recreational facilities, a boat launce measures, and invasive species control/upland has	rovements, installation of new ADA-accessible h, bathing beach improvements, bank stabilization			
7a.	Project Type Checklist: (Limited Project Types se	ee Section A. 7b.)			
	1. Single Family Home	2. Residential Subdivision			
	3. Commercial/Industrial	4. Dock/Pier			
	5. Utilities	6. Coastal engineering Structure			
	7, Agriculture (e.g., cranberries, forestry)	8. Transportation			
	9. 🛛 Other				
[10	.53(4)] If the proposed activity is eligible to be treated as	ent uses [10.53(3)(I)], ecological restoration project an Ecological Restoration Limited Project (310 attach Appendix A: Ecological Restoration Limited			
8.	Property recorded at the Registry of Deeds for:				
	Middlesex County	N/A			
	a. County	b. Certificate # (if registered land)			
	01	01			
	c. Book	d. Page Number			
B.	Buffer Zone & Resource Area Imp	pacts (temporary & permanent)			
		경시 여전 문자 경험된다 이렇지 하다니 이렇게 하면 내내다.			
1.	Buffer Zone Only – Check if the project is local Vegetated Wetland, Inland Bank, or Coastal F	Resource Area			
2.	✓ Inland Resource Areas (see 310 CMR 10.54- Coastal Resource Areas).				
	Check all that apply below. Attach narrative and a project will meet all performance standards for eastandards requiring consideration of alternative programmer.	ich of the resource areas altered, including			



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands

WPA Form 3 - Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

MassDEP File Number
Document Transaction Number

City/Town

B. Buffer Zone & Resource Area Impacts (temporary & permanent) (cont'd)

Resource Area		rce Area	Size of Proposed Alteration	Proposed Replacement (if any)
	52	DI	2,000 (approximately)	2,000 (approximately)
	a. 🛛	Bank	1. linear feet	2. linear feet
	b. 🔲	Bordering Vegetated	0	0
		Wetland	1. square feet	2. square feet
	с. 🔲	Land Under	1. square feet	2. square feet
		Waterbodies and	0	
		Waterways	3. cubic yards dredged	
	Resou	rce Area	Size of Proposed Alteration	Proposed Replacement (if any)
	d. \square	Bordering Land		
	о. <u>С</u>	Subject to Flooding	1. square feet	2. square feet
			3. cubic feet of flood storage lost	4. cubic feet replaced
	е. 🗌	Isolated Land		
	2,720	Subject to Flooding	1. square feet	
			2. cubic feet of flood storage lost	3. cubic feet replaced
		Table Lee Novel	Mill Brook (inland)	
	f. 🛛	Riverfront Area	1. Name of Waterway (if available) - s	pecify coastal or inland
	2.	and the second s	a (check one): Densely Developed Areas only	
		☐ 100 ft New agricu	Itural projects only	
		200 ft All other pr	oiects	
		Z 200 11. 7 11 011 01 pr	ojucio	80.00
	3.	Total area of Riverfront A	rea on the site of the proposed pro	ject: 30,000 square feet
	4.	Proposed alteration of the	Riverfront Area:	
				0
	a.	total square feet	b. square feet within 100 ft.	c. square feet between 100 ft. and 200 ft.
	5.	Has an alternatives analy	sis been done and is it attached to	this NOI? ☐ Yes ☒ No
	6.	Was the lot where the act	tivity is proposed created prior to A	ugust 1, 1996? X Yes No
3.	□ Cc	pastal Resource Areas: (S	ee 310 CMR 10.25-10.35)	
				4 6 2 1 2 1
	Note:	for coastal riverfront area	s, please complete Section B.2.f.	above.

affecting other Resource Areas, please attach a narrative explaining how the resource area was delineated.

For all projects



Bureau of Resource Protection - Wetlands

WPA Form 3 - Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

P	Provided by MassDEP:
	MassDEP File Number
	Document Transaction Number
	Arlington

City/Town

B. Buffer Zone & Resource Area Impacts (temporary & permanent) (cont'd)

Check all that apply below. Attach narrative and supporting documentation describing how the project will meet all performance standards for each of the resource areas altered, including standards requiring consideration of alternative project design or location.

Online Users: Include your document transaction number (provided on your receipt page) with all supplementary information you submit to the Department.

Resou	rce Area	Size of Proposed Altera	tion Proposed Replacement (if any)
а. 🔲	Designated Port Areas	Indicate size under La	nd Under the Ocean, below
b. 🔲	Land Under the Ocean	1. square feet	
		2. cubic yards dredged	
с. 🔲	Barrier Beach	Indicate size under Coa	stal Beaches and/or Coastal Dunes below
d. 🔲	Coastal Beaches	1. square feet	2. cubic yards beach nourishment
е. 🗌	Coastal Dunes	1. square feet	2. cubic yards dune nourishment
		Size of Proposed Altera	tion Proposed Replacement (if any)
f. 🗆	Coastal Banks	1. linear feet	
g. 🔲	Rocky Intertidal Shores	1. square feet	
h. 🔲	Salt Marshes	1. square feet	2. sq ft restoration, rehab., creation
i. 🔲	Land Under Salt Ponds	1. square feet	
		2. cubic yards dredged	
i. 🗆	Land Containing Shellfish	1. square feet	
k. 🔲	Fish Runs		stal Banks, inland Bank, Land Under the and Under Waterbodies and Waterways,
		1. cubic yards dredged	
i. 🔲	Land Subject to Coastal Storm Flowage	1, square feet	
If the			wetland resource area in addition to the .3.h above, please enter the additional
a. squa	re feet of BVW	b. squa	re feet of Salt Marsh
☐ P	roject Involves Stream Cro	ssings	
a. numl	per of new stream crossings	b. num	ber of replacement stream crossings

4.

5.



Bureau of Resource Protection - Wetlands

WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

	MassDEP File Number
	Desument Transaction Number
	Document Transaction Number
	Arlington
ľ	City/Town

C. Other Applicable Standards and Requirements This is a proposal for an Ecological Restoration Limited Project. Skip Section C and complete Appendix A: Ecological Restoration Limited Project Checklists - Required Actions (310 CMR 10.11). Streamlined Massachusetts Endangered Species Act/Wetlands Protection Act Review 1. Is any portion of the proposed project located in Estimated Habitat of Rare Wildlife as indicated on the most recent Estimated Habitat Map of State-Listed Rare Wetland Wildlife published by the Natural Heritage and Endangered Species Program (NHESP)? To view habitat maps, see the Massachusetts Natural Heritage Atlas or go to http://maps.massgis.state.ma.us/PRI_EST_HAB/viewer.htm. If yes, include proof of mailing or hand delivery of NOI to: a. Yes No Natural Heritage and Endangered Species Program Division of Fisheries and Wildlife 1 Rabbit Hill Road 2017 Westborough, MA 01581 b. Date of map If yes, the project is also subject to Massachusetts Endangered Species Act (MESA) review (321 CMR 10.18). To qualify for a streamlined, 30-day, MESA/Wetlands Protection Act review, please complete Section C.1.c, and include requested materials with this Notice of Intent (NOI); OR complete Section C.2.f, if applicable. If MESA supplemental information is not included with the NOI, by completing Section 1 of this form, the NHESP will require a separate MESA filing which may take up to 90 days to review (unless noted exceptions in Section 2 apply, see below). c. Submit Supplemental Information for Endangered Species Review* Percentage/acreage of property to be altered: (a) within wetland Resource Area percentage/acreage (b) outside Resource Area percentage/acreage Assessor's Map or right-of-way plan of site Project plans for entire project site, including wetland resource areas and areas outside of wetlands jurisdiction, showing existing and proposed conditions, existing and proposed tree/vegetation clearing line, and clearly demarcated limits of work ** Project description (including description of impacts outside of wetland resource area & (a) buffer zone) Photographs representative of the site

MESA projects may not be segmented (321 CMR 10.16). The applicant must disclose full development plans even if such plans are streeting as part of the Notice of Intent process. not required as part of the Notice of Intent process. Page 5 of 9

wpaform3.doc • rev. 2/8/2018

Some projects not in Estimated Habitat may be located in Priority Habitat, and require NHESP review (see http://www.mass.gov/eea/agencies/dfg/dfw/natural-heritage/regulatory-review/). Priority Habitat includes habitat for state-listed plants and strictly upland species not protected by the Wetlands Protection Act.



Bureau of Resource Protection - Wetlands

WPA Form 3 – Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by	MassDEP:
-------------	----------

MassDEP File Number

Document Transaction Number Arlington

City/Town

C. Other Applicable Standards and Requirements (cont'd)

		check payable to "Commonwealth of Ma address	issachusetts - NHESP" ai	nd <i>mail to NHESP</i> at		
	Projects	s altering 10 or more acres of land, also su	bmit:			
	(d)	Vegetation cover type map of site				
	(e) 🗌	Project plans showing Priority & Estim	ated Habitat boundaries			
	(f) OF	R Check One of the Following				
	1, 🔲	Project is exempt from MESA review. Attach applicant letter indicating which http://www.mass.gov/dfwele/dfw/nhes the NOI must still be sent to NHESP if 310 CMR 10.37 and 10.59.)	p/regulatory review/mesa	a/mesa exemptions.htm;		
	2. 🔲	Separate MESA review ongoing.	a. NHESP Tracking #	b. Date submitted to NHESP		
	3, 🗌	Separate MESA review completed. Include copy of NHESP "no Take" det Permit with approved plan.	ermination or valid Conse	ervation & Management		
For coastal projects only, is any portion of the proposed pline or in a fish run?			posed project located belo	ow the mean high water		
	a. 🛛 Not a	applicable – project is in inland resource	e area only b. 🗌 Yes	□ No		
	If yes, inclu	f yes, include proof of mailing, hand delivery, or electronic delivery of NOI to either:				
	South Short the Cape &	e - Cohasset to Rhode Island border, and Islands:	North Shore - Hull to New	w Hampshire border:		
	Southeast M Attn: Enviro 836 South F New Bedfor	Marine Fisheries - Marine Fisheries Station Inmental Reviewer Rodney French Blvd. rd, MA 02744 F.EnvReview-South@state.ma.us	Division of Marine Fisher North Shore Office Attn: Environmental Rev 30 Emerson Avenue Gloucester, MA 01930 Email: <u>DMF.EnvRevie</u>			

Also if yes, the project may require a Chapter 91 license. For coastal towns in the Northeast Region, please contact MassDEP's Boston Office. For coastal towns in the Southeast Region, please contact MassDEP's Southeast Regional Office.



Online Users: Include your document transaction number

(provided on your receipt page) with all supplementary information you submit to the Department.

Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands

WPA Form 3 - Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided	by	MassDEP:
----------	----	----------

MassDEP File Number

Document Transaction Number Arlington City/Town

C. Other Applicable Standards and Requirements (cont'd)

4.	Is any portion of the proposed project within an Area of Critical Environmental Concern (ACEC)?				
	a. Yes No If yes, provide name of ACEC (see instructions to WPA Form 3 or MassDEP Website for ACEC locations). Note: electronic filers click on Website.				
	b. ACEC				
5.	Is any portion of the proposed project within an area designated as an Outstanding Resource Water (ORW) as designated in the Massachusetts Surface Water Quality Standards, 314 CMR 4.00?				
	a. 🗌 Yes 🗵 No.				
6.	Is any portion of the site subject to a Wetlands Restriction Order under the Inland Wetlands Restriction Act (M.G.L. c. 131, § 40A) or the Coastal Wetlands Restriction Act (M.G.L. c. 130, § 105)?				
	a. 🗌 Yes 🖂 No				
7.	Is this project subject to provisions of the MassDEP Stormwater Management Standards?				
	 Yes. Attach a copy of the Stormwater Report as required by the Stormwater Management. Standards per 310 CMR 10.05(6)(k)-(q) and check if: Applying for Low Impact Development (LID) site design credits (as described in Stormwater Management Handbook Vol. 2, Chapter 3) 				
	2. A portion of the site constitutes redevelopment				
	3. Proprietary BMPs are included in the Stormwater Management System.				
	b. No. Check why the project is exempt:				
	1. Single-family house				
	2. Emergency road repair				
	3. Small Residential Subdivision (less than or equal to 4 single-family houses or less than or equal to 4 units in multi-family housing project) with no discharge to Critical Areas.				
D.	Additional Information				
	This is a proposal for an Ecological Restoration Limited Project. Skip Section D and complete Appendix A: Ecological Restoration Notice of Intent – Minimum Required Documents (310 CMR 10.12).				
	Applicants must include the following with this Notice of Intent (NOI). See instructions for details.				
	Online Users: Attach the document transaction number (provided on your receipt page) for any of the following information you submit to the Department.				
	USGS or other map of the area (along with a narrative description, if necessary) containing sufficient information for the Conservation Commission and the Department to locate the site (Electronic filers may omit this item.)				

Plans identifying the location of proposed activities (including activities proposed to serve as

a Bordering Vegetated Wetland [BVW] replication area or other mitigating measure) relative

to the boundaries of each affected resource area.

2.



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands

WPA Form 3 - Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

	MassDEP File Number		
	Document Transaction Number		
1	Arlington		
	City/Town		

Additional Information (cont'd)

	3. Identify the method for BVW and other resource area boundary delineations (MassDEP B Field Data Form(s), Determination of Applicability, Order of Resource Area Delineation, early and attach documentation of the methodology.							
	4. 🛭	☐ List the titles and dates for all plans and other materials submitted with this NOI.						
		Arlington Reservoir Phase 2 a. Plan Title						
	Kyle Zick Landscape Architecture, Inc			Kyle Zick, RLA				
	b. Prepared By			c. Signed and Stamped by				
	September 25, 2020			varies				
	d. Final Revision Date Bank Restoration Plans, SWCA f. Additional Plan or Document Title			e, Scale	September 29, 2020 g. Date			
	5. If there is more than one property owner, please attach a list of these property owners relisted on this form.							
	6. Attach proof of mailing for Natural Heritage and Endangered Species Program			Program, if needed.				
	7. Attach proof of mailing for Massachusetts Division of Marine Fisheries, if needed.				s, if needed.			
	8. Attach NOI Wetland Fee Transmittal Form 9. Attach Stormwater Report, if needed.							
Ε.	Fe	Fees						
	1.	 Fee Exempt: No filing fee shall be assessed for projects of any city, town, county, or district of the Commonwealth, federally recognized Indian tribe housing authority, municipal housing authority, or the Massachusetts Bay Transportation Authority. 						
	Ap	Applicants must submit the following information (in addition to pages 1 and 2 of the NOI Wetland Fee Transmittal Form) to confirm fee payment.						
	2. Municipal Check Number		pal Check Number	3. Check date				

5. Check date

7. Payor name on check: Last Name

4. State Check Number

6. Payor name on check: First Name



Bureau of Resource Protection - Wetlands

WPA Form 3 - Notice of Intent

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:

MassDEP File Number

Document Transaction Number

Arlington City/Town

F. Signatures and Submittal Requirements

I hereby certify under the penalties of perjury that the foregoing Notice of Intent and accompanying plans, documents, and supporting data are true and complete to the best of my knowledge. I understand that the Conservation Commission will place notification of this Notice in a local newspaper at the expense of the applicant in accordance with the wetlands regulations, 310 CMR 10.05(5)(a).

I further certify under penalties of perjury that all abutters were notified of this application, pursuant to the requirements of M.G.L. c. 131, § 40. Notice must be made by Certificate of Mailing or in writing by hand delivery or certified mail (return receipt requested) to all abutters within 100 feet of the property line of the project location.

Anona Const	11/12/2020
1. Signature of Appliearit	2. Date
3. Signature of Property Owner (if different)	4. Date
Digitally signed by Mickey Marcus	
5. Mr. Curk (The State of the	6. Date
Date: 2020 11 12 14:02:10 -05'00'	

For Conservation Commission:

Two copies of the completed Notice of Intent (Form 3), including supporting plans and documents, two copies of the NOI Wetland Fee Transmittal Form, and the city/town fee payment, to the Conservation Commission by certified mail or hand delivery.

For MassDEP:

One copy of the completed Notice of Intent (Form 3), including supporting plans and documents, one copy of the NOI Wetland Fee Transmittal Form, and a **copy** of the state fee payment to the MassDEP Regional Office (see Instructions) by certified mail or hand delivery.

Other:

If the applicant has checked the "yes" box in any part of Section C, Item 3, above, refer to that section and the Instructions for additional submittal requirements.

The original and copies must be sent simultaneously. Failure by the applicant to send copies in a timely manner may result in dismissal of the Notice of Intent.

NOTICE OF INTENT N ARLINGTON RESERVOIR RENOVATION PROJECT-PHASE 2 ARLINGTON AND LEXINGTON, MASSACHUSETTS

Prepared for

Arlington Parks & Recreation Commission

422 Summer Street Arlington, MA 02474 Attn: Joseph Connelly, Director

SWCA Environmental Consultants

15 Research Drive Amherst, MA 01002 413-531-7156 www.swca.com

Kyle Zick Landscape Architecture, Inc.

36 Bromfield Street Boston, MA 02108 617-451-1018 www.kylezick.com

SWCA Project No. 60780

December 2020

CONTENTS

1	Introduction				
2	Site Descr	Site Description			
		land Resources			
		Land Under Waterbodies and Waterways			
	2.1.2	Inland Bank			
	2.1.3	Bordering Land Subject to Flooding	3		
	2.1.4	Buffer Zone/Erosion Control.			
	2.2 Othe	er Sensitive Resources	3		
	2.2.1	Natural Heritage and Endangered Species Review Program (NHESP)	3		
	2.2.2	Outstanding Resource Waters and Areas of Critical Environmental Concern	4		
3	Proposed Work				
	3.1 Project Description		4		
	3.1.1	Parking Area Improvements			
	3.1.2	Stormwater Management			
	3.1.3	Walking Path Improvements			
	3.1.4	Other Recreational Structures			
	3.1.5	Bank Stabilization			
	3.1.6	Upland Habitat Restoration/Invasive Species Removal	7		
	3.2 Proje	ect Impacts	8		
	3.3 Miti	gation Measures	8		
4	Regulator	y Review	9		
5	Summary				

Appendices

Appendix A. Abutter Information

Appendix B. Figures
Appendix C. Site Photographs

Appendix D. Project Plans

Appendix E Stormwater Report

1 INTRODUCTION

SWCA Environmental Consultants (SWCA) in conjunction with Kyle Zick Landscape Architecture (KZLA) and Woodard & Curran Engineering (W&C) have prepared this Notice of Intent (NOI) on behalf of the Town of Arlington Parks & Recreation Commission for the proposed Arlington Reservoir Renovation Project – Phase 2 (Project). The Project consists of the second phase of implementation of the Arlington Reservoir Master Plan and includes the following activities:

- parking area and stormwater improvements
- improvements to existing pathways to make them accessible under the Americans with Disabilities Act (ADA)
- renovation and adding new recreational facilities, including renovations of the existing bathhouse and concessions building, lifeguard stands, picnic tables, a playground, a multi-use court, boat launch, check-in shelter, and several other site improvements.
- bank stabilization measures along the reservoir shore; and
- upland habitat restoration / invasive species removal.

This project work is a continuation of the Phase I Master Plan for the Res completed in 2018 by the Town of Arlington and Weston & Sampson engineers.

This joint NOI is submitted to the Arlington and Lexington Conservation Commissions pursuant to the Massachusetts Wetland Protection Act (WPA) MGL c.131 §40 and its Regulations, 310 CMR 10.00, the Arlington Wetlands Protection Bylaw (Arlington Bylaw) and the Lexington Wetlands Protection Bylaw (Lexington Bylaw) for activities within jurisdictional wetland resource areas and buffer zones. A copy of the NOI has also been provided to the Massachusetts Department of Environmental Protection (MassDEP).

We are providing both the Towns of Arlington and Lexington with a full set of the site plans. Separate NOI forms have been prepared for each of the Towns.

2 SITE DESCRIPTION

The Arlington Reservoir (Res) is in the Arlington Heights neighborhood with Lowell Street on the eastern side of the property. Although all the Res and its shoreline are owned by the Town of Arlington, approximately half of the area is located within the Town of Lexington. The total area of the Res is approximately 65 acres. The 28 acre reservoir was created in 1871 for use as a water supply by damming Munroe Brook. The Res is no longer used as a water supply source. The Res currently offers the community with recreational opportunities for swimming, fishing, walking, non-motorized boating, and other outdoor pursuits. During the summer months, the Town of Arlington operates a chlorinated and filtered swim area, separated from the main body of the pond by an Embankment. Facilities at the bathing beach are proposed to be updated, and several of these facilities are within the 100 foot buffer zone.

There is a gravel parking area off Lowell Street which is the primary site access. A dam with two outlets for flood mitigation is maintained and is in good condition having been rebuilt in 2006. A nearly one mile long walking path encircles the Res. There has been an active program to control invasive aquatic vegetation within the open water, and this NOI does not overlap with these activities, except to provide a reinforced boat ramp to permit weed harvesters better access to the water.

1

The pond banks are heavily eroded due to a combination of natural wind/water erosion, but also due to fishing and pond edge access for recreation.

Munroe Brook enters the Res on the northwest in the Town of Lexington, and the outlet is to the south in Arlington via a dam at the confluence with Sickle Brook to form Mill Brook.

2.1 Wetland Resources

The Arlington and Lexington Conservation Commission have previously reviewed project work and wetlands at the Res. The Arlington Conservation Commission issued Orders of Conditions for file 091-0304 for work at the bathing beach and a test plot of the walking path, and the Lexington Conservation Commission issued Orders for this same project work under DEP File: 201-1117 on January 7, 2019. This NOI is a continuation of the previous project work, but since there is additional work in wetland Resource Areas (primarily for bank restoration and beach renovation) a new NOI is appropriate rather than to amend the previous Orders of Conditions. We will request that the open Orders for both Towns should be closed.

Given the heavy use of the Res by residents, we did not place flagging tape to show the top of the bank. These areas were surveyed and are shown on the site plan. There is no BVW proposed to be altered as part of this project. We describe invasive species control within the uplands, and a significant amount of this work will be within the 100 foot buffer of the Res. The Town of Arlington has determined not to remove any trees, even those which may be non-native; the invasive species control/removal will be herbaceous vegetation and shrubs.

2.1.1 Land Under Waterbodies and Waterways

The entire Res (approximately 28 acres) is LUW. The Town of Arlington has retained Solitude Lake Services to help manage the invasive aquatic vegetation (preliminary water chestnut), and this NOI does not propose work within LUW. The bank stabilization and restoration work proposed is within the Bank wetland resource area.

No work is proposed within any of the perennial or intermittent streams on the Res. Work for the walking path reconstruction and bank stabilization will be within the 200 foot Riverfront Area of Munroe Brook, but there is no new clearing or permanent alteration of habitat.

2.1.2 Inland Bank

Embankment. A stone berm separates the bathing beach from the main body of the Res and is located both in Arlington and Lexington (see site plans L1.1 and L1.2). The total area is approximately 12,520 square feet and is jurisdictional bank (10.54). This area is currently overgrown and vegetated with trees and shrubs and provides both an informal walking path as well as wildlife habitat. Although it is "bank", it is not deemed to provide important wildlife habitat (10.54 (4)(a)(5) due to the stone construction. It is proposed to clear this area of invasive vegetation (multiflora rose, autumn olive, bittersweet, purple loosestrife). Poison ivy on the embankment is also proposed to be removed. Work on the embankment is to provide better public access, including ADA compliant use. The trees are not proposed to be cut.

Pond Bank. Most of the banks of the Res are steep and eroded. This NOI proposes to repair all the eroded banks over time (see bank restoration figure). We have surveyed the edge of the Res and have shown a color-coded map of the erosion observed during the summer of 2020. The areas shown in red (Treatment A) shows heavily eroded areas with more than 12 inch high banks, with a vertical profile. The areas shown in Orange (Treatment B) are moderately eroded vertically banks less than 12 inches high.

2 40 of 479

The Yellow areas (Treatment C) are stable banks with little or no erosion, and no recommendations for stabilization, except for restoring vegetation along the bank and adjacent slopes. The Green areas (Treatment D) are stable banks with good vegetation cover, and no action or treatments are proposed, except for the removal of invasive species. We are recommending that four separate Treatment A areas should be the first phase of bank restoration. These are locations are shown on sheet 2 of the restoration site plans and include: 305 feet adjacent to the parking lot and boat launch; 270 feet along the outlet structure (used for fishing); 145 feet along an area of an eroded piped inlet; and 125 linear feet adjacent to the Munroe Brook inlet. These four eroded and unstable areas are the highest priority for the first phase of bank stabilization.

The proposed bank stabilization exceeds the 50 foot wildlife habitat threshold; however, the bank restoration may be permitted by the Conservation Commissions as the proposed work will not have an adverse effect on wildlife habitat in accordance with the procedures contained in 10.60. We are proposing all biodegradable materials and native plantings to reduce erosion, and enhance wildlife habitat features along the shoreline of the Res.

The proposed work extends from the lower boundary of Bank to the upper boundary of Bank. The lower boundary fluctuates based on the reservoir level but is typically 156.8 feet.

2.1.3 Bordering Land Subject to Flooding

The water level within the Res is controlled by the dam and two outlet control structures. No alteration of BLSF is proposed.

2.1.4 Buffer Zone/Erosion Control

Almost the entire Res property is within the 100 buffer zone to the banks of the Res, or inlet/outlet streams. There is significant new work proposed within the buffer zone, and sediment and erosion controls are proposed adjacent to all new work activities, include the bank restoration work.

Compost filled filter socks are proposed to be used in the upland areas adjacent to all site work to protect the Res from sedimentation. For the bank restoration we are proposing the use of a turbidity curtain to be placed between the edge of the work at the open water to protect the Res from site work and erosion during construction. Silt sacks will be installed in existing catch basins draining to the Res, and tree protection fencing will be used to separate and protect existing trees during construction activities. Site Plan LD1.1 shows the details of the proposed erosion controls.

2.2 Other Sensitive Resources

SWCA reviewed the Massachusetts Geographic Information System (MassGIS) to determine if the proposed project is within or near other sensitive environmental areas. These areas included protected rare species, important watersheds, and other special environmental characteristics. There are no known sensitive resources within the work area.

2.2.1 Natural Heritage and Endangered Species Review Program (NHESP)

SWCA reviewed the MassGIS database to determine if the project is located within or adjacent to areas designated as NHESP Priority Habitats of Rare Species, Estimated Habitats of Rare Wildlife, certified vernal pools (CVP), or potential vernal pools (PVP). No Priority Habitats, Estimated Habitats, CVPs or

3 41 of 479

PVPs are mapped by MassGIS in the area. No potentially certifiable vernal pools were noted during field investigations.

2.2.2 Outstanding Resource Waters and Areas of Critical Environmental Concern

SWCA reviewed the MassGIS database to determine if the site is located within Outstanding Resource Waters (ORWs) or Areas of Critical Environmental Concern (ACECs). ORWs are watershed areas that have been classified as such under the Massachusetts Surface Water Quality Standards and are areas that contain surface waters and their tributaries, including certain wetlands, that have been designated for protection based on their outstanding socio-economic, recreational, ecological and/or aesthetic values. These waters have been identified so that the quality of the waters may be protected and maintained. ACECs are areas designated in Massachusetts that receive special recognition because of the quality, uniqueness, and significance of its natural and/or and cultural resources. There are no ORWs or ACECs located within or adjacent to the proposed project area.

3 PROPOSED WORK

The goal of this project work by the Tow of Arlington is to improve the recreational opportunities of the entire Res property, and to improve the ecological health of the pond. The Town of Arlington has recognized that the stormwater management of the Res should be improved, and the sediment and nutrient loading into the Res could be improved by improvements to the existing parking areas, and shoreline. The following is a summary of the proposed work as outlined in the site plans.

3.1 Project Description

The Project consists of the second phase of implementation of the Arlington Reservoir Master Plan and includes the following activities:

- parking area improvements
- Stormwater upgrades
- improvements to existing pathways to make them accessible under the Americans with Disabilities Act (ADA)
- renovated or new recreational facilities, including renovations of the existing bathhouse and concessions building, lifeguard stands, picnic tables, a playground, a multi-use court, boat launch, check-in shelter, and several other surficial site improvements
- bank stabilization measures along the reservoir shore; and
- upland habitat restoration / invasive species removal.

Depending on permitting, and bidding, the construction activities are expected to begin in March 2021 and to be completed in November 2021. The Town anticipates that the bank restoration work will be completed as funding allows, starting with the most eroded locations as shown on the restoration site plans. Each of these activities are further described below.

3.1.1 Parking Area Improvements

The existing gravel parking area will be replaced with permeable concrete pavers, porous pavement, and concrete pavement. Accessible parking will be incorporated into the parking lot, and a concrete boat launch area will be established for non-motorized boats, and to ensure entry to the open water for the weed harvester used for aquatic species removal and control. Benches, a canoe storage rack, and revegetation plan are proposed within the redeveloped parking lot. Site plan L2.2 shows the details of the parking area.

The Arlington Parks & Recreation Commission proposes to install porous pavement over the approximately 0.5-acre gravel parking area in the southern portion of the site.

3.1.2 Stormwater Management

A stormwater management report in compliance with DEP stormwater regulations was prepared by Woodard & Curran and dated October 2020. The proposed design uses Low Impact Development designs as recommended in the Phase I Master Plan (2018) and with current DEP stormwater management recommendations. The project work will use porous pavement materials to replace a 0.5 acre gravel parking lot. The proposed stormwater measures also include the renovation of the existing bathhouse ad concessions building, the installation of new ADA accessible concrete pathways, the playground, boat launch, an athletic court, and several other surficial site improvements. The proposed work is a redevelopment project as there are no new development areas, only improvements of existing developed areas, and the improvement of stormwater management and water quality to the Res.

In accordance with the MA stormwater regulations, storm events from 1 year (2.67 inches) to the 100 year storm event (8.85 inches) were evaluated. The parking lot restoration includes a 21,500 square foot area of porous pavement, and the multi-purpose athletic court is also designed with permeable materials to maximize infiltration. In addition to the multi-layers of stone and gravel, the design has built in sufficient storage capacity to retain the 100 year storm event. Beyond this storm event, the drainage will discharge via three outlets to the Res.

The goal of the stormwater management is to improve the existing site conditions by infiltrating stormwater rather than having a direct overland flow into the Res. We anticipate immediate improvements to water quality in the Res by reducing the nutrient load and reducing the total suspended solids currently in the stormwater runoff.

The stormwater calculations (see page 9 of the stormwater report) shows a net decrease in the post development rate of runoff from the 1 year to the 100 year storm event, and full compliance with the DEP stormwater management standards. A copy of the DEP stormwater checklist is included at the end of the stormwater management report.

3.1.3 Walking Path Improvements

The existing walking path is composed of gravel and un-improved packed dirt and un-even surfaces. It is proposed to replace the existing trail with an 8 foot wide to 12 foot wide crushed granite path, with an alternate design using a rubber surfaced trail. The rebuilt trail will be installed around the circumference of the Res to replace the existing trail with a uniform and ADA compliant surface. The surface will be underlain by a crushed stone base. Plan Sheet LD1.2 provides the details of the walking path.

5 43 of 479

Additional paths which join other walkways will be re-built and made ADA compliant. All walking paths are within the 100 foot buffer zone to the Bank, and sediment and erosion controls are proposed (compost sock) adjacent to all work areas until the construction is completed and the site stabilized.

3.1.4 Other Recreational Structures

The proposed work will rebuild the bathing beach & recreational facilities to include a new playground, ADA compliant access, refreshing bathing beach sand, concession buildings, athletic court, pump house, and bathhouse. The existing buildings will be fully renovated. Sheets L1.1 shows the northern end of these facilities, and L1.2 shows the southern end of the facilities. There are additional structures proposed around the Res and these include benches, trash and recycling receptacles, a large hexagonal bench, a picnic pavilion, boulders, signage, and other similar features.

Almost all work is within the 100 foot buffer zone to the banks of the Res, and sediment and erosion controls (compost sock) is proposed to be installed between all work areas and the open water, including on either side of the embankment. These locations are shown on the site plan LD1.2 and LD1.3.

A new boat launch is proposed for recreational non-motorized boats. It is proposed using an articulating concrete block ramp (see Plan detail on Sheet LD1.3) which will allow the launching of the weed harvester used to collect water chestnut, and for aquatic plant management pond access. A canoe rack is proposed to be installed near the boat launch.

3.1.5 Bank Stabilization

As described in an earlier section, the banks of the Res have significant areas of erosion due to normal processes from wind and water, but also due to heavy use by recreational uses who want access to the open water. Design plans to use biodegradable coir (coconut fiber) are to be used against the vertically eroded banks, with the soil backfilled behind the logs. Details are provided on the restoration site plans Sheet 4.0. For the eroded bank sections with less than 12 inches of vertical erosion one 12 inch coir log installed against the bank face is proposed. Where the vertical erosion is greater than 12 inches high, a stacked arrangement of three coir logs will be used. The coir will be held in place with duck bill earth anchors and wire. This anchoring method will not use protruding stakes which may be a hazard to young children clamoring over the bank. Coir is not permanent and has a normal life span of approximately 5 years. The coir does provide a stable bank which allows the installed native vegetation to become established and allows the roots to help permanently stabilize the shoreline.

The following table shows the total bank restoration proposed in the NOI. The Town of Arlington will conduct this work in phases, and funding permits.

6

Table 1. Bank Restoration

Area	Type of Erosion	Total linear feet	Estimated Restoration Planting (square feet)
Area A	High erosion >12"	2,120	31,800
Area B	Moderate erosion <12"	1,650	24,750
Area C	Stable. Planting only	130	1,950
Area D	Stable. Planting only	680	10,200
Embankment	Stable		Invasive removal only

Native trees, shrubs and emergent plant species are proposed to be used in conjunction with the bank stabilization work. The total buffer zone habitat revegetation enhancement is 68,700 square feet. Restoration Plan Sheet 5.0 includes a list of the proposed revegetation planting plan to be implemented. We anticipate that the restoration of the bank and adjacent habitat will be restored over time, as funding permits. The restoration plantings will follow the bank stabilization and the invasive species removal as described below. A native seed mix has been specified to restore disturbed soils in the buffer zone and shady areas adjacent to the Res.

3.1.6 Upland Habitat Restoration/Invasive Species Removal

Revegetation. Landscape plantings have been incorporated into the design plans by KZLA and these areas are shown on the site plan drawings. Sheet L4.4 incorporates the restoration using trees and shrubs to be used to revegetate the different shoreline restoration areas. Sheet L4.2A provides the plant list to be incorporated in the bathing beach and parking lot areas which includes trees, shrubs, and groundcover plantings. The revitalization of the landscape is an important aspect of this project, and the goal is to establish new shade trees, and to provide a native and attractive landscape planting to replace the older landscaping and plants in poor condition.

Invasive Species Management. The invasive plant species identified at the project site by SWCA and KZLA included the following species: multiflora rose (*Rosa multiflora*); common buckthorn (*Rhamnus cathartica*); autumn olive (*Elaeagus umbellate*); Oriental bittersweet (*Celatrus orbiculatus*); Japanese Barberry; burning bush; Black Swallowort; Japanees Knotweed and purple loosestrife (*Lythrum salicaria*). Poison ivy (*Toxicodendron radicans*), although not a listed invasive species, was observed throughout the project site and will be managed due to its potential to cause harm to recreational users. Invasive trees such as Black Locust and Norway Maple are not proposed to be cut or managed. Invasive species management will be conducted to reduce or eradicate the invasive plant species identified within the project limits. Due to the varying levels of plant maturity and presence of both herbaceous and woody invasive species, various methods of management will be utilized to provide the most effective control.

Herbaceous species such as purple loosestrife and immature woody invasive species seedlings will be managed with a foliar herbicide application. Foliar treatments will be conducted by using a low-pressure backpack sprayer or handheld sprayer to apply an herbicide solution to the leaves of the target species. All

foliar management will be conducted as spot treatments where individual target plants are selected for treatment. Broadcast treatments are not proposed. Foliar applications require the use of a non-ionic surfactant to provide successful control. SWCA proposes the use of a non-ionic surfactant approved for use within wetland areas for this project. For all foliar applications, a 2% solution of Rodeo (glyphosate) or 2.56 ounces of herbicide per gallon of water will be applied with 1% or 1.33 ounces of the surfactant. Following successful control of herbaceous populations and other target plants, dead invasive species material will be removed and disposed of offsite.

Target invasive trees, shrubs, and vines encountered within the project limits will be managed with cutstem herbicide treatments. Cut-stem treatments will involve the use of hand tools (chainsaws, pruners, loppers, etc.) to cut the stem or vine followed by a spray or wipe application of herbicide solution to the exposed stem surface. All cuts will be made within 6-inches of the ground and the cut material will be removed and disposed of offsite. Invasive vines such as Oriental bittersweet encountered climbing on trees will be cut and removed to the greatest extent feasible. Special care will be taken to avoid damages to the native canopy during removal. Following cutting, a 50% solution of Rodeo or 64 ounces of herbicide per gallon of water will be applied to the freshly cut surface. The herbicide solution will be applied using a handheld sprayer or a brush/swab.

All invasive species management will be conducted during the summer months while the target plants are actively growing. Treatments should be conducted between July and August of each year and should be separated by at-least two weeks. Approximately two herbicide treatments should be scheduled per season for at-least two years following initiation of project work. As regulated by the label for the products, the applicator will not apply more than 8 quarts of Rodeo per acre, per year at the project site. A marking dye will be used to help the applicators identify the treated plant materials as they are working and to minimize overspray onto non-target species during the herbicide applications.

We anticipate that the control of invasive species at the Res will be a long-term endeavor and will require multiple years to bring the invasive species population under control. We will therefore request that the Arlington and Lexington Conservation Commission along the control of upland invasive species to be part of the O&M plan and to be a non-expiring Condition. We anticipate that year end reports by the Certified Applicator will be provided to the Conservation Commissions.

3.2 Project Impacts

There are short term impacts to Inland Bank during restoration, but no long-term alteration or filling. The proposed work is ecological restoration of a degraded wetland Resource Area. We anticipate the bank restoration work will be a long-term project to be completed over multiple years and will require continuing Conditions to allow the long-term maintenance of the restored bank and vegetation.

The total area of high and moderate bank erosion is 3,770 linear feet.

3.3 Mitigation Measures

In addition to the restoration of the Bank. We estimate the restoration of the upland buffer zone to be approximately 68,700 square feet. The restoration work is anticipated to be a long-term project at the Res and will be conducted over multiple years. We will request the Conservation Commissions to issue a non-expiring Order to permit the maintenance of the buffer zone vegetation that will include revegetation and the removal of invasive species.

8 46 of 479

4 REGULATORY REVIEW

The proximity of jurisdictional resources to the project work area at the Res falls under the regulation of the WPA and its implementing regulations, the Town of Arlington Wetlands Protection Bylaw, and the Town of Lexington Wetlands Protection Bylaw. We request coordination by both Towns to issue Orders of Conditions which contain the same language as the site contractors will be working in both Arlington and Lexington to implement the beach improvement project and restoration work.

5 SUMMARY

The proposed work plan is the implementation phase and follows the initial recommendations of Phase I of the Master Plan for the Res. There are significant site improvements proposed for the recreational use of the bathing beach and play areas. The gravel parking area is proposed to be rebuilt using permeable materials to infiltrate stormwater, and to improve the water quality of the Res. Reconstruction of the walking path around the Res, and numerous infrastructure features are proposed. The eroded bank segments along the shoreline are proposed to be restored and stabilized, and invasive species are proposed to be removed, and replaced with native species.

There are no wetland resource areas which will be lost. The work within resource areas is for restoration purposes and will result in improved stormwater management, improved wildlife habitat, and a decrease in nutrients and sediment entering the Res. This NOI does not include aquatic vegetation control within the Res. Work proposed is along the Bank and Buffer Zone.

We anticipate the major infrastructure project work at the Res will be completed within the next three years, but the ecological restoration work will likely be initiated over a longer time due to funding availability. For this reason, we request the Conservation Commissions to consider issuing a 5 year Order of Conditions to allow for continued bank and buffer zone restoration work. We are also requesting the Conservation Commissions to issue non-expiring Conditions for the maintenance of the restored infrastructure, stormwater management, bank restoration, and invasive species control.

9 47 of 479

APPENDIX A

Abutter Notification



Office of the Board of Assessors Robbins Memorial Town Hall Arlington, MA 02476 (781) 316-3050 Assessors@town.arlington.ma.us

Abutters List

Date: November 12, 2020

Subject Property Address: 0-LOT LOWELL ST Arlington, MA

Subject Property ID: 61-1-4

Search Distance: 100 Feet - Conservation

The Board of Assessors certifies the names and addresses of requested parties in interest, all abutters to a single parcel within 100 feet.

Please see enclosed map for any abutting property within 100 feet that is in another city or town.

Board of Assessors



Town Boundary
Parcels
Buildings
Cemetery - Roads
Road3
Road3
Road4
Pavement Markings

MA Highways Interstate

Open Space
Town, State, or Priva
Other Town Owned

Abutting Towns

US Highway Numbered Routes

Open Space: Conservation

Recreation - Fields Courts Recreation - Fields Courts

Open Space - Minuteman I Open Space - Labels

Impervious Surface - For B
Street
Sidewalk
Street Island
Driveway
Parking Lot
Bike Path
Bike Path

Roads - For Small Scale (for Major Road Local Road Master Plan Base Map - M

Places by Category
Police Station
Fire Station
School
Libray
Libray
Public Works
Recreation - Facilities

Abutters List

Date: November 12, 2020

Subject Property Address: 0-LOT LOWELL ST Arlington, MA

Subject Property ID: 61-1-4 Search Distance: 100 Feet

Prop ID: 61-1-3

Prop Location: 0-LOT MASS AVE Arlington, MA

Owner: TOWN OF ARLINGTON PARK

Co-Owner: Mailing Address: 730 MASS AVE

ARLINGTON, MA 02476

Prop ID: 61-1-4

Prop Location: 0-LOT MASS AVE Arlington, MA

Owner: TOWN OF ARLINGTON PARK

Co-Owner: Mailing Address: 730 MASS AVE

ARLINGTON, MA 02476

Prop ID: 61-1-5

Prop Location: 202 LOWELL ST Arlington, MA Owner: YOUNG DOUGLAS W & CATHRINE K

Co-Owner: Mailing Address: 202 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 61-1-6

Prop Location: 198 LOWELL ST Arlington, MA

Owner: SCHWARTZ ELIZABETH

Co-Owner: Mailing Address: 198 LOWELL ST

ARLINGTON, MA 02474

Prop ID: 61-1-7

Prop Location: 194 LOWELL ST Arlington, MA

Owner: BULL PETER
Co-Owner: DOIDGE THEA

Mailing Address: 194 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 61.A-10-1

Prop Location: 10 COLONIAL VILLAGE DR UNIT JI

Arlington, MA

Owner: VALLE ALISON Y

Co-Owner: Mailing Address:

10 COLONIAL VILLAGE DR #1 ARLINGTON, MA 02474

Prop ID: 61.A-10-10

Prop Location: 10 COLONIAL VILLAGE DR UNIT J10

Arlington, MA

Owner: SULLIVAN ROSEMARY T

Co-Owner: Mailing Address:

10 COLONIAL VILLAGE DR #10

ARLINGTON, MA 02474

Prop ID: 61.A-10-11

Prop Location: 10 COLONIAL VILLAGE DR UNIT J11

Arlington, MA

Owner: GILLIGAN BARBARA YEM- HANG/ TRS Co-Owner: BARBARA YEM-HANG GILLIGAN

Mailing Address:

10 COLONIAL VILLAGE DR #11

ARLINGTON, MA 02474

Prop ID: 61.A-10-12

Prop Location: 10 COLONIAL VILLAGE DR UNIT J12

Arlington, MA

Owner: BRASIL DEASSIS MORAES GUSTAVO

Co-Owner: SOARES CRISTIANE

Mailing Address:

10 COLONIAL VILLAGE DR #12

ARLINGTON, MA 02474

Prop ID: 61.A-10-2

Prop Location: 10 COLONIAL VILLAGE DR UNIT J2

Arlington, MA

Owner: IORDANIDIS ATHINA

Co-Owner: Mailing Address:

10 COLONIAL VILLAGE DR #2

ARLINGTON, MA 02474

Prop ID: 61.A-10-3

Prop Location: 10 COLONIAL VILLAGE DR UNIT J3

Arlington, MA

Owner: ROGERS BRUCE LEE

Co-Owner: LI JINYU Mailing Address: 107 PINE ST

WOBURN, MA 01801-3373

Prop ID: 61.A-10-4

Prop Location: 10 COLONIAL VILLAGE DR UNIT J4

Arlington, MA

Owner: VAN RHEENEN CONNIE

Co-Owner: Mailing Address:

38 BRADBURY STREET CAMBRIDGE, MA 02138

Prop ID: 61.A-10-5

Prop Location: 10 COLONIAL VILLAGE DR UNIT J5

Arlington, MA

Owner: ABUGOV GREGORY & VICTORIA

Co-Owner: Mailing Address: 16 ENDICOTT PL CANTON, MA 02021

Prop ID: 61.A-10-6

Prop Location: 10 COLONIAL VILLAGE DR UNIT J6

Arlington, MA

Owner: PINE DANIEL R

Co-Owner: Mailing Address: 51 STOWCROFT RD ARLINGTON, MA 02474

Prop ID: 61.A-10-7

Prop Location: 10 COLONIAL VILLAGE DR UNIT J7

Arlington, MA

Owner: HAN XIAOGANG & Co-Owner: DONG JENNIFER

Mailing Address: 508 LOWELL ST

LEXINGTON, MA 02420

Prop ID: 61.A-10-8

Prop Location: 10 COLONIAL VILLAGE DR UNIT J8

Arlington, MA

Owner: LIN ZHOUFANG

Co-Owner: Mailing Address:

10 COLONIAL VILLAGE DR #8 ARLINGTON, MA 02474

Prop ID: 61.A-10-9

Prop Location: 10 COLONIAL VILLAGE DR UNIT J9

Arlington, MA

Owner: CHAN MARY KAR-MI

Co-Owner: Mailing Address:

10 COLONIAL VILLAGE DR #9 ARLINGTON, MA 02474

Prop ID: 61.A-1-1

Prop Location: 1 COLONIAL VILLAGE DR UNIT A1

Arlington, MA

Owner: BAGWADIA ZUBIN ETAL TR Co-Owner: HOPE CYRUS BAGWADIA

Mailing Address: 87 OAK RIDGE TER LYNNFIELD, MA 01940

Prop ID: 61.A-1-10

Prop Location: 1 COLONIAL VILLAGE DR UNIT A10

Arlington, MA

Owner: ZHOU XIAOXIONG Co-Owner: A/K/A ZHOU FLORA

Mailing Address:

1 COLONIAL VILLAGE DR #10 ARLINGTON, MA 02474

Prop ID: 61.A-1-11

Prop Location: 1 COLONIAL VILLAGE DR UNIT A11

Arlington, MA

Owner: BARRY ELLEN J

Co-Owner: Mailing Address:

1 COLONIAL VILLAGE DR #11 ARLINGTON, MA 02474

Prop ID: 61.A-11-1

Prop Location: 11 COLONIAL VILLAGE DR UNIT K1

Arlington, MA

Owner: LOPEZ DAVID

Co-Owner: QUIROS LOURDES

Mailing Address: 146 OAKLAND ST MALDEN, MA 02148

Prop ID: 61.A-11-10

Prop Location: 11 COLONIAL VILLAGE DR UNIT K10

Arlington, MA

Owner: LOPEZ DAVID F

Co-Owner: Mailing Address: 146 OAKLAND ST MALDEN, MA 02148

Prop ID: 61.A-11-11

Prop Location: 11 COLONIAL VILLAGE DR UNIT K11

Arlington, MA

Owner: HIGGINS JAMES F

Co-Owner: Mailing Address:

4836 COMANCHE TRAIL PRESCOTT, AZ 86301

Prop ID: 61.A-11-12

Prop Location: 11 COLONIAL VILLAGE DR UNIT K12

Arlington, MA

Owner: WALKER KATHRYN R

Co-Owner: Mailing Address:

11 COLONIAL VILLAGE DR #12

ARLINGTON, MA 02474

Prop ID: 61.A-1-12

Prop Location: 1 COLONIAL VILLAGE DR UNIT A12

Arlington, MA

Owner: MA ZHOUYANG

Co-Owner: Mailing Address:

1 COLONIAL VILLAGE DR #12 ARLINGTON, MA 02474

Prop ID: 61.A-11-2

Prop Location: 11 COLONIAL VILLAGE DR UNIT K2

Arlington, MA

Owner: TIERNEY LAURA J TRUSTEE

Co-Owner: PIANTES SOUTH MIDDLESEX COUNTY

Mailing Address:

216 RANGEWAY RD UNIT 142 NORTH BILLERICA, MA 01862

Prop ID: 61.A-11-3

Prop Location: 11 COLONIAL VILLAGE DR UNIT K3

Arlington, MA

Owner: DIMILLA JULIE ELIZABETH

Co-Owner: Mailing Address:

11 COLONIAL VILLAGE DR #3

ARLINGTON, MA 02474

Prop ID: 61.A-11-4

Prop Location: 11 COLONIAL VILLAGE DR UNIT K4

Arlington, MA

Owner: TU WENHONG

Co-Owner: Mailing Address: 26 SADDLE CLUB RD LEXINGTON, MÅ 02420

Prop ID: 61.A-11-5

Prop Location: 11 COLONIAL VILLAGE DR UNIT K5

Arlington, MA

Owner: LOPEZ DAVID F

Co-Owner: Mailing Address: 146 OAKLAND ST MALDEN, MA 02148

Prop ID: 61.A-11-6

Prop Location: 11 COLONIAL VILLAGE DR UNIT K6

Arlington, MA

Owner: VAN MOORTEL MARJORIE

Co-Owner: Mailing Address:

11 COLONIAL VILLAGE DR #6

ARLINGTON, MA 02474

Prop ID: 61.A-11-7

Prop Location: 11 COLONIAL VILLAGE DR UNIT K7

Arlington, MA Owner: TU WENJIE

Co-Owner: Mailing Address:

11 COLONIAL VILLAGE DR #7

ARLINGTON, MA 02474

Prop ID: 61.A-11-8

Prop Location: 11 COLONIAL VILLAGE DR UNIT K8

Arlington, MA

Owner: BURKE CHARLES TR

Co-Owner: C/O HILARIE CHANDLER MGMT

Mailing Address: 19 DOONAN STREET TR OF S.R. REALTY TRUST MEDFORD, MA 02155

Prop ID: 61.A-11-9

Prop Location: 11 COLONIAL VILLAGE DR UNIT K9

Arlington, MA

Owner: VEZNAIAN MARY

Co-Owner: Mailing Address: 11 COLONIAL VILLAGE DR #9 ARLINGTON, MA 02474

Prop ID: 61.A-1-2

Prop Location: 1 COLONIAL VILLAGE DR UNIT A2

Arlington, MA

Owner: HERZBERG LORRIE

Co-Owner: Mailing Address: 1 COLONIAL VILLAGE DR #2 ARLINGTON, MA 02474 Prop ID: 61.A-12-1

Prop Location: 12 COLONIAL VILLAGE DR UNIT L1

Arlington, MA

Owner: SONAM TENZIN

Co-Owner: Mailing Address: 4 BRIDLE PATH SUDBURY, MA 01776

Prop ID: 61.A-12-10

Prop Location: 12 COLONIAL VILLAGE DR UNIT L10

Arlington, MA

Owner: SHARP JOHN D & KENNETH G/TRS

Co-Owner: 2019 CLIFFORD A SHARP

Mailing Address:

12 COLONIAL VILLAGE DR

UNIT 10

ARLINGTON, MA 02474

Prop ID: 61.A-12-11

Prop Location: 12 COLONIAL VILLAGE DR UNIT L11

Arlington, MA

Owner: MURPHY EDWARD

Co-Owner: Mailing Address:

12 COLONIAL VILLAGE DR UNIT 11

ARLINGTON, MA 02474

Prop ID: 61.A-12-12

Prop Location: 12 COLONIAL VILLAGE DR UNIT L12

Arlington, MA

Owner: BAI DONGFANG Co-Owner: FEI XINGYUAN

Mailing Address:

12 COLONIAL VILLAGE DR

APT 12

ARLINGTON, MA 02474

Prop ID: 61.A-12-2

Prop Location: 12 COLONIAL VILLAGE DR UNIT L2

Arlington, MA

Owner: LAZURE PETER B/ LIFE ESTATE

Co-Owner: Mailing Address:

12 COLONIAL VILLAGE DR

UNIT 2

ARLINGTON, MA 02474

Prop ID: 61.A-12-3

Prop Location: 12 COLONIAL VILLAGE DR UNIT L3

Arlington, MA

Owner: DAY STEVEN J

Co-Owner: Mailing Address:

12 COLONIAL VILLAGE DR #3

ARLINGTON, MA 02474

Prop ID: 61.A-12-4

Prop Location: 12 COLONIAL VILLAGE DR UNIT L4

Arlington, MA

Owner: JONES MARILYN J & RICHARD C/TRS

Co-Owner: JONES 2020 FAMILY TRUST

Mailing Address: 225 PHEASANT AVE ARLINGTON, MA 02474

Prop ID: 61.A-12-5

Prop Location: 12 COLONIAL VILLAGE DR UNIT L5

Arlington, MA

Owner: MORILLO-TAYLOR LILIANA

Co-Owner: Mailing Address: 2675 MONTROSE PL

SANTA BARBARA, CA 93105

Prop ID: 61.A-12-6

Prop Location: 12 COLONIAL VILLAGE DR UNIT L6

Arlington, MA

Owner: KUNWAR CHHABINDRA Co-Owner: KUNWAR SUSHMA

Mailing Address:

12 COLONIAL VILLAGE DR #6 ARLINGTON, MA 02474

Prop ID: 61.A-12-7

Prop Location: 12 COLONIAL VILLAGE DR UNIT L7

Arlington, MA

Owner: MISAWA TAKAKO

Co-Owner: Mailing Address:

12 COLONIAL VILLAGE DR #7 ARLINGTON, MA 02474

Prop ID: 61.A-12-8

Prop Location: 12 COLONIAL VILLAGE DR UNIT L8

Arlington, MA

Owner: PIRNIA SHAHRZAD

Co-Owner: Mailing Address: 21409 DAVIS MILL RD GERMANTOWN, MD 20876

Prop ID: 61.A-12-9

Prop Location: 12 COLONIAL VILLAGE DR UNIT L9

Arlington, MA

Owner: FERREIRA JOYCE P

Co-Owner:
Mailing Address:

12 COLONIAL VILLAGE DR #9

ARLINGTON, MA 02474

Prop ID: 61.A-1-3

Prop Location: 1 COLONIAL VILLAGE DR UNIT A3

Arlington, MA

Owner: FARINO CARLOS

Co-Owner: FARINO-VIDAL ZORAYDA

Mailing Address: 4 SYLVIA ST

LEXINGTON, MA 02421

Prop ID: 61.A-1-4

Prop Location: 1 COLONIAL VILLAGE DR UNIT A4

Arlington, MA Owner: HE JIANG

Co-Owner: YAO TIANQING

Mailing Address:

1 COLONIAL VILLAGE DR

#4

ARLINGTON, MA 02474

Prop ID: 61.A-1-5

Prop Location: 1 COLONIAL VILLAGE DR UNIT A5

Arlington, MA Owner: WU DAI Co-Owner: Mailing Address:

1 COLONIAL VILLAGE DR #5 ARLINGTON, MA 02474

Prop ID: 61.A-1-6

Prop Location: 1 COLONIAL VILLAGE DR UNIT A6

Arlington, MA

Owner: CARSER DIANE L

Co-Owner: Mailing Address:

1 COLONIAL VILLAGE DR #6 ARLINGTON, MA 02474

Prop ID: 61.A-1-7

Prop Location: 1 COLONIAL VILLAGE DR UNIT A7

Arlington, MA

Owner: ISMAYLOV DMITRIY

Co-Owner: Mailing Address: 48 SHADY HILL RD WESTON, MA 02493

Prop ID: 61.A-1-8

Prop Location: 1 COLONIAL VILLAGE DR UNIT A8

Arlington, MA

Owner: WANG PINGLANG & YING

Co-Owner: Mailing Address: 35 SKYLINE DR

STATEN ISLAND, NY 10304

Prop ID: 61.A-1-9

Prop Location: 1 COLONIAL VILLAGE DR UNIT A9

Arlington, MA

Owner: SABIO DARIO R & JOSEFINA B/TRS Co-Owner: SABIO FMLY REVOCABLE LIVING TR

Mailing Address: 10598 SANTERNO ST LAS VEGAS, NV 89141

Prop ID: 61.A-2-1

Prop Location: 2 COLONIAL VILLAGE DR UNIT B1

Arlington, MA

Owner: DONG JENNIFER Q Co-Owner: HAN XIAOGANG

Mailing Address: 508 LOWELL ST

LEXINGTON, MA 02420

Prop ID: 61.A-2-10

Prop Location: 2 COLONIAL VILLAGE DR UNIT B10

Arlington, MA

Owner: TAM THOMAS & Co-Owner: TAM WINNIE YIN

Mailing Address:

25 WINCHESTER DRIVE LEXINGTON, MA 02420

Prop ID: 61.A-2-11

Prop Location: 2 COLONIAL VILLAGE DR UNIT B11

Arlington, MA

Owner: RAMSAY RAYLENE L

Co-Owner: Mailing Address:

2 COLONIAL VILLAGE DR #11

ARLINGTON, MA 02474

Prop ID: 61.A-2-12

Prop Location: 2 COLONIAL VILLAGE DR UNIT B12

Arlington, MA

Owner: TANO YUKI NOBU

Co-Owner: Mailing Address:

2 COLONIAL VILLAGE DR #12

ARLINGTON, MA 02474

Prop ID: 61.A-2-2

Prop Location: 2 COLONIAL VILLAGE DR UNIT B2

Arlington, MA

Owner: SQUIRES PROPERTIES LLC

Co-Owner: Mailing Address:

344 BISHOPS FOREST DR WALTHAM, MA 02452

Prop ID: 61.A-2-3

Prop Location: 2 COLONIAL VILLAGE DR UNIT B3

Arlington, MA

Owner: BERGMAN BRUCE L

Co-Owner: Mailing Address:

2 COLONIAL VILLAGE DR #3 ARLINGTON, MA 02474

Prop ID: 61.A-2-4

Prop Location: 2 COLONIAL VILLAGE DR UNIT B4

Arlington, MA

Owner: LEDDY WILLIAM A

Co-Owner: Mailing Address:

2 COLONIAL VILLAGE DR #4 ARLINGTON, MA 02474

Prop ID: 61.A-2-5

Prop Location: 2 COLONIAL VILLAGE DR UNIT B5

Arlington, MA

Owner: ZHANG YUANYE Co-Owner: HAO XINMING

Mailing Address: 60 ALBEMARLE AVE LEXINGTON, MA 02420 Prop ID: 61.A-2-6

Prop Location: 2 COLONIAL VILLAGE DR UNIT B6

Arlington, MA

Owner: MORONEY KEVIN F & PAUL R/TRS Co-Owner: MORONEY FAMILY REALTY TRUST

Mailing Address:

2 COLONIAL VILLAGE DR #6 ARLINGTON, MA 02474

Prop ID: 61.A-2-7

Prop Location: 2 COLONIAL VILLAGE DR UNIT B7

Arlington, MA

Owner: QUAN SUSAN

Co-Owner: Mailing Address: 67 SLADE ST

BELMONT, MA 02478

Prop ID: 61.A-2-8

Prop Location: 2 COLONIAL VILLAGE DR UNIT B8

Arlington, MA

Owner: WANG ROBERT T & KATHY K/TRS

Co-Owner: WANG REALTY TRUST

Mailing Address: 402 HEATHER DR LYNNFIELD, MA 01940

Prop ID: 61.A-2-9

Prop Location: 2 COLONIAL VILLAGE DR UNIT B9

Arlington, MA

Owner: WANG LIANGYUN

Co-Owner: Mailing Address:

75 SAINT ALPHONSUS ST BOSTON, MA 02120

Prop ID: 61.A-3-1

Prop Location: 3 COLONIAL VILLAGE DR UNIT C1

Arlington, MA

Owner: COSTA MARIA C

Co-Owner: Mailing Address: 39 BENTON RD

SOMERVILLE, MA 02143

Prop ID: 61.A-3-10

Prop Location: 3 COLONIAL VILLAGE DR UNIT C10

Arlington, MA

Owner: CRONIN WILLIAM E JR

Co-Owner: Mailing Address: 327 LOWELL ST

LEXINGTON, MA 02420

Prop ID: 61.A-3-11

Prop Location: 3 COLONIAL VILLAGE DR UNIT C11

Arlington, MA

Owner: KINIRY JOHN J JR

Co-Owner: Mailing Address:

3 COLONIAL VILLAGE DR #11

ARLINGTON, MA 02474

Prop ID: 61.A-3-12

Prop Location: 3 COLONIAL VILLAGE DR UNIT C12

Arlington, MA

Owner: DITROIA ELIZABETH

Co-Owner: Mailing Address:

3 COLONIAL VILLAGE DR # 12

ARLINGTON, MA 02474

Prop ID: 61.A-3-2

Prop Location: 3 COLONIAL VILLAGE DR UNIT C2

Arlington, MA

Owner: BENNETT FREDERICK

Co-Owner: BENNETT YUAN WEI MARY

Mailing Address:

3 COLONIAL VILLAGE DR #2 ARLINGTON, MA 02474

Prop ID: 61.A-3-3

Prop Location: 3 COLONIAL VILLAGE DR UNIT C3

Arlington, MA

Owner: LEE RICHARD

Co-Owner: Mailing Address:

3 COLONIAL VILLAGE DR #3 ARLINGTON, MA 02474

Prop ID: 61.A-3-4

Prop Location: 3 COLONIAL VILLAGE DR UNIT C4

Arlington, MA

Owner: ARLINGTON COLONIAL LLC

Co-Owner: Mailing Address: 26 SADDLE CLUB RD LEXINGTON, MA 02420

Prop ID: 61.A-3-5

Prop Location: 3 COLONIAL VILLAGE DR UNIT C5

Arlington, MA

Owner: FENG DUANSI

Co-Owner: Mailing Address:

3 COLONIAL VILLAGE DR #5 ARLINGTON, MA 02474

Prop ID: 61.A-3-6

Prop Location: 3 COLONIAL VILLAGE DR UNIT C6

Arlington, MA

Owner: THAMES THOMAS L Co-Owner: THAMES ELLEN M

Mailing Address:

3 COLONIAL VILLAGE DR #6 ARLINGTON, MA 02474

Prop ID: 61.A-3-7

Prop Location: 3 COLONIAL VILLAGE DR UNIT C7

Arlington, MA

Owner: CAMERON MELANIE

Co-Owner: Mailing Address: 9 PRINCETON ROAD ARLINGTON, MA 02474 Prop ID: 61.A-3-8

Prop Location: 3 COLONIAL VILLAGE DR UNIT C8

Arlington, MA

Owner: WANG ROBERT T & KATHY K/TRS

Co-Owner: WANG REALTY TRUST

Mailing Address: 402 HEATHER RD LYNNFIELD, MA 01940

Prop ID: 61.A-3-9

Prop Location: 3 COLONIAL VILLAGE DR UNIT C9

Arlington, MA

Owner: LARSEN DAVID L

Co-Owner: Mailing Address:

14 WESTERN AVE UNIT 2 GLOUCESTER, MA 01930

Prop ID: 61.A-4-1

Prop Location: 4 COLONIAL VILLAGE DR UNIT D1

Arlington, MA

Owner: JUNG JONATHAN

Co-Owner: Mailing Address:

4 COLONIAL VILLAGE DR #1 ARLINGTON, MA 02474

Prop ID: 61.A-4-10

Prop Location: 4 COLONIAL VILLAGE DR UNIT D10

Arlington, MA

Owner: THOMPSON JOHN R & JUDITH

Co-Owner: Mailing Address: 20 CONNOLLY RD BILLERICA, MA 01821

Prop ID: 61.A-4-11

Prop Location: 4 COLONIAL VILLAGE DR UNIT D11

Arlington, MA

Owner: ONEIL EMILY

Co-Owner: Mailing Address:

4 COLONIAL VILLAGE DR #11 ARLINGTON, MA 02474

Prop ID: 61.A-4-12

Prop Location: 4 COLONIAL VILLAGE DR UNIT D12

Arlington, MA

Owner: COMMONWEALTH BOSTON REALTY LLC

Co-Owner: Mailing Address:

111 PERKINS STREET #192 JAMAICA PLAIN, MA 02130

Prop ID: 61.A-4-2

Prop Location: 4 COLONIAL VILLAGE DR UNIT D2

Arlington, MA

Owner: COLONIAL VILLAGE CONDOMINIUM

Co-Owner: TRUST Mailing Address:

C/O DEPT 368 FIRST REALTY MANAGEMENT COR

PO BOX 4579 HOUSTON, TX 77210-4579

Prop ID: 61.A-4-3

Prop Location: 4 COLONIAL VILLAGE DR UNIT D3

Arlington, MA

Owner: JOHNSON CARL R

Co-Owner: Mailing Address: 75 WILSON RD BEDFORD, MA 01730

Prop ID: 61.A-4-4

Prop Location: 4 COLONIAL VILLAGE DR UNIT D4

Arlington, MA

Owner: SHIEH TONY TUNG HSIEN

Co-Owner: CHAN WING CHI

Mailing Address: 50 CHANDLER RD BURLINGTON, MA 01803

Prop ID: 61.A-4-5

Prop Location: 4 COLONIAL VILLAGE DR UNIT D5

Arlington, MA

Owner: JENNINGS LAURIE/TRUSTEE

Co-Owner: SANDRA L FJELD 2017 IRREVOCABL

Mailing Address:

4 COLONIAL VILLAGE DR #5 ARLINGTON, MA 02474

Prop ID: 61.A-4-6

Prop Location: 4 COLONIAL VILLAGE DR UNIT D6

Arlington, MA

Owner: MANANDHAR ANILA

Co-Owner: Mailing Address: 2 ST MARY'S RD

BURLINGTON, MA 01803

Prop ID: 61.A-4-7

Prop Location: 4 COLONIAL VILLAGE DR UNIT D7

Arlington, MA

Owner: PHAM GIANG T M

Co-Owner: Mailing Address:

4 COLONIAL VILLAGE DR #7 ARLINGTON, MA 02474

Prop ID: 61.A-4-8

Prop Location: 4 COLONIAL VILLAGE DR UNIT D8

Arlington, MA
Owner: XIE CHAO
Co-Owner: YAN MINGLI
Mailing Address:
47 SOMERSET RD

LEXINGTON, MA 02420

Prop ID: 61.A-4-9

Prop Location: 4 COLONIAL VILLAGE DR UNIT D9

Arlington, MA

Owner: KIM MYUNG HEE

Co-Owner: Mailing Address:

131 COOLIDGE AVE UNIT 128 WATERTOWN, MA 02472-2847

Prop ID: 61.A-5-1

Prop Location: 5 COLONIAL VILLAGE DR UNIT E1

Arlington, MA

Owner: LEXINGTON REALTY HOLDINGS LLC

Co-Owner: Mailing Address: PO BOX 134

LEXINGTON, MA 02420

Prop ID: 61.A-5-10

Prop Location: 5 COLONIAL VILLAGE DR UNIT E10

Arlington, MA

Owner: OCALLAGHAN KELLY & Co-Owner: SCHNEIDER BRENDYN

Mailing Address:

5 COLONIAL VILLAGE DR #10 ARLINGTON, MA 02474

Prop ID: 61.A-5-11

Prop Location: 5 COLONIAL VILLAGE DR UNIT E11

Arlington, MA
Owner: CHENG HUI
Co-Owner: WANG HUI
Mailing Address:

5 COLONIAL VILLAGE DR #11

ARLINGTON, MA 02474

Prop ID: 61.A-5-12

Prop Location: 5 COLONIAL VILLAGE DR UNIT E12

Arlington, MA

Owner: HUANG GRACE

Co-Owner: Mailing Address:

5 COLONIAL VILLAGE DR #12 ARLINGTON, MA 02476

Prop ID: 61.A-5-2

Prop Location: 5 COLONIAL VILLAGE DR UNIT E2

Arlington, MA

Owner: COLARUSSO PROPERTIES LLC

Co-Owner: Mailing Address: 22 MILL ST SUITE 305 ARLINGTON, MA 02476

Prop ID: 61.A-5-3

Prop Location: 5 COLONIAL VILLAGE DR UNIT E3

Arlington, MA

Owner: SMITH IRENE H

Co-Owner: Mailing Address:

5 COLONIAL VILLAGE DR #3 ARLINGTON, MA 02474

Prop ID: 61.A-5-4

Prop Location: 5 COLONIAL VILLAGE DR UNIT E4

Arlington, MA

Owner: JAIN SUJIT G

Co-Owner: GOLECHA PRATIBHA S

Mailing Address:

30 APPLETON PL UNIT 2 ARLINGTON, MA 02476

Prop ID: 61.A-5-5

Prop Location: 5 COLONIAL VILLAGE DR UNIT E5

Arlington, MA

Owner: WU PHILIP C

Co-Owner: Mailing Address:

10 BROADWAY PL APT 3 SOMERVILLE, MA 02145

Prop ID: 61.A-5-6

Prop Location: 5 COLONIAL VILLAGE DR UNIT E6

Arlington, MA

Owner: GROSS GERALDINE R

Co-Owner: Mailing Address:

5 COLONIAL VILLAGE DR #6 ARLINGTON, MA 02474

Prop ID: 61.A-5-7

Prop Location: 5 COLONIAL VILLAGE DR UNIT E7

Arlington, MA

Owner: AHMARI SOHRAB

Co-Owner: Mailing Address:

5 COLONIAL VILLAGE DR #7 ARLINGTON, MA 02474

Prop ID: 61.A-5-8

Prop Location: 5 COLONIAL VILLAGE DR UNIT E8

Arlington, MA

Owner: MASKEY ANURAG Co-Owner: SHRESTHA SHACHI

Mailing Address: 47 WALLACE ST

NEWTON HIGHLANDS, MA 02461

Prop ID: 61.A-5-9

Prop Location: 5 COLONIAL VILLAGE DR UNIT E9

Arlington, MA

Owner: LAWSON MARTHA A

Co-Owner: Mailing Address: 70 MT VERNON ST HAVERHILL, MA 01830

Prop ID: 61.A-6-1

Prop Location: 6 COLONIAL VILLAGE DR UNIT F1

Arlington, MA

Owner: MENDEZ VICTOR F

Co-Owner: Mailing Address: 11 RICHARDSON RD STONEHAM, MA 02180

Prop ID: 61.A-6-10

Prop Location: 6 COLONIAL VILLAGE DR UNIT F10

Arlington, MA

Owner: WOLFE DANIEL P

Co-Owner: Mailing Address:

6 COLONIAL VILLAGE DR #10 ARLINGTON, MA 02474 Prop ID: 61.A-6-11

Prop Location: 6 COLONIAL VILLAGE DR UNIT F11

Arlington, MA

Owner: HARRIS JEFFREY M

Co-Owner: Mailing Address:

6 COLONIAL VILLAGE DR #11 ARLINGTON, MA 02474

Prop ID: 61.A-6-12

Prop Location: 6 COLONIAL VILLAGE DR UNIT F12

Arlington, MA

Owner: LEE FONG-CHANG Co-Owner: LEE SHIU-IN

Mailing Address: C/O JOSEPH LEE 1531 LUDINGTON AVE WESLEY CHAPEL, FL 33543

Prop ID: 61.A-6-2

Prop Location: 6 COLONIAL VILLAGE DR UNIT F2

Arlington, MA

Owner: CATALDI MAUREEN

Co-Owner: Mailing Address:

6 COLONIAL VILLAGE DR UNIT 2

ARLINGTON, MA 02474

Prop ID: 61.A-6-3

Prop Location: 6 COLONIAL VILLAGE DR UNIT F3

Arlington, MA

Owner: RANNEY ROGER ERIC

Co-Owner: Mailing Address:

6 COLONIAL VILLAGE DR #3 ARLINGTON, MA 02474

Prop ID: 61.A-6-4

Prop Location: 6 COLONIAL VILLAGE DR UNIT F4

Arlington, MA

Owner: MEI KATHY XIUWEN

Co-Owner: Mailing Address: 32 ARCOLA ST

LEXINGTON, MA 02420

Prop ID: 61.A-6-5

Prop Location: 6 COLONIAL VILLAGE DR UNIT F5

Arlington, MA

Owner: SHENG JIANXIONG & Co-Owner: LIU WENYING

Mailing Address:

6 COLONIAL VILLAGE DR #5 ARLINGTON, MA 02474

Prop ID: 61.A-6-6

Prop Location: 6 COLONIAL VILLAGE DR UNIT F6

Arlington, MA

Owner: BRIGHTMAN HELEN A ETAL/TRUSTEE Co-Owner: BRIGHTMAN NOMINEE REALTY TRUST

Mailing Address:

13 EDSON ST NASHUA, NH 03064

Prop ID: 61.A-6-7

Prop Location: 6 COLONIAL VILLAGE DR UNIT F7

Arlington, MA

Owner: MACAULEY LYNNE A

Co-Owner: Mailing Address:

6 COLONIAL VILLAGE DR #7 ARLINGTON, MA 02474

Prop ID: 61.A-6-8

Prop Location: 6 COLONIAL VILLAGE DR UNIT F8

Arlington, MA

Owner: ZHANG YANFANG Co-Owner: CUI JIKE Mailing Address: 78 MAPLE ST

BELMONT, MA 02478

Prop ID: 61.A-6-9

Prop Location: 6 COLONIAL VILLAGE DR UNIT F9

Arlington, MA

Owner: PERKINS ELLIOTT W & ANITA C Co-Owner: TRS/ PERKINS FAMILY TRUST

Mailing Address:

17 STEEPLE CHASE CIRCLE WESTFORD, MA 01886

Prop ID: 61.A-7-1

Prop Location: 7 COLONIAL VILLAGE DR UNIT G1

Arlington, MA

Owner: LAMB MARTHA

Co-Owner: Mailing Address:

7 COLONIAL VILLAGE DR #1 ARLINGTON, MA 02474

Prop ID: 61.A-7-10

Prop Location: 7 COLONIAL VILLAGE DR UNIT G10

Arlington, MA

Owner: GIOVINAZZO EMMA

Co-Owner: Mailing Address:

7 COLONIAL VILLAGE DR #10 ARLINGTON, MA 02474

TITELITO TOTA, MITTOZ TITA

Prop ID: 61.A-7-11

Prop Location: 7 COLONIAL VILLAGE DR UNIT G11

Arlington, MA

Owner: MUSE CAROLYN M & JAMES A

Co-Owner: Mailing Address: 1 PONDEROSA DR PELHAM, NH 03076

Prop ID: 61.A-7-12

Prop Location: 7 COLONIAL VILLAGE DR UNIT G12

Arlington, MA

Owner: AUSTIN ALEXANDER B

Co-Owner: Mailing Address:

7 COLONIAL VILLAGE DR #12 ARLINGTON, MA 02474

Prop ID: 61.A-7-2

Prop Location: 7 COLONIAL VILLAGE DR UNIT G2

Arlington, MA

Owner: JANTZ JOAN E

Co-Owner: Mailing Address:

7 COLONIAL VILLAGE DR #2 ARLINGTON, MA 02474

Prop ID: 61.A-7-3

Prop Location: 7 COLONIAL VILLAGE DR UNIT G3

Arlington, MA

Owner: FARRELL MICHAEL W Co-Owner: STEIN BRITTANY T

Mailing Address:

7 COLONIAL VILLAGE DR #3 ARLINGTON, MA 02474

Prop ID: 61.A-7-4

Prop Location: 7 COLONIAL VILLAGE DR UNIT G4

Arlington, MA

Owner: MAUGEL NATHAN/JENNIFER

Co-Owner: Mailing Address: 60 MUNROE DR

EAST HAMPSTEAD, NH 03826

Prop ID: 61.A-7-5

Prop Location: 7 COLONIAL VILLAGE DR UNIT G5

Arlington, MA

Owner: SHIU PLACID K

Co-Owner: Mailing Address: 19 GRANT PL

LEXINGTON, MA 02420

Prop ID: 61.A-7-6

Prop Location: 7 COLONIAL VILLAGE DR UNIT G6

Arlington, MA

Owner: MAHER DAVID F/TRUSTEE Co-Owner: 7 COLONIAL TRUST

Mailing Address: 966 BROADWAY

SOMERVILLE, MA 02144

Prop ID: 61.A-7-7

Prop Location: 7 COLONIAL VILLAGE DR UNIT G7

Arlington, MA

Owner: SIEGEL JULES

Co-Owner: Mailing Address:

1010 WALTHAM ST APT 295 LEXINGTON, MA 02421

Prop ID: 61.A-7-8

Prop Location: 7 COLONIAL VILLAGE DR UNIT G8

Arlington, MA

Owner: ZHANG ZHENZHEN &

Co-Owner: CHEN KUN Mailing Address: 58 CRESTVIEW RD

BELMONT, MA 02478

Prop ID: 61.A-7-9

Prop Location: 7 COLONIAL VILLAGE DR UNIT G9

Arlington, MA

Owner: SWARTS HEIDI

Co-Owner: Mailing Address:

7 COLONIAL VILLAGE DR #9 ARLINGTON, MA 02474

Prop ID: 61.A-8-1

Prop Location: 8 COLONIAL VILLAGE DR UNIT H1

Arlington, MA

Owner: LEXINGTON REALTY HOLDINGS LLC

Co-Owner: Mailing Address: PO BOX 134

LEXINGTON, MA 02420

Prop ID: 61.A-8-10

Prop Location: 8 COLONIAL VILLAGE DR UNIT H10

Arlington, MA

Owner: JONAS MICHAEL

Co-Owner: Mailing Address:

8 COLONIAL VILLAGE DR #10

ARLINGTON, MA 02476

Prop ID: 61.A-8-11

Prop Location: 8 COLONIAL VILLAGE DR UNIT H11

Arlington, MA

Owner: RAHMATPOUR SOHAILA--ETAL

Co-Owner: NAKHAEE HAMID

Mailing Address:

20 OVERBROOK DRIVE WELLESLEY, MA 02482

Prop ID: 61.A-8-12

Prop Location: 8 COLONIAL VILLAGE DR UNIT H12

Arlington, MA

Owner: MILLER CHERYL S

Co-Owner: Mailing Address:

8 COLONIAL VILLAGE DR #12

ARLINGTON, MA 02474

Prop ID: 61.A-8-2

Prop Location: 8 COLONIAL VILLAGE DR UNIT H2

Arlington, MA

Owner: KNIGHT WILL

Co-Owner: Mailing Address:

8 COLONIAL VILLAGE DR #2 ARLINGTON, MA 02474

Prop ID: 61.A-8-3

Prop Location: 8 COLONIAL VILLAGE DR UNIT H3

Arlington, MA

Owner: ELANBRI NOUREDDINE Co-Owner: AZMANI WAFA

Mailing Address:

8 COLONIAL VILLAGE DR #3 ARLINGTON, MA 02474 Prop ID: 61.A-8-4

Prop Location: 8 COLONIAL VILLAGE DR UNIT H4

Arlington, MA

Owner: NADJARIAN VATCHE

Co-Owner: Mailing Address:

8 COLONIAL VILLAGE DR

UNIT 4

ARLINGTON, MA 02474

Prop ID: 61.A-8-5

Prop Location: 8 COLONIAL VILLAGE DR UNIT H5

Arlington, MA

Owner: KING ALLISON J

Co-Owner: Mailing Address:

8 COLONIAL VILLAGE DR #5 ARLINGTON, MA 02474

Prop ID: 61.A-8-6

Prop Location: 8 COLONIAL VILLAGE DR UNIT H6

Arlington, MA

Owner: HUEY JEFFREY K

Co-Owner: Mailing Address:

8 COLONIAL VILLAGE DR APT 6

ARLINGTON, MA 02474

Prop ID: 61.A-8-7

Prop Location: 8 COLONIAL VILLAGE DR UNIT H7

Arlington, MA

Owner: SHEEHAN KEVIN/ANDREA

Co-Owner: Mailing Address: 228 FOX HILL RD

BURLINGTON, MA 01803

Prop ID: 61.A-8-8

Prop Location: 8 COLONIAL VILLAGE DR UNIT H8

Arlington, MA

Owner: RUSSO ANMARIE

Co-Owner: Mailing Address:

8 COLONIAL VILLAGE DR #8

ARLINGTON, MA 02474

Prop ID: 61.A-8-9

Prop Location: 8 COLONIAL VILLAGE DR UNIT H9

Arlington, MA Owner: LIU QING

Co-Owner: LI SHUANGLIAN

Mailing Address:

8 COLONIAL VILLAGE DR #9 ARLINGTON, MA 02474

Prop ID: 61.A-9-1

Prop Location: 9 COLONIAL VILLAGE DR UNIT I1

Arlington, MA

Owner: GOODWIN DESIREE

Co-Owner: Mailing Address:

9 COLONIAL VILLAGE DR #1

ARLINGTON, MA 02474

Prop ID: 61.A-9-10

Prop Location: 9 COLONIAL VILLAGE DR UNIT 110

Arlington, MA

Owner: PRESTON DIANE

Co-Owner: Mailing Address: 186 NEWPORT ST ARLINGTON, MA 02476

Prop ID: 61.A-9-11

Prop Location: 9 COLONIAL VILLAGE DR UNIT 111

Arlington, MA

Owner: VALDETTARO VERONIQUE A

Co-Owner: Mailing Address:

9 COLONIAL VILLAGE DR #11 ARLINGTON, MA 02474

Prop ID: 61.A-9-12

Prop Location: 9 COLONIAL VILLAGE DR UNIT 112

Arlington, MA

Owner: FLEMING ELLEN T

Co-Owner: Mailing Address:

9 COLONIAL VILLAGE DR #12 ARLINGTON, MA 02474

Prop ID: 61.A-9-2

Prop Location: 9 COLONIAL VILLAGE DR UNIT 2

Arlington, MA

Owner: NEWMARK GERRY G

Co-Owner: Mailing Address:

9 COLONIAL VILLAGE DR #2 ARLINGTON, MA 02474

Prop ID: 61.A-9-3

Prop Location: 9 COLONIAL VILLAGE DR UNIT 13

Arlington, MA

Owner: ELBANNAN SAMAA

Co-Owner: Mailing Address: 39 PINE HILL RD BEDFORD, MA 01730

Prop ID: 61.A-9-4

Prop Location: 9 COLONIAL VILLAGE DR UNIT 14

Arlington, MA

Owner: DONOVAN JOANNE

Co-Owner: Mailing Address:

9 COLONIAL VILLAGE DR #14

ARLINGTON, MA 02474

Prop ID: 61.A-9-5

Prop Location: 9 COLONIAL VILLAGE DR UNIT 15

Arlington, MA

Owner: LAI RALPH W M & CINDY S T

Co-Owner: Mailing Address: 28 CORNERSTO

28 CORNERSTONE CT DOYLESTOWN, PA 18901 Prop ID: 61.A-9-6

Prop Location: 9 COLONIAL VILLAGE DR UNIT 16

Arlington, MA

Owner: WANG PINGLANG & YING

Co-Owner: Mailing Address: 35 SKYLINE DR

STATEN ISLAND, NY 10304

Prop ID: 61.A-9-7

Prop Location: 9 COLONIAL VILLAGE DR UNIT 17

Arlington, MA

Owner: ZHANG YANFANG &

Co-Owner: CUI JIKE Mailing Address: 78 MAPLE ST

BELMONT, MA 02478

Prop ID: 61.A-9-8

Prop Location: 9 COLONIAL VILLAGE DR UNIT 18

Arlington, MA

Owner: SHINGU IKUE

Co-Owner: Mailing Address:

9 COLONIAL VILLAGE DR #8 ARLINGTON, MA 02474

Prop ID: 61.A-9-9

Prop Location: 9 COLONIAL VILLAGE DR UNIT 19

Arlington, MA

Owner: MAC INNES PATRICIA

Co-Owner: Mailing Address: 32 ST CATHERINE RD NORWOOD, MA 02062

Prop ID: 62-1-4.A

Prop Location: 16-38 DRAKE RD Arlington, MA Owner: ARLINGTON HOUSING AUTHORITY

Co-Owner: DRAKE VILLAGE

Mailing Address: 730 MASS AVE

ARLINGTON, MA 02476

Prop ID: 85-1-7

Prop Location: 4 WESTMORELAND AVE Arlington, MA

Owner: CALLAGHAN OWEN & JESSICA

Co-Owner: Mailing Address:

4 WESTMORELAND AVE ARLINGTON, MA 02474

Prop ID: 85-1-8

Prop Location: 239 LOWELL ST Arlington, MA

Owner: VERDERESE JOHN T

Co-Owner: Mailing Address:

239 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 85-1-9

Prop Location: 243 LOWELL ST Arlington, MA

Owner: WYATT PATRICIA L

Co-Owner: Mailing Address: 243 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 85-4-14

Prop Location: 3 WESTMORELAND AVE Arlington, MA

Owner: ENG DAVID H

Co-Owner: CANTY ANDREA M

Mailing Address:

3 WESTMORELAND AVE ARLINGTON, MA 02474

Prop ID: 85-4-15

Prop Location: 221 LOWELL ST Arlington, MA Owner: LAMONT STUART & BARBARA

Co-Owner: Mailing Address: 221 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 85-4-16

Prop Location: 219 LOWELL ST Arlington, MA

Owner: SMITH ROBERT G & JANE R

Co-Owner: Mailing Address: 219 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 85-4-21

Prop Location: 7 WEST COURT TERR Arlington, MA

Owner: STROK GAVIN M

Co-Owner: STROK MARIE-CAROLINE

Mailing Address: 7 WEST COURT TERR ARLINGTON, MA 02474

Prop ID: 85-4-22

Prop Location: 207 LOWELL ST Arlington, MA

Owner: MARTENS CHINA L

Co-Owner: MARTENS SIEGFRIED

Mailing Address: 207 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 85-4-23

Prop Location: 203 LOWELL ST Arlington, MA

Owner: SALOCKS JEFFREY D--ETAL Co-Owner: STAFFORD SHARON L

Mailing Address: 203 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 85-4-26

Prop Location: 197 LOWELL ST Arlington, MA Owner: GETTLER JUSTIN B & HOLLY K

Co-Owner: Mailing Address: 197 LOWELL ST ARLINGTON, MA 02474 Prop ID: 86-5-10.A

Prop Location: 255 LOWELL ST Arlington, MA

Owner: GALVIN ANNE M

Co-Owner: Mailing Address: 255 LOWELL ST

ARLINGTON, MA 02474

Prop ID: 86-5-10.B

Prop Location: 0-LOT LOWELL ST Arlington, MA

Owner: PLANT SUSAN W Co-Owner: CHO DANYUL Y

Mailing Address: 257 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 86-5-11

Prop Location: 257 LOWELL ST Arlington, MA

Owner: PLANT SUSAN W Co-Owner: CHO DANYUL Y

Mailing Address: 257 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 86-5-12

Prop Location: 261 LOWELL ST Arlington, MA

Owner: SOUCY PAUL EDWARD Co-Owner: SILVERMAN MELANIE TIA

Mailing Address: 261 LOWELL STREET ARLINGTON, MA 02474

Prop ID: 86-5-13

Prop Location: 265 LOWELL ST Arlington, MA Owner: CHARLIER-MATTHEWS REBECCA Co-Owner: KOSMATKA KRISTOPHER

Mailing Address: 265 LOWELL ST

ARLINGTON, MA 02474

Prop ID: 86-5-14

Prop Location: 269 LOWELL ST Arlington, MA

Owner: CANADAY JOHN T

Co-Owner: Mailing Address: 269 LOWELL ST

ARLINGTON, MA 02474

Prop ID: 86-5-15

Prop Location: 271 LOWELL ST Arlington, MA

Owner: GEISSLER GARY J

Co-Owner: Mailing Address: 1 LOWELL STREET LEXINGTON, MA 02420

Prop ID: 86-5-9

Prop Location: 251 LOWELL ST Arlington, MA

Owner: ALLEN THOMAS J & Co-Owner: SENESE MARGARET D

Mailing Address:

251 LOWELL STREET ARLINGTON, MA 02474

Notification to Abutters Under the Massachusetts Wetlands Protection Act and Arlington Wetlands Protection Bylaw

In accordance with the second paragraph of Massachusetts General Laws Chapter 131, Section 40, and the Arlington Wetlands Protection Bylaw, you are hereby notified of the following:

The Conservation Commission will hold a public hearing on Thursday, December 17, 2020 at 7:30pm in accordance with the provisions of the Mass. Wetlands Protection Act (M.G.L. Ch. 131, s. 40, as amended) and the Town of Arlington By-Laws Article 8, By-Law for Wetland Protection, for a Notice of Intent from the Town of Arlington Parks & Recreation Commission, for the Arlington Reservoir Renovation Project Phase II, which includes parking area improvements, installation of new ADA-accessible pathways, new recreational facilities, a boat launch, bathing beach improvements, bank stabilization measures, and invasive species control / upland habitat restoration at the Arlington Reservoir, within regulated wetland resource areas and buffer zones, on Assessor's Property Map/Lot 61-1-4 in Arlington. *Due to COVID-19, please refer to the town website for information on the location of the meeting or virtual (Zoom) meeting information. Conservation Commission agendas are posted on their website at least 48 hours in advance at: https://www.arlingtonma.gov/town-governance/boards-and-committees/conservation-commission.*

A copy of the application and accompanying plans are available for inspection Mon. - Fri. 8am-noon at the Conservation Commission office, first floor of the Town Hall Annex, 730 Massachusetts Avenue and by request via email at Rebecca.weissman@swca.com. (Please note that the town hall may be closed or office hours reduced due to COVID-19 concerns).

For more information call the Town of Arlington Parks and Recreation Commission at 781-316-3880 or the Arlington Conservation Commission at 781-316-3012, or the DEP Northeast Regional Office, 978-694-3200.

NOTE: Notice of the Public Hearing will be published at least five (5) days in advance in *The Arlington Advocate* and be posted not less than 48 hours in advance in the Arlington Town Hall of the public hearing.

AFFIDAVIT OF SERVICE

(Return to Conservation Commission)

I, Becky Barber, being duly sworn, do hereby state as follows: on December 3, 2020, I mailed a "Notification to Abutters" in compliance with the second paragraph of Massachusetts General Laws, Chapter 131, s.40, the DEP Guide to Abutter Notification dated April 8, 1994, and the Arlington Wetlands Protection Bylaw, Title V, Article 8 of the Town of Arlington Bylaws in connection with the following matter: A Notice of Intent

The form of the notification, and a list of the abutters to whom it was provided and their addresses, are attached to this Affidavit of Service. Signed under the pains and penalties of perjury, this 3rd day of December, 2020.

Name

Becky Barber

APPENDIX B

Figures





APPENDIX C

Site Photographs

All photographs taken July 17, 2020

Photo 1: Bathing Beach



Photo 2. Swim Area with Embankment on left.



Photo 3. Embankment. The surface is proposed to be improved for walking, and invasive species, including poison ivy to be removed.



All photographs taken July 17, 2020

Photo 4: Existing gravel parking lot. It is proposed to rebuild the parking lot with permeable materials to improve water quality in the Res.



Photo 5. Bank and slope erosion from parking lot overland runoff. The banks are proposed to be restored, and the stormwater will be infiltrated.



Photo 6. Typical bank and slope erosion along the Res. These areas are proposed to be restored and re-vegetated.



All photographs taken July 17, 2020

Photo 7: Existing Walking Path in Arlington proposed to be rebuilt and the adjacent bank/slopes restored.



Photo 8. Existing walking path in Lexington. Vegetation is dominated by invasive species proposed to be controlled.



Photo 9. Areas of significant bank erosion are proposed to be restored in the first phase of site work (west side of Res near Rindge Park).



APPENDIX D

Project Plans (Under Separate Cover)

A-1 72 of 479

APPENDIX E

Stormwater Report (Under Separate Cover)

A-1 73 of 479

TOWN OF ARLINGTON

ARLINGTON RESERVOIR - PHASE 2

ARLINGTON, MASSACHUSETTS

100% DESIGN DEVELOPMENT SET

DRAWING LIST

COVER SHEET KEY PLAN SITE PREPARATION AND DEMO PLANS L2.1 - L2.5 LAYOUT AND MATERIAL PLANS L3.1 - L3.5 GRADING PLANS L4.1 - L4.5PLANTING PLANS LANDSCAPE DETAILS CIVIL DRAINAGE PLAN CIVIL DETAIL SHEETS PROPOSED BANK RESTORATION AREAS PROPOSED AREAS OF PHASE1 BANK RESTORATION BANK RESTORATION SECTIONS BANK RESTORATION DETAILS

BANK RESTORATION DETAILS AND NOTES

PREPARED BY:

LANDSCAPE ARCHITECT:

Kyle Zick Landscape Architecture, Inc.

36 Bromfield Street, Suite 202

Boston, MA 02108 617-451-1018 Tel www. kylezick.com

ARCHITECT:

Bargmann Hendrie + Archetype, Inc.

9 Channel Center Street #300, Boston, MA 02210 617-350-0450 Tel 617-350-0215 Fax

CIVIL ENGINEER:


Woodard & Curran, Inc.

980 Washington Street #325, Dedham, MA 02026 800-446-5518 Tel

ENVIRONMENTAL CONSULTING:

SWCA Environmental Consultants

15 Research Drive, Amherst, MA 01002 413-575-9883 Tel



Arlington, MA

ARLINGTON RESERVOIR -PHASE 2

ARLINGTON, MASSACHUSETTS

TOWN OF ARLINGTON

NO. REVISION DATE

kzla

Kyle Zick Landscape Architecture, Inc.
36 Bromfield Street Suite 202 617 451
Boston, MA 02108 www.ky



100% DESIGN DEVELOPMENT SET

Job Numbe

Project: ARLINGTON RE

Drawn By: JL/MD/RB CI

Date: NOVEMBER 13, 2020

Contact NI/A


Drawing Title:


•

COVER SHEET

G

74 of 479





GENERAL NOTES:

- CONTRACTOR SHALL BE FAMILIAR WITH DRAWINGS AND SPECIFICATIONS BEFORE BIDDING
 DRAWINGS SHALL SUPERSEDE SPECIFICATIONS FOR ANY
- 3. CONTRACTOR SHALL CONFORM TO ALL FEDERAL, STATE AND LOCAL CODES, INCLUDING CMR521/ADA.
- 4. NO SMOKING IS ALLOWED WITHIN THE PARK AT ANY TIME 5. SURVEY WAS PERFORMED BY WESTON & SAMPSON
- ENGINEERS, INC. OF ALBANY, NY WAS UNDERTAKEN IN DECEMBER 2017
- 6. PER THE STORMWATER POLLUTION PREVENTION PLAN (DATED 11/9/2020), THE CONTRACTOR CAN NOT DISTURB MORE THAN 5 ACRES AT ANY GIVEN TIME.

<u>LEGEND</u>


----- APPROXIMATE TOP OF BANK

----- 200' RIVERFRONT AREA

ARLINGTON RESERVOIR -PHASE 2

ARLINGTON, MASSACHUSETTS

TOWN OF ARLINGTON





Kyle Zick Landscape Architecture, Inc. 36 Bromfield Street Suite 202 617 451-1018 Tel Boston, MA 02108 www.kylezick.com





100% DESIGN DEVELOPMENT SET


Job Number:	
Project: ARLINGTON RES.	
Drawn By: JL/MD/RB	Checked By: KZ
Date: NOVEMBER 13, 202	0
Scale: AS SHOWN	
Drawing Title:	


KEY PLAN


L0







































































UNDISTURBED


SCALE: 1 1/2" = 1'-0"


SUBGRADE

FLUSH GRANITE CURB CONDITION

UNDISTURBED

SUBGRADE






100% DESIGN DEVELOPMENT SET Job Number: Project: ARLINGTON RES. Drawn By: JL/MD/RB Checked By: KZ Date: NOVEMBER 13, 2020 Scale: AS SHOWN Drawing Title: **DETAILS** LD1.1

REVISION

DATE


617 451-1018 Tel

www.kylezick.com



PERMEABLE ATHLETIC COURT SURFACING


SCALE: $1 \frac{1}{2} = 1'-0"$



- 1. TO PREVENT INJURY TO CRITICAL ROOT ZONES OF ADJACENT TREES, SOIL IS TO BE EXCAVATED NON—INVASIVELY A MINIMUM OF 6 INCHES USING SUPERSONIC AIR KNIFE. FABRIC AND STONE ARE TO BE INSTALLED OVER AND AROUND ROOTS. SUBGRADE SHALL BE COMPACTED TO THE GREATEST EXTENT POSSIBLE. ROOT PRUNING MAY BE PERFORMED BY ARBORIST AS NEEDED ON SELECTED ROOTS LESS THAN 2 INCHES IN DIAMETER PROVIDED NO MORE THAN 15% OF THE CRITICAL ROOT ZONE IS REMOVED.
- 2. WHEREVER POSSIBLE, AND WITHOUT INJURING CRITICAL ROOT ZONES OF ADJACENT TREES. CRUSHED STONE BASE SHALL RUN 6 INCHES BEYOND THE END OF THE FLEXIBLE POROUS PAVING. AT LEAST 2" OF STONE SHALL COVER THE TOP OF ROOTS BEFORE FLEXIBLE POROUS MATERIAL IS LAID.

 3. WALKWAY SHALL MAINTAIN A CROSS RITCH OF NOT MORE THAN ONE AND A HALE (1.5%) REPOENT ANY DISCREPANCY NOT ALLOWING THIS TO OCCUP SHALL RE
- 3. WALKWAY SHALL MAINTAIN A CROSS PITCH OF NOT MORE THAN ONE AND A HALF (1.5%) PERCENT. ANY DISCREPANCY NOT ALLOWING THIS TO OCCUR SHALL BE REPORTED TO LANDSCAPE ARCHITECT PRIOR TO CONTINUING WORK.


RUBBER SURFACING - TRAIL (ADD ALTERNATE)





- 1. TO PREVENT INJURY TO CRITICAL ROOT ZONES OF ADJACENT TREES, SOIL IS TO BE EXCAVATED NON—INVASIVELY A MINIMUM OF 6 INCHES USING SUPERSONIC AIR KNIFE. FABRIC AND STONE ARE TO BE INSTALLED OVER AND AROUND ROOTS. SUBGRADE SHALL BE COMPACTED TO THE GREATEST EXTENT POSSIBLE. ROOT PRUNING MAY BE PERFORMED BY ARBORIST AS NEEDED ON SELECTED ROOTS LESS THAN 2 INCHES IN DIAMETER PROVIDED NO MORE THAN 15% OF THE CRITICAL ROOT ZONE IS REMOVED.
- 2. WHEREVER POSSIBLE, AND WITHOUT INJURING CRITICAL ROOT ZONES OF ADJACENT TREES. CRUSHED STONE BASE SHALL RUN 6 INCHES BEYOND THE END OF THE STONEDUST PAVING. AT LEAST 2" OF STONE SHALL COVER THE TOP OF ROOTS BEFORE STONEDUST IS LAID.
- 3. WALKWAY SHALL MAINTAIN A CROSS PITCH OF NOT MORE THAN ONE AND A HALF (1.5%) PERCENT. ANY DISCREPANCY NOT ALLOWING THIS TO OCCUR SHALL BE REPORTED TO LANDSCAPE ARCHITECT PRIOR TO CONTINUING WORK.


STABILIZED CRUSHED GRANITE PAVEMENT OVER TREE ROOTS


SCALE: 1" = 1'-0"














ARLINGTON RESERVOIR -PHASE 2 ARLINGTON, MASSACHUSETTS TOWN OF ARLINGTON

NO. REVISION DATE

kzla Kyle Zick Landscape Architecture, Inc. 36 Bromfield Street Suite 202 617 451-1018 Tel

www.kylezick.com

100% DESIGN DEVELOPMENT SET

Project: ARLINGTON RES. Drawn By: JL/MD/RB Checked By: KZ Date: NOVEMBER 13, 2020


Scale: AS SHOWN


Job Number:

Drawing Title:


DETAILS


LD1.6







106 of 479





















ARLINGTON, MASSACHUSETTS

TOWN OF ARLINGTON



kzla

Kyle Zick Landscape Architecture, Inc.
36 Bromfield Street Suite 202 617 451-1018 Tel
Boston, MA 02108 www.kylezick.com



100% DESIGN DEVELOPMENT SET

Job Number:

Project: ARLINGTON RES.

Drawn By: JL/MD/RB Checked By: KZ


Date: NOVEMBER 13, 2020


Scale: AS SHOWN


Drawing Title:


DETAILS


LD1.9














Scale: NTS





Scale: NTS



ARLINGTON

NO. REVISION DATE

SWCA ENVIRONMENTAL CONSULTANTS

15 RESEARCH DRIVE AMHERST, MA 01002 (P) 413.256.0202 WWW.SWCA.COM

Kyle Zick Landscape Architecture, Inc. 36 Bromfield Street Suite 202 617 451-1018 Tel Boston, MA 02108 www.kylezick.com


DESIGN DEVELOPMENT SET

Job Number: Project: ARLINGTON RES. Checked By: MM Drawn By: TS Date: SEPTEMBER 29, 2020

Drawing Title:


BANK RESTORATION SECTIONS

3.0



NOTE: TURBIDITY CURTAIN TO BE TEMPORARILY INSTALLED SURROUNDING ANY BANK OR BOAT RAMP WORK WHICH WILL DISTURB SOILS NEXT TO OPEN WATER. ONCE SUSPENDED SEDIMENT HAS CLEARED, THE TURBIDITY CURTAIN MAY BE REMOVED.

TURBIDITY CURTAIN DETAIL FOR IN-WATER SEDIMENT CONTROL (TYP.)



COIR LOG INSTALLATION (TYP.) Scale: NTS

PROTECTED RESOURCE AREA

UNDISTURBED SOIL

BIODEGRADABLE MATERIAL

2"X2"X3' WOOD STAKES, EVERY

AREA OF DISTURBANCE -


5' O.C. PER STRAW WATTLE

SET 3" BELOW GRADE


Scale: NTS

STRAW WATTLE EROSION CONTROL


STRAW WATTLES TO BE



COIR FASCINE INSTALLATION (TYP.) Scale: NTS




EMERGENT SHELF (TYP.) Scale: NTS




BIODEGRADABLE EROSION CONTROL FABRIC SLOPE STABILIZATION DETAIL Scale: NTS

EROSION CONTROL FABRIC NOTES: SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS TO ENSURE THAT THE EROSION CONTROL FABRIC WILL HAVE GOOD SOIL CONTACT.

- 2. APPLY PERMANENT SEEDING BEFORE PLACING EROSION CONTROL FABRIC.
- LAY FABRIC LOOSELY AND STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.
- 4. STAPLE FABRIC WITH 6" STAPLES. STAPLE FABRIC EVERY 12" ON SIDES, TOP AND BOTTOM. 18" O.C. IN THE MIDDLE OF THE FABRIC. (PER MANUFACTURES SPECIFICATIONS)
- 5. THE EROSION CONTROL FABRIC TO BE INSTALLED IN SECTIONS RUNNING FROM THE TOP TO THE BOTTOM OF THE SLOPE, ALONG THE ENTIRE AREAS AS SHOWN ON THE PLAN (PER MANUFACTURES SPECIFICATIONS)
- 6. EROSION CONTROL FABRIC SHALL USE BIODEGRADABLE (NON-PLASTIC) NETTING
- 7. TO BE USED ONLY IN AREAS OF TEMPORARY SOIL DISTURBANCE ON SLOPES ADJACENT TO THE POND.
- 8. FLAT SURFACES SHALL RECEIVE STRAW MULCH APPLIED TO THE GROUND SURFACE AT A RATE OF 2,500 LBS./ACRE.




COIR FASCINE INSTALLATION FOR BERM (TYP.) Scale: NTS



EMERGENT SHELF PLANTING ZONES (TYP.) Scale: NTS

ARLINGTON RESERVOIR -PHASE 2

ARLINGTON, MASSACHUSETTS



SWCA ENVIRONMENTAL CONSULTANTS 15 RESEARCH DRIVE (P) 413.256.0202 AMHERST, MA 01002 WWW.SWCA.COM

Kyle Zick Landscape Architecture, Inc. 36 Bromfield Street Suite 202 617 451-1018 Tel Boston, MA 02108 www.kylezick.com

DESIGN DEVELOPMENT SET

Job Number: Project: ARLINGTON RES. Checked By: MM Drawn By: TS Date: SEPTEMBER 29, 2020

Scale: Drawing Title:

> BANK RESTORATION DETAILS

> > 4.0

EROSION CONTROL PLAN AND CONSTRUCTION SEQUENCING

EROSION AND SEDIMENT CONTROL METHODS FOR THE PROJECT INCLUDE STRUCTURAL AND STABILIZATION PRACTICES. STRUCTURAL PRACTICES INVOLVE THE CONSTRUCTION OF DEVICES TO DIVERT AND LIMIT RUNOFF. STABILIZATION PRACTICES WILL BE IMPLEMENTED TO COVER EXPOSED SOIL SO THAT DISCHARGE OF SEDIMENT IS MINIMIZED. AN ADEQUATE STOCKPILE OF EROSION CONTROL MATERIALS WILL BE MAINTAINED AT THE PROJECT SITE IN THE EVENT OF AN EMERGENCY OR ROUTINE REPAIR.


TO FURTHER MINIMIZE SEDIMENT LOSS ON THE SITE, A GENERAL CONSTRUCTION SEQUENCE PLAN HAS BEEN DEVELOPED. THE FOLLOWING ARE PROCEDURES TO BE FOLLOWED:


- 1. ALL VEHICLES AND EQUIPMENT BROUGHT TO THE PROJECT SITE SHALL BE CLEAN AND FREE OF INVASIVE PLANT MATERIAL.
- 2. THE WETLAND SPECIALIST SHALL MARK OUT RESOURCE BOUNDARIES IN IMPACT/RESTORATION AREAS IN THE FIELD PRIOR TO CONSTRUCTION.
- 3. PRIOR TO ANY SITE GRADING OR SITE WORK, THE CONTRACTOR SHALL INSTALL ALL SEDIMENT AND EROSION CONTROLS AS SHOWN ON THE RESTORATION PLAN, PLUS ANY ADDITIONAL CONTROLS REQUESTED BY THE WETLAND SPECIALIST BASED ON SITE CONDITIONS TO PREVENT SEDIMENT FROM LEAVING THE SITE OR FURTHER ENCROACHING INTO WETLANDS AND THE RESERVOIR.
- 4. THE CONTRACTOR FOREMAN SHALL BE DESIGNATED AS THE ON-SITE INDIVIDUAL RESPONSIBLE FOR THE DAILY MONITORING AND MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROLS. ANY BREACH OR FAILURE IN SEDIMENT CONTROLS SHALL BE IMMEDIATELY REPAIRED OR REPLACED. SEDIMENT BUILD-UP BEHIND ANY EROSION CONTROL BARRIER SHALL BE REMOVED WHENEVER SEDIMENT HAS ACCUMULATED TO 3-INCHES IN DEPTH.
- 5. THE CONTRACTOR SHALL INCORPORATE PERMANENT EROSION CONTROL FEATURES, PERMANENT SLOPE STABILIZATION, AND VEGETATION INTO THE PROJECT PLANS AT THE EARLIEST PRACTICAL TIME TO MINIMIZE THE NEED FOR TEMPORARY CONTROLS.
- 6. ANY AREA DISTURBED WITHIN THE LIMIT OF BANK WORK IS TO BE SEEDED WITH NEW ENGLAND SEMI-SHADE GRASS AND FORBS SEED MIX UNLESS SPECIFIED OTHERWISE IN THE PLANTING PLAN. THE GROUND SURFACE SHALL BE SCARIFIED PRIOR TO SEEDING. AFTER SEEDING, STRAW MULCH SHALL BE APPLIED TO THE GROUND SURFACE AT A RATE OF 2,500 LBS./ACRE. SEEDED AND/OR PLANTED SLOPES GREATER THAN 3:1 SHALL BE COVERED WITH A BIODEGRADABLE EROSION CONTROL BLANKET SPECIFIED IN THE PLANS.
- 7. THE CONTRACTOR SHALL MAINTAIN TEMPORARY EROSION AND SEDIMENTATION CONTROL SYSTEMS IN GOOD CONDITION UNTIL THE SITE IS STABLE. AS VERIFIED BY THE WETLAND SPECIALIST. ONCE THE SITE IS STABLE, THE SEDIMENT AND EROSION CONTROLS MAY BE REMOVED UNDER THE DIRECTION OF THE
- 8. SHOULD ANY EROSION CONTROL BLANKET BE UTILIZED. THEY SHALL BE COMPRISED OF NON-SYNTHETIC MATERIALS (E.G., JUTE MATTING), NO EROSION CONTROL BLANKETS COMPOSED OF PLASTIC-BASED MATERIALS SHALL BE USED.


- 9. THE PURPOSE OF THIS RESTORATION PLAN IS TO IMPROVE BANK STABILITY OF ARLINGTON RESERVOIR BY REDUCING AND CONTROLLING SEDIMENTATION, RESTORING ERODED BANKS, AND ERADICATING NUISANCE VEGETATION.
- 10. THIS RESTORATION PLAN INCLUDES THREE ACTION OPTIONS DEPENDING ON THE EXTENT OF EXISTING EROSION CONDITIONS OBSERVED IN THE FIELD. BANK RESTORATION OPTIONS ADDRESS ONE OF THREE CONDITIONS A) VERTICAL BANK EROSION GREATER THAN 12 INCHES IN HEIGHT FROM THE WATER LINE, B) VERTICAL BANK EROSION LESS THAN 12 INCHES IN HEIGHT FROM THE WATER LINE, AND C) STABLE BANK EDGES WITH SLOPES DENUDED OF VEGETATION. AREAS INDICATED AS D) WERE OBSERVED TO BE STABLE AND SUFFICIENTLY VEGETATED AND REQUIRE NO ACTION.
- 11. ERODED PORTIONS OF POND EDGES ARE TO BE RESTORED WITH 12" BIODEGRADABLE COIR LOGS. COIR LOGS WILL BE INSTALLED BY HAND AND ASSOCIATED MINOR EARTHWORK WILL ALSO BE COMPLETED BY HAND OR WITH LIGHT MACHINERY. AREA OF RESERVOIR EDGES IMMEDIATELY UPGRADIENT OF COIR LOGS TO BE REVEGETATED AS NEEDED.
- 12. INVASIVE RIPARIAN AND AQUATIC WEEDS AND NUISANCE VEGETATION ARE TO BE REMOVED. REMOVAL TO BE CONDUCTED BY "HYDRO-RAKE" AND CHEMICAL TREATMENTS.
- 13. A FRIABLE "PLANTING BED" CONSISTENCY SHALL BE PREPARED. ANY COMPACTION CAUSED BY EXCAVATION SHALL BE ALLEVIATED.
- 14. THE RESTORATION AREAS ARE TO BE PLANTED WITH NATIVE WOODY SPECIES, THEN SEEDED WITH NATIVE SEED. (SEE PLANT LIST). PLANT SUBSTITUTIONS DUE TO COMMERCIAL AVAILABILITY OR HYDROLOGIC CONDITIONS MUST BE APPROVED BY THE WETLAND SPECIALIST.
- 15. THE EROSION CONTROL BARRIER BETWEEN THE RESERVOIR AND RESTORATION AREAS SHALL BE REMOVED UPON STABILIZATION OF THE RESTORATION AREAS AND THE AREA RAKED TO ELIMINATE ANY BERM THAT MAY BE PRESENT BETWEEN THE RESOURCE RESTORATION AREAS AND THE ADJACENT BVW OR RESERVOIR. ANY BARE SOIL THAT RESULTS FROM THE REMOVAL OF THE EROSION CONTROLS SHALL BE SEEDED WITH THE SPECIFIED SEED MIX. ALL STAKES AND TWINE SHALL BE REMOVED.

SEEDING GUIDANCE

- 16. SEED METHODOLOGY: THE FOLLOWING METHODOLOGY PROVIDES SEQUENCING FOR ESTABLISHING THE SEED MIXES PRESCRIBED ON IN THE PLANS. THIS PROCESS SHOULD BEGIN FOLLOWING FINAL GRADING. THIS METHODOLOGY DOES NOT SPECIFY A TEMPORARY COVER CROP. A COVER CROP MAY BE NEEDED TO STABILIZE THE SITE DEPENDING ON WEATHER CONDITIONS AND CONSTRUCTION TIMING RELATIVE TO THE SEASONS AND THE IDEAL TIME FRAME FOR ESTABLISHING THE SEEDED AREAS. THE BEST TIME TO SEED FOR THIS PROJECT IS IN THE SPRING WHEN THE SOILS ARE AT A NORMAL MOISTURE CONTENT LEVEL (MOIST, NOT SATURATED) AND NO LATER THAN JUNE 30. WEATHER FORECASTS SHOULD BE MONITORED AS OCCASIONAL WATERING MAY BE NECESSARY IF A DRY SPRING SEASON OCCURS. THE SEEDING SEQUENCE SHOULD BEGIN NO LONGER THAN 48 HOURS AFTER FINAL GRADING. SITE STABILIZATION TECHNIQUES SHOULD BE UTILIZED IN THIS 48-HOUR TIME PERIOD.
- 17. SOIL SCARIFICATION/ SEED BED PREPARATION: SEED BED PREPARATION IS THE PROCESS OF SCARIFYING AND LOOSENING THE SOIL SURFACE TO CREATE A LOOSE, FRIABLE, SOIL SURFACE. THE SOIL SURFACE SHOULD BE A UNIFORM PLANAR SURFACE THAT IS FLAT AND WITHOUT EXCESSIVE RIDGES, FURROWS, RUTS OR MOUNDS AND LOW SPOTS WHERE WATER CAN COLLECT. SOIL SCARIFICATION SHOULD ONLY OCCUR WHEN WEATHER, SOIL CONDITIONS, AND CONSTRUCTION PHASING ALLOWS FOR NO LONGER THAN 48 HOURS BETWEEN SCARIFICATION (THE BEGINNING OF THE SEEDING PROCESS) AND COVERING THE SEED WITH WEED FREE STRAW MULCH (NOT HAY), OR EROSION CONTROL BLANKET. THE SOIL SHOULD BE SCARIFIED TO MAXIMUM DEPTH OF 3 INCHES (SEE BELOW). DURING THIS PROCESS, AREAS WHERE COARSE GRAVEL DOMINATES THE SOIL SURFACE SHOULD BE IDENTIFIED AND AMENDED WITH FINE SANDY-SOIL COMMON BORROW GENERATED FROM ON-SITE EARTHWORK. THE IMPORTATION OF TOPSOIL SHOULD BE A LAST RESORT AND ONLY USED AS AN AMENDMENT FOR "LOCALIZED" SPOTS THAT LACK THE CHARACTERISTICS OF A SOIL SEED BED.
- 18. SEED APPLICATION: A WELL-PREPARED SEED BED PROVIDES A LOOSE FRIABLE SOIL SURFACE FOR WHICH THE SEED CAN BE SOWN INTO. SEED APPLICATION IS A TWO-PART PROCESS: 1) SEED APPLICATION AT PROPER RATES PER ACRE AND 2) SOW THE SEED INTO THE SOIL ½ TO ½" DEPTH MAXIMUM. APPROPRIATE SEED RATES FOR EACH PRESCRIBED SEED MIX ARE SPECIFIED ON THE ACCOMPANYING DETAILS SHEET.
- a. SEEDING BY HAND: CHECK THE SEED LABEL PRIOR TO OPENING THE BULK BAG TO CONFIRM THE CORRECT SEED IS BEING APPLIED TO THE SPECIFIED LOCATION. THE BULK BAGS OF SEED SHOULD BE AGITATED BY HAND ON SITE TO REDISTRIBUTE THE SEEDS IN THE MATRIX BEFORE SPREADING. IN BARE AREAS A WEED FREE STRAW MULCH MAY BE USED TO COVER THE SOIL SURFACE FOLLOWING THE SEED APPLICATION.
- b. SOWING THE SEED: ONCE THE SEED IS SPREAD THE SEED MUST BE SOWN INTO THE SOIL TO THE DEPTH ABOVE TO INCREASE CHANCES OF GERMINATION BY KEEPING SOIL MOISTURE CLOSE TO THE SEED. THE SEED CAN BE SOWN BY A NUMBER OF WAYS INCLUDING "TRACKED" IN WITH A LOW PSI RUBBER TIRE OR TRACKED MACHINE, USING A YORK LANDSCAPE RAKE OR SIMILAR, OR THE TRADITIONAL MEANS OF USING A METAL LEAF RAKE.
- 19. RESEEDING: AREAS TO BE RESEEDED SHALL FOLLOW THE SAME SEEDING SEQUENCE OUTLINED ABOVE. IT IS EXPECTED THAT SOME SEEDED AREAS MAY NOT GERMINATE, BUT THAT OVER TIME THE PLANTED AREAS SHALL FILL IN THROUGH SEED PROLIFERATION AND GROWTH HABITS. AREAS LARGE ENOUGH TO BE IDENTIFIED THROUGH MONITORING AS BEING DOMINATED BY WEEDS OR OTHER INVASIVE SPECIES THAT HAVE OUT COMPETED THE SPECIFIED SEED MIX OR AREAS DEEMED UNSTABLE DUE TO LOW PLANT GROWTH SHALL BE RESEEDED ACCORDINGLY.
- 20. PLANT SUCCESSION NOTES: IT IS POSSIBLE THAT OVER TIME SOME SEEDED AREAS MIGHT BECOME DOMINATED BY NATIVE PLANT SPECIES EXISTING IN THE SOIL SEED BANK. ONE EXAMPLE OF THIS IS THE LIKELIHOOD THAT VARIOUS TYPES OF NATIVE FERNS COULD EMERGE IN SHADED AREAS. NO SPECIES OF FERNS ARE IN THE PRESCRIBED SEED MIX BUT ARE HIGHLY DESIRABLE SPECIES THAT CAN EXIST AND THRIVE IN THE IDENTIFIED PLANTING AREAS ADDING TO LANDSCAPE DIVERSITY. NATIVE SPECIES SUCH AS FERNS THAT EMERGE DUE TO BEING IN THE SOIL SEED BANK SHOULD REMAIN. THOROUGH AND REGULAR MONITORING DURING THE MATURATION OF THE ESTABLISHMENT AREAS IS A KEY COMPONENT TO BALANCING AREAS TO BE RESEEDED AND AREAS WHERE SUCCESSIONAL PLANT GROWTH OF NATIVES SHOULD BE ALLOWED TO THRIVE.








1- Shrubs shall be of quality prescribed in the root observations detail and specifications.


2- See specifications for further requirements related to this detail.

SHRUB PLANTING DETAIL

To io in the second sec
Junuary Junuar
10'-0" MIN.
TREE SPACING (TYP.)



Scale: NTS



New England Semi-Shade Grass and Forbs Mix

Botanical Name	Common Name	Indicator
Elymus virginicus	Virginia Wild Rye	FACW-
Elymus canadensis	Canada Wild Rye	FACU+
Festuca rubra	Red Fescue	FACU
Chamaecrista fasciculata	Partridge Pea	FACU
Liatris spicata	Spiked Gayfeather/Marsh Blazing Star	FAC+
Onoclea sensibilis	Sensitive Fern	FACW
Aster prenanthoides (Symphyotrichum prenanthoide)	Zigzag Aster	FAC
Eupatorium fistulosum (Eutrochium fistulosum)	Hollow-Stem Joe Pye Weed	FACW
Eupatorium perfoliatum	Boneset	FACW
Juncus tenuis	Path Rush	FAC

Apply: 30 lbs/acre

NEW ENGLAND SEMI-SHADE GRASS AND FORBS MIX Scale: NTS Source: Seed mixes referenced herein are provided by New England Wetland Plants, Inc.

over Type	Abbrev.	Scientific Name	Common Name	Plant Size @ Installation	Area 'A'	Area 'B'	Area 'C'	rea 'D'
	•		Total Enhancement Area (If)		2,120	1,650	130	680
			Total Enhancement Area Approx. (sf)		31,800	24,750	1,950	10,200
rees								
	Ar	Acer rubrum	Red Maple	4'-6' ht. min.		9	3	
	Ва	Betula alleghaniensis	Yellow Birch	4'-6' ht. min.		9		
	Вр	Betula populifolia	Grey Birch	4'-6' ht. min.		9		
	Ns	Nyssa sylvatica	Black Gum	4'-6' ht. min.		9	3	
	Pd	Populus deltoides	Cottonwood	4'-6' ht. min.		9		
	Qr	Quercus rubra	Red Oak	4'-6' ht. min.		9	3	
	Sd	Salix discolor	Pussywillow	4'-6' ht. min.		9	3	
	Sn	Salix nigra	Black Willow	4'-6' ht. min.	-	9	3	
Shrubs	•							
	Ca	Clethra alnifolia	Sweet Pepperbush	3'-4' ht. min.	50	27	6	
	Cs	Cornus sericea	Red Osier Dogwood	3'-4' ht. min.	50	27	6	
	V	Ilex verticillata	Winterberry	3'-4' ht. min.	50	27	6	
	Vd	Viburnum dentatum	Northern Arrowwood	3'-4' ht. min.	50	27	6	
Herbacious							,	
- Shoreline/Fringe	Ср	Caltha palustris	Marsh Marigold	2" plug	2,100	1,800	150	
	Ер	Eupatorium perfoliatum	Boneset Aster	2" plug	2,100	1,800	150	
	Mr	Mimulus ringens	Monkey Flower	2" plug	2,100	1,800	150	
- Water Depth 0"-6"	Am	Acorus americana	Sweetflag	2" plug	2,100	1,800	150	
	Lc	Lobelia cardinalis	Cardinal Flower	2" plug	2,100	1,800	150	
	V	Iris versicolor	Blue Flag Iris	2" plug	2,100	1,800	150	
- Water Depth 6"-8"	Рс	Pontederia cordata	Pickerelweed	2" plug	1,350	1,050	450	
	Sa	Schoenoplectus acutus	Hard-stem Bulrush	2" plug	1,350	1,050	450	
	Sc	Scirpus cyperinus	Woolgrass	2" plug	1,350	1,050	450	
	SI	Sagittaria latifolia	Duck Potato	2" plug	1,350	1,050	450	
	Sm	Sparganium americanum	Burreed	2" plug	1,350	1,050	450	
- Water Depth > 3'	No	Nymphaea odorata	White Water Lily	tuber		5,220	5,850	
Seed Mix			.					
	New End	aland Erosion Control/Restorat	ion Mix For Detention Basins and Moist Sites (Lbs)	18lbs/acre	13.0	11.0	1.0	

ree quantities specified are based off the USDA New England Forest. Baseline for New England Forest Health Monitoring report.

Trees shall be installed not less than 10 feet on center and no farther than 12 feet on center. Shrubs shall be planted in clusters of 2 or 3, and shall be installed not less than 3 feet on center.

Areas within planting areas not 100% vegetated with existing herbaceous plants will be seeded with the appropriate seed mix at the manufacturers specified rate to cover the bare area.

A wetland scientist or landscape architect shall provide supervision of the plant layout.

Plant substitutions may be necessary due to commercial availability. Substitutions shall be approved by the supervising wetland scientist or landscape architect. Invasive species control semi-annually for the first two-years

Area A woody material assumes 50% slope coverage of upland areas based on the USDA New England Forest prescribed rate of 240 trees per acre and 75% shrub cover at the prescribed spacing above Area B woody material assumes 50% slope coverage of upland areas based on the USDA New England Forest prescribed rate of 240 trees per acre and 75% shrub cover at the prescribed spacing above

Area C woody material assumes 25% slope coverage of upland areas based on the USDA New England Forest prescribed rate of 240 trees per acre and 75% shrub cover at the prescribed spacing above Fringe and aquadic vegetation assumes an average of 3 square feet of planting area per linear foot at 12-inch on center spacing for each community



PLANT SCHEDULE

ARLINGTON **RESERVOIR -**PHASE 2

ARLINGTON, MASSACHUSETTS

TOWN OF ARLINGTON



SWCA ENVIRONMENTAL CONSULTANTS 15 RESEARCH DRIVE (P) 413.256.0202 AMHERST, MA 01002 WWW.SWCA.COM

Kyle Zick Landscape Architecture, Inc. 36 Bromfield Street Suite 202 617 451-1018 Tel Boston, MA 02108 www.kylezick.com

DESIGN DEVELOPMENT SET

Job Number: Project: ARLINGTON RES. Checked By: MM Drawn By: TS Date: SEPTEMBER 29, 2020

Drawing Title:

BANK RESTORATION DETAILS AND NOTES

5.0



STORMWATER MANAGEMENT REPORT

Arlington Reservoir – Phase 2



40 Shattuck Road | Suite 110 Andover, Massachusetts 01810 800.426.4262

woodardcurran.com COMMITMENT & INTEGRITY DRIVE RESULTS

0233115.00

Town of Arlington

Massachusetts

October 2020



TABLE OF CONTENTS

SEC.	TION	PA	GE NO.
1.	PROJEC1	T DESCRIPTION	1-1
	1.1	Introduction	1-1
	1.2	Existing Conditions	
	1.2	.1 Land Cover and Soils	1-1
	1.2	-	
	1.2		
	1.3	Proposed Project Work	
2.	STORMW	/ATER EVALUATION	2-1
	2.1	Stormwater Modeling Methodology	
	2.2	Hydraulic Model Description	
	2.2	•	
		.2 Pre-Development Conditions	
	2.2	 .3 Post-Development Conditions	
	2.3	Peak Discharge Rates and Runoff Volumes	
•		· ·	
3.		ANCE WITH STORMWATER MANAGEMENT STANDARDS	
	3.1	Standard 1: No New Untreated Discharges	3-1
	3.2	Standard 2: Peak Rate Attenuation	
	3.3	Standard 3: Recharge	
	3.4 3.5	Standard 4: Water Quality Standard 5: Land Uses with Higher Potential Pollutant Loads	
	3.6	Standard 6: Critical Areas	
	3.7	Standard 7: Redevelopment	
	3.8	Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Cont	
	3.9	Standard 9: Operation and Maintenance Plan	
	3.10	Standard 10: Prohibition of Illicit Discharges	
		TABLES	
Table	2-1: Design	n Rainfall Data	2-1
		nd Post-Development Peak Discharge Rates	
		and Post-Development Runoff Volumes	
		APPENDICES	
Appe	ndix A:	Environmental Resource Documentation	
	ndix B:	Soils Map and Test Pit Logs	
	ndix C:	Stormwater Figures	
	ndix D:	HydroCAD Stormwater Model Reports	
	ndix E:	Operations & Maintenance Plan	
	ndix F:	Stormwater Pollution Prevention Plan MassDEP Checklist for Stormwater Report	
Appe	ndix G:	Massper Checklist Int Statillingter Vehalt	



1. PROJECT DESCRIPTION

1.1 Introduction

On behalf of the Town of Arlington, Massachusetts (the Town), Woodard & Curran, Inc. (Woodard & Curran) has prepared this Stormwater Management Report for the proposed improvements to the Arlington Reservoir, located at 210 Lowell Street in Arlington, Massachusetts (the Site). The Town is proposing to revitalize the eastern shore of the Arlington Reservoir recreation area. Weston & Sampson Engineers, Inc. (Weston and Sampson), on behalf of the Town of Arlington, developed a Master Plan for the Reservoir in 2018. This proposed project encompasses Phase 2 of the Master Plan and improvements include installing porous pavement over the approximately 0.5-acre gravel parking area in the southern portion of the site, installation of new ADA-accessible pathways, a new play area, a multi-use court, a boat launch, and several other Site improvements as shown on the Post-Development Watershed Figure located in **Appendix C**. The impacts of these improvements to the Site's stormwater drainage patterns are summarized in this report.

1.2 Existing Conditions

A Site Locus Plan on a United States Geological Survey (USGS) Quadrangle Map depicting the project location has been provided in **Appendix A**. Arlington Reservoir is a 65-acre man-made recreational and stormwater-control pond on the Arlington and Lexington Town border. About half of the reservoir's open water is located in the Town of Lexington, however, the Town of Arlington owns and manages the reservoir. The earthen dam around the southern edge of the Reservoir is approximately 600 yards long and up to 14 feet tall. The water within the Reservoir discharges into Mill Brook through a sluice gate.

In 1935, the Town of Arlington constructed a sandy beach on the Reservoir's eastern shore. In the late 1970s, the Town completed improvements to the beach and added an embankment to separate the swimming area from the rest of the Reservoir. The beach now includes a filtered, chlorinated swimming area with a ramp for ADA accessibility, a bathhouse, vending machines, a concession area, and a playground. The Reservoir also has a one-mile walking trail around its perimeter, open to the public throughout the year.

1.2.1 Land Cover and Soils

Land cover and soils datasets were used to develop hydrologic curve numbers. Land cover was determined by a site visit conducted on September 3, 2020 and review of aerial photography and site survey data. A more detailed examination of the existing land cover within individual drainage subcatchments can be found in section 2.2.2. All existing impervious areas located within the Town of Lexington that are proposed to be replaced with a pervious land cover are required to be considered open space in good condition for stormwater calculations purposes per Lexington's Stormwater Management Regulations.

Soil characteristics were observed during test pit evaluations conducted in August 2020 and supplemented with information obtained from the United States Department of Agriculture's (USDA's) most recent Web Soil Survey. A Site map showing soil types and hydrologic soil group classifications within the project vicinity from the USDA's Web Soil Survey is located in **Appendix B**.

Test pits were conducted by Civil Design Consultants, Inc. (CDCI) of Methuen, Massachusetts on August 6, 2020 to evaluate the subsurface soil conditions and identify the estimated seasonal high groundwater table elevation. In all four borings conducted, CDCI observed a surface layer of fill ranging from 9 to 27 inches in depth, followed by a sandy loam layer extending to the bottom of each test pit. From these test pits, it was determined that at its highest elevation in the 0.5-acre parking lot, the seasonal high groundwater table is located approximately at elevation 159.40. Woodard & Curran used this data to locate the proposed stormwater best management practices (BMPs) at elevations with at



least two feet of separation from groundwater. Bedrock was not encountered during test pitting activities. The test pit logs and location figure provided by CDCI are located in **Appendix B**.

1.2.2 Topography

Subcatchment boundaries were delineated using the site survey performed and prepared by Weston & Sampson in December 2017. Topographically, the eastern shore of the Reservoir generally slopes downward from Lowell Street towards the Reservoir, with the exception of the southern-most portion of the 0.5-acre gravel parking area, which slopes downwards towards a ditch just north of the property located at 202 Lowell Street.

In both the pre- and post-development Site conditions, stormwater travels across the Site via overland flow and discharges into one of three Design Points: Arlington Reservoir, the on-Site swimming area, and the ditch located north of 202 Lowell Street. The Design Points and contributing areas are further described in Section 2.2.1. and are depicted in the Pre- and Post-Development Watershed Figures in **Appendix C**.

1.2.3 Resource and Critical Areas

Woodard & Curran reviewed Massachusetts Geographic Information System (MassGIS) data, the Massachusetts Department of Environmental Protection's (MassDEP's) Habitat of Potential Regional and Statewide Importance maps, the Massachusetts Stormwater Handbook, the Massachusetts Year 2016 Integrated List of Waters, and the Federal Emergency Management Agency's (FEMA's) National Flood Hazard Layer (NFHL) database. The findings of our review are below:

- The Massachusetts Endangered Species Act (MESA) protects rare species and their habitats by prohibiting the taking of any plant or animal species listed as Endangered, Threatened, or Special Concern by the Massachusetts Division of Fisheries & Wildlife. MESA review is required by the Natural Heritage & Endangered Species Program (NHESP) for projects and activities located within a Priority or Estimated Habitat of Rare Species. Review of the MassGIS Data shows there are no Priority or Estimated Habitats within the Project Area; therefore, the project is not subject to MESA review.
- Per MassGIS Data, there are no Certified or Potential Vernal Pools within or near the project area.
- Per MassGIS Data, the project is not located within any Areas of Critical Environmental Concern.
- Per the MassDEP's Habitat of Potential Regional and Statewide Importance maps for the Towns of Arlington and Lexington, the project in not located within a Habitat of Regional or Statewide Importance.
- Per the Massachusetts Stormwater Handbook, critical areas include Outstanding Resource Waters and Special Resource Waters, recharge areas for public water supplies, bathing beaches, cold-water fisheries, and shellfish growing areas. Review of MassGIS Data indicated that the Arlington Reservoir is not located within a resource area, however, the Swimming Area on the eastern shore of the Reservoir is classified as a bathing beach, as defined in 105 CMR 445, and thus a critical area.
- Per the Massachusetts Year 2016 Integrated List of Waters, Mill Brook, which receives discharges from
 Arlington Reservoir via a sluice gate on the southern portion of the Reservoir, is classified as a Category 5
 water, meaning the waterbody requires a Total Maximum Daily Load (TMDL) restriction. Mill Brook's
 impairment of concern is Escherichia Coli (E. Coli). Proposed site improvements are not likely to increase E.
 Coli levels in Arlington Reservoir, and thus contributing to Mill Brook's impairment.



• Per FEMA's NFHL database, the majority of the Site is located within an area of minimal flood hazard (Zone X). The Reservoir's shoreline and the isolated swimming area are located within special flood hazard areas (Zone AE). The FEMA NFHL FIRMette Map is located in **Appendix A**.

Measures taken to address the presence of a critical area on-Site are detailed in Section 3.6. Critical areas have specific stormwater analysis guidelines, requiring the use of certain pollution prevention measures and BMPs to the maximum extent practicable for redevelopment projects.

1.3 Proposed Project Work

The proposed project consists of paving the approximately 0.5-acre gravel parking area in the southern portion of the site, renovation of the existing bathhouse and concessions building, installation of new ADA-accessible concrete pathways, lifeguard stands, picnic tables, a playground, multi-use court, boat launch, check-in shelter, and several other surficial Site improvements. Construction activities are expected to begin in March 2021 and end in November 2021.



2. STORMWATER EVALUATION

2.1 Stormwater Modeling Methodology

TR-55/TR-20 methodology was used to develop a hydrologic model of the site. Woodard & Curran used the computer program entitled HydroCAD Version 10.0, developed by HydroCAD Software Solutions, LLC in order to create and analyze the site hydrology. The analysis was conducted in order to establish the peak rates of runoff and estimated runoff volume from the project site. This was accomplished to evaluate pre- and post-development conditions during various storm events. Contributing drainage areas were identified and soils, surface cover, watershed slope, and flow paths were evaluated to develop the necessary HydroCAD model input parameters. A minimum Time of Concentration (Tc) of 6 minutes was used in the calculations, as applicable.

Drainage calculations were performed for the pre- and post-development conditions for the 1-, 2-, 10-, 25-, and 100-year 24-hour Type III storm events, and are included in **Appendix D**, in accordance with the Town of Arlington's, Town of Lexington's, and the Massachusetts Department of Environmental Protection's Stormwater Management Regulations. The total rainfall for each of the storm events was based upon data published by the Northeast Regional Climate Center (NRCC) and Natural Resources Conservation Service (NRCS) entitled *Extreme Precipitation in New York and New England* found at http://precip.eas.cornell.edu/. The total precipitation depth for the project site associated with each rainfall event is outlined in **Table 2-1**, below.

Table 2-1: Design Rainfall Data

Type III 24-Hour Storm Event (Frequency)	Rainfall Depth (Inches)
1-Year	2.67
2-Year	3.21
10-Year	4.86
25-Year	6.17
100-Year	8.85

A copy of the NRCC and NRCS Extreme Precipitation Table for the project Site is included in **Appendix A**.

2.2 Hydraulic Model Description

A stormwater model has been developed to compare the peak runoff rates from the pre-development site to the peak runoff rates anticipated from the post-development site. As further described herein, the model demonstrates that the post-development runoff rates will not exceed pre-development rates.

2.2.1 Design Points

Existing and proposed subcatchments were delineated in order to compare pre- and post-development peak rates of runoff. Although the size of each subcatchment differs slightly between the existing and proposed site conditions, the total area analyzed between the two conditions remained the same. A Design Point was established for each watershed, symbolizing the area's ultimate stormwater discharge location. For this analysis, two watershed areas were identified, and therefore two Design Points were chosen, as follows:

• Design Point 1 (DP-1): represents runoff discharging to the Arlington Reservoir and Swimming Area.



 Design Point 2 (DP-2): represents runoff discharging to the ditch located north of the property at 202 Lowell Street.

The locations of the Design Points do not differ in the pre- and post-development analyses, as seen in the figures located in **Appendix C**.

2.2.2 Pre-Development Conditions

The pre-development project area consists of a swimming area, sandy beach, bathhouse, vending machines, concession area, playground, pump station building, walking paths, benches, lifeguard stands, a 0.5-acre gravel parking lot, a small paved parking lot, and various other Site features. Existing grassed areas on-Site were modeled to be in "fair" condition, as much of the grassed surfaces are currently covered in beach sand and therefore are not likely infiltrating groundwater as efficiently as grass in "good" condition would be.

Per Article 15 – Storm Water Mitigation of the Town of Arlington's Title V – Regulations Upon the Use of Private Property Bylaws, impervious surfaces are defined as "a hard-surfaced, human-made area that does not readily absorb or retain water, preventing the infiltration of storm water runoff; including but not limited to...parking and driveway areas..." Upon review of existing conditions at the site, it appears the 0.5-acre gravel parking lot on the southern half of the Site exhibits the hydrologic characteristics one would expect with an impervious surface. Ponded water has been observed on the gravel surface several days after rain events due to its inability to infiltrate to the soil below. Based on this review and Article 15 of the Town of Arlington's Title V Bylaws, the gravel parking area has been considered impervious for the purposes of this stormwater analysis.

The pre-development watershed area is approximately 5.42 acres in size. There are no existing stormwater BMPs on-Site; stormwater runoff from the three subcatchments within the project area is conveyed via overland flow to their respective design points, as described below:

- Subcatchment 1: Subcatchment 1 encompasses the northern portion of the Site, including the playground, beach, and parking lots. Stormwater runoff from subcatchment 1 flows via overland flow from east to west before discharging into the Arlington Reservoir and Swimming Area (DP-1), which is classified by MassDEP as a critical area. The area is approximately 5.22 acres in size; land cover is primarily comprised of grass, beach sand, surface water, and impervious gravel with smaller areas of brush, impervious structures, and sand pathways. The calculated weighted curve number for this subcatchment is 71.
- Subcatchment 2: Subcatchment 2 encompasses the southern-most portion of the 0.5-acre gravel parking area. Stormwater runoff from subcatchment 3 flows via overland flow from north to south before discharging into the ditch just north of the property at 202 Lowell Street (DP-2). The area is approximately 0.20 acre in size; land cover is primarily comprised of impervious gravel, grass, and brush, with smaller areas of impervious surfaces. The calculated weighted curve number for this subcatchment is 64.

The subcatchment areas and their associated design points are illustrated on the Pre-Development Watershed Figure provided in **Appendix C** of this Report.

2.2.3 Post-Development Conditions

The post-development project area will consist of a swimming area, sandy beach, renovated bathhouse, vending machine, and concession area, a newly-paved picnic pavilion and drop-off area, a new check-in area, permeable multi-surface athletic court, playground, lifeguard stands, walking paths, restored grass areas, 21,500 square-foot porous pavement parking lot, and various other Site features. The new walking paths around the project area will be ADA-



accessible and will allow increased Site access not currently provided in the Site's existing condition. The porous pavement parking lot is described in further detail in Section 2.2.4.

Similar to the pre-development model, the post-development watershed area is also 5.42 acres in size. Stormwater runoff from the two subcatchments will flow to its respective design points, as described below:

- Subcatchment 1: Subcatchment 1 will encompass the northern portion of the Site, including the playground, beach, and parking lots. Stormwater runoff from subcatchment 1 will flow via overland flow from east to west before either discharging directly into Arlington Reservoir and Swimming Area (DP-1) or into the porous pavement system proposed for installation over the Site's southern parking area. Stormwater entering the porous pavement system will either infiltrate into the ground or, during large storm events, will be collected by the system's underdrain and discharged towards Arlington Reservoir. The subcatchment area will be approximately 5.32 acres in size; land cover will be primarily comprised of grass, surface water, beach sand, porous asphalt pavement, and various impervious surfaces (including standard asphalt pavement, concrete walkways, and structures), with smaller areas of brush, permeable playground and athletic court surfaces, and stone dust. The calculated weighted curve number for this subcatchment is 69.
- Subcatchment 2: Subcatchment 2 will encompass the area south of the porous pavement parking area. Stormwater runoff from subcatchment 2 will flow via overland flow from north to south before discharging into the ditch just north of the property at 202 Lowell Street (DP-2). The area will be approximately 0.10 acre in size; land cover will be entirely comprised of grass. The calculated weighted curve number for this subcatchment is 39.

The subcatchment areas and their associated design points are illustrated on the Post-Development Watershed Figure provided in **Appendix D** of this Report.

2.2.4 Low Impact Development Technique – Porous Pavement

Porous pavement was selected as a Low Impact Development (LID) technique for this Site in accordance with the Arlington Reservoir Master Plan written by Weston & Sampson in 2018. The proposed 21,500 square-foot porous pavement parking lot will replace the existing impervious gravel lot, which will provide a stabilized parking area and minimize the amount of maintenance required to upkeep the parking lot and reduce the amount sediment transported into Arlington Reservoir during post-construction conditions. Stormwater directed to the porous pavement will filter through the system's asphalt, choker, and pea gravel courses and enter the reservoir course, designed to provide storage capacity while stormwater infiltrates into the soils beneath the system. The bottom of the reservoir course was designed at elevation 161.40, providing a 2-foot separation from the highest seasonal high groundwater table elevation observed during test pitting activities conducted at the Site. A four-inch PVC underdrain and three grate inlets will be installed within the western-most portion of the system's reservoir course to provide an outlet for stormwater during extreme storm events. The invert of these outlets was designed at the 100-year storm elevation within the porous pavement BMP, meaning rainfall greater than the 100-year storm will flow through the reservoir course of the pavement system to the PVC underdrain and grate inlets and will discharge to the Arlington Reservoir (DP-1).

Volume 1, Chapter 1 of the Massachusetts Stormwater Handbook does not list porous pavement as an approved stormwater BMP for discharges near bathing beaches and Volume 2, Chapter 2 of the Handbook states that porous pavement shall be set back at least 100 feet from surface waters to receive any water quality credit. Existing Site constraints, including the lack of available area to install stormwater BMPs and the proximity to surface water across the entire project area, inhibit the use of many typical BMPs. Although porous pavement is not a listed BMP for bathing beaches, its use can be implemented within the project area and it will improve stormwater treatment at the Site by increasing water quality volume, annual recharge, and removal of total suspended solids (TSS) in the post-development Site condition.



2.3 Peak Discharge Rates and Runoff Volumes

The tables below summarize the pre- and post-development peak discharge rates and runoff volumes for each Design Point.

Table 2-2: Pre- and Post-Development Peak Discharge Rates

Design	Design 1-year (cfs)				2-year (cfs)			10-year (cfs)			year (cfs	s)	100-year (cfs)			
Point	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	
DP-1	2.96	1.65	-1.31	4.93	3.15	-1.78	12.11	8.92	-3.19	18.53	14.29	-4.24	32.53	26.30	-6.23	
DP-2	0.04	0.00	-0.04	0.10	0.00	-0.10	0.33	0.00	-0.33	0.54	0.02	-0.52	1.04	0.13	-0.91	

Note: Δ stands for net difference between the pre- and post-development rates.

Table 2-3: Pre- and Post-Development Runoff Volumes

Design	1-year (af)			2-year (af)			10-year (af)			25	-year (a	f)	100-year (af)		
Point	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ
DP-1	0.25	0.17	-0.08	0.38	0.27	-0.11	0.87	0.66	-0.21	1.32	1.03	-0.29	2.32	1.87	-0.45
DP-2	0.00	0.00	0.00	0.00	0.00	0.00	0.03	0.00	-0.03	0.04	0.00	-0.04	0.07	0.01	-0.06

Note: Δ stands for net difference between the pre- and post-development volumes.

Table 2-2 demonstrates a decrease in peak discharge rates between the existing and proposed site conditions for all scenarios shown above; **Table 2-3** demonstrates a decrease in runoff volumes between the existing and proposed site conditions for all scenarios shown above. Complete copies of the pre- and post-development HydroCAD computer model outputs demonstrating that peak discharge rates and runoff volumes decrease between the existing and proposed Site conditions are included in **Appendix D**.



3. COMPLIANCE WITH STORMWATER MANAGEMENT STANDARDS

Volume 1, Chapter 1 of the Massachusetts Stormwater Handbook states:

"For purposes of the Stormwater Management Standards, redevelopment projects are defined to include...maintenance and improvement of existing roadways, including widening less than a single lane, adding shoulders, correcting substandard intersections, improving existing drainage systems, and repaving."

By this definition, the Arlington Reservoir Phase 2 project is considered a redevelopment project, meaning certain Standards included in the Massachusetts Stormwater Handbook only need to be met to the maximum extent practicable (as defined by Standard 7). The following sections further detail applicability of these Stormwater Management Standards and demonstrates that the proposed Arlington Reservoir – Phase 2 Project complies with these requirements.

3.1 Standard 1: No New Untreated Discharges

"No new stormwater conveyances (e.g. outfalls) will discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth."

In the existing site condition, stormwater is generally transported via overland flow towards the Arlington Reservoir and Swimming Area (DP-1) and the ditch just north of the property at 202 Lowell Street (DP-2). Runoff from the project area is not currently treated prior to discharge. The proposed site improvements will not create any new untreated stormwater discharges and will result in a net decrease in impervious area of approximately 18,000 square feet. Stormwater runoff from Site will be either conveyed via overland flow to Design Points, similar to existing condition drainage patterns, or will be treated by a new porous pavement system prior to infiltrating into the ground or, during extreme storms greater than the 100-year event, discharging into the Arlington Reservoir (DP-1) after filter treatment. There are no proposed untreated stormwater discharges that will cause erosion in or to wetlands or waters of the Commonwealth. This Standard has been met.

3.2 Standard 2: Peak Rate Attenuation

"Stormwater management systems shall be designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates."

Calculations are provided to show that the post-development peak discharge rates do not exceed pre-development rates for the 1-, 2-, 10-, 25-, and 100-year 24-hour storm events. A detailed description of both the existing and proposed Site conditions are located in Section 2.2 of this report. Copies of the existing and proposed HydroCAD computer model outputs demonstrating that this standard has been met are included in **Appendix D**.

3.3 Standard 3: Recharge

"Loss of annual recharge to groundwater shall be eliminated or minimized through the use of infiltration measures including environmentally sensitive site design, low impact development techniques, stormwater best management practices, and good operation and maintenance. At a minimum, the annual recharge from the post-development site shall approximate the annual recharge from pre-development conditions based on soil type. This condition is met when the stormwater management system is designed to infiltrate the required volume as determined in accordance with the Massachusetts Stormwater Handbook."

The proposed improvements will decrease the amount of impervious area across the project Site by approximately 18,000 square feet. No additional groundwater recharge volume is required, however, installation of porous pavement over the existing gravel parking lot in the southern portion of the Site and restoration of grass areas throughout the Site



are proposed as part of this project. The porous pavement and restored grass areas will increase stormwater infiltration, and therefore annual recharge, in the post-development Site condition.

3.4 Standard 4: Water Quality

"Stormwater management systems shall be designed to remove 80% of the average annual post-construction load of Total Suspended Solids (TSS). This Standard is met when: (a) Suitable practices for source control and pollution prevention are identified in long-term pollution prevention plan, and thereafter implemented and maintained; (b) Structural stormwater best management practices are sized to capture the required water quality volume determined in accordance with the Massachusetts Stormwater Handbook; and (c) Pretreatment is provided in accordance with the Massachusetts Stormwater Handbook."

Existing Site conditions provide 0% TSS removal. The Town of Arlington is proposing to install a porous pavement system over the existing gravel parking lot in the southern portion of the Site. The system will increase water quality volume and remove TSS from the stormwater runoff produced from the proposed parking lot area and the adjacent grass area to the east sloping downward from Lowell Street in the post-development Site condition. During storm events, stormwater will filter through the porous pavement system's asphalt, choker, and pea gravel courses and enter the reservoir course, designed to provide storage capacity while stormwater infiltrates into the soils beneath the system.

According to Volume 2, Chapter 2 of the Massachusetts Stormwater Handbook, porous pavement systems can remove up to 80% of TSS if the reservoir course is designed to hold the Site's required water quality volume and to drain within 72 hours of a storm event. The proposed Site improvements will decrease the amount of impervious area across the project Site by approximately 18,000 square feet, and therefore no additional water quality volume is required on-Site. However, the porous pavement system's reservoir course has been designed to store the 100-year storm event and to drain within 26 hours of the 100-year event. Therefore, it can be assumed that the proposed porous pavement system will remove up to 80% of the TSS in stormwater runoff discharging to the system. On other parts of the proposed project Site, this Standard is met to the maximum extent practicable by not creating any new untreated stormwater discharges.

An Operations and Maintenance Plan is provided in **Appendix E**, which specifies suitable practices for source control and long-term pollution prevention.

3.5 Standard 5: Land Uses with Higher Potential Pollutant Loads

"For land uses with higher potential pollutant loads, source control and pollution prevention shall be implemented in accordance with the Massachusetts Stormwater Handbook to eliminate or reduce the discharge of stormwater runoff from such land uses to the maximum extent practicable. If through source control and/or pollution prevention all land uses with higher potential pollutant loads cannot be completely protected from exposure to rain, snow, snow melt, and stormwater runoff, the proponent shall use the specific structural stormwater BMPs determined by the Department to be suitable for such uses as provided in the Massachusetts Stormwater Handbook."

The proposed project is not considered a Land Use with Higher Potential Pollutant Loads; therefore, this standard does not apply.

3.6 Standard 6: Critical Areas

"Stormwater discharges within the Zone II or Interim Wellhead Protection Area of a public water supply and stormwater discharges near or to any other critical area require the use of the specific source control and pollution prevention measures and the specific structural stormwater best management practices determined by the Department to be suitable for managing discharges to such areas as provided in the Massachusetts Stormwater Handbook."



Per the Massachusetts Stormwater Handbook, the Arlington Reservoir and associated Swimming Area on the eastern shore of the Reservoir are classified as critical areas. These surface water features are described throughout this report as DP-1 and will receive stormwater discharges from subcatchment 1 in the post-development Site condition. Critical areas have specific stormwater analysis guidelines, requiring the use of certain pollution prevention measures and BMPs to the maximum extent practicable for redevelopment projects. Compliance with these guidelines is discussed below:

- Standard 6 requires BMP trains discharging to critical areas to remove 80% of TSS prior to discharge. There are no existing stormwater BMPs located in subcatchment 1. In the proposed Site condition, the majority of stormwater runoff from subcatchment 1 will travel, via overland flow, to the Reservoir and Swimming Area by passing over grassed areas and beach sand prior to discharging into DP-1. This stormwater runoff will not be treated by a stormwater BMP, similar to existing Site conditions. Stormwater runoff produced from the proposed porous parking lot area and the adjacent grass area to the east sloping downward from Lowell Street will filter through the porous pavement system, during which 80% of TSS will be removed.
- A water quality depth of one-inch (1") must be used for water quality volume calculations in critical areas. The proposed Site improvements will decrease the amount of impervious area across the project Site by approximately 18,000 square feet, and therefore no additional water quality volume is required on-Site.

The proposed Site improvements meet this Standard to the maximum extent practicable.

3.7 Standard 7: Redevelopment

"A redevelopment project is required to meet the following Stormwater Management Standards only to the maximum extent practicable: Standard 2, Standard 3, and the pretreatment and structural best management practice requirements of Standards 4, 5 and 6. Existing stormwater discharges shall comply with Standard 1 only to the maximum extent practicable. A redevelopment project shall also comply with all other requirements of the Stormwater Management Standards and improve existing conditions."

The proposed project is considered a redevelopment project and will decrease the overall impervious area on Site by approximately 18,000 square feet. The proposed work fully complies with Stormwater Management Standards 1, 2, 3, 5, 8, 9, and 10, and complies, to the maximum extent practicable, with Standards 4 and 6 as described herein.

3.8 Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

"A plan to control construction related impacts including erosion, sedimentation, and other pollutant sources during construction and land disturbance activities (construction period erosion, sedimentation, and pollution prevention plan) shall be developed and implemented."

A plan to control construction-related impacts, specifically erosion and sedimentation, has been developed and is included in **Appendix F**. The proposed project has been designed to minimize land disturbance and preserve existing vegetation to the maximum extent practicable. The proposed construction BMPs have been designed in accordance with Massachusetts Erosion and Sediment Control BMPs Handbook published by MassDEP.

The Contractor will be responsible for implementing the specified erosion and sedimentation control methods. These measures will be maintained and kept in place until the disturbed areas of the project have fully stabilized. In addition, a U.S. Environmental Protection Agency (EPA) National Pollutant Discharge Elimination System (NPDES) Construction General Permit is required whenever construction activities will disturb one or more acres; the proposed project will disturb approximately 5.42 acres.



3.9 Standard 9: Operation and Maintenance Plan

"A long-term operation and maintenance plan shall be developed and implemented to ensure that stormwater management systems function as designed."

A long-term Operation and Maintenance Plan is included in **Appendix E** of this report.


3.10 Standard 10: Prohibition of Illicit Discharges

Standard 10 states that "All illicit discharges to the stormwater management system are prohibited."

The project will not result in any new illicit discharges. An Illicit Discharge Compliance Statement will be submitted prior to construction.



ENVIRONMENTAL RESOURCE DOCUMENTATION APPENDIX A:



1. BASE MAP TAKEN FROM UNITED STATES GEOLOGICAL SERVICES, DATED 2018. ACCESSED ON SEPTEMBER 15, 2020.

CHECKED BY: BSM 2020.09.15 LOCUS MAP.dw

40 Shattuck Road, Suite 110 Andover, Massachusetts 01810 866.702.6371 | www.woodardcurran.com

COMMITMENT & INTEGRITY DRIVE RESULTS

ARLINGTON RESERVOIR PHASE 2 LOCUS MAP

DESIGNED BY: LLT DRAWN BY: LLT

TOWN OF ARLINGTON, MA 51 GROVE STREET ARLINGTON, MA 02476

JOB NO: 0233115.00 DATESEPTEMBER 202


ARLINGTON RESERVOIR 129 OF 47 GURE 1

1DWLRODO (DRRG-EDUGIDHU)51WWH




HHOG

UHJYO DWRU\ SYUSRAHY



Habitat of Potential Regional or Statewide Importance Town of ARLINGTON, MA





131 of 479

The MassDEPs Massachusetts Wildlife Habitat Protection Guidance for Inland Wetlands, June 2006 adopted a new approach for assessing wildlife habitat impacts associated with work in wetlands. This approach utilizes maps developed at the University of Massachusetts Amherst using the Conservation Assessment and Prioritization System (CAPS). The maps depict Habitat of Potential Regional or Statewide Importance that may trigger more intensive levels of review. For more information on how to assess wildlife habitat impacts, see Section III of the Guidance document: http://www.mass.gov/dep/water/laws/wldhab.pdf.

Miles

The CAPS model assesses the ecological integrity of Massachusetts landscape features as influenced by environmental stressor metrics (e.g. pollution, fragmentation). CAPS relies on data that are broadly available across Massachusetts. Ecological features which are not consistently surveyed or uniformly available, such as certified vernal pools, rare species, and contamination sites are not included in CAPS. When available, this more specific ecological information may be used in conjunction with the CAPS outputs to better understand particular sites in Massachusetts and support informed conservation decision-making. For more information on the statewide maps produced by the CAPS model, see: http://www.masscaps.org.

These maps are funded in part by the Massachusetts Executive Office of Energy and Environmental Affairs, the Massachusetts Department of Environmental Protection and the U.S. Environmental Protection Agency under section 104 (b)(3) of the U.S. Clean Water Act. Environmental data sources include the Office of Geographic and Environmental Information (MassGIS).




Important Wildlife Habitat



Habitat of Potential Regional or Statewide Importance Town of LEXINGTON, MA





The MassDEPs Massachusetts Wildlife Habitat Protection Guidance for Inland Wetlands, June 2006 adopted a new approach for assessing wildlife habitat impacts associated with work in wetlands. This approach utilizes maps developed at the University of Massachusetts Amherst using the Conservation Assessment and Prioritization System (CAPS). The maps depict Habitat of Potential Regional or Statewide Importance that may trigger more intensive levels of review. For more information on how to assess wildlife habitat impacts, see Section III of the Guidance document: http://www.mass.gov/dep/water/laws/wldhab.pdf.

The CAPS model assesses the ecological integrity of Massachusetts landscape features as influenced by environmental stressor metrics (e.g. pollution, fragmentation). CAPS relies on data that are broadly available across Massachusetts. Ecological features which are not consistently surveyed or uniformly available, such as certified vernal pools, rare species, and contamination sites are not included in CAPS. When available, this more specific ecological information may be used in conjunction with the CAPS outputs to better understand particular sites in Massachusetts and support informed conservation decision-making. For more information on the statewide maps produced by the CAPS model, see: http://www.masscaps.org.

These maps are funded in part by the Massachusetts Executive Office of Energy and Environmental Affairs, the Massachusetts Department of Environmental Protection and the U.S. Environmental Protection Agency under section 104 (b)(3) of the U.S. Clean Water Act. Environmental data sources include the Office of Geographic and Environmental Information (MassGIS).





Extreme Precipitation Tables

Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

Smoothing Yes

State Massachusetts

Location

Longitude 71.187 degrees West 42.428 degrees North

Elevation 0 feet

Date/Time Thu, 10 Sep 2020 11:23:56 -0400

Extreme Precipitation Estimates

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.28	0.43	0.53	0.70	0.87	1.10	1yr	0.75	1.04	1.28	1.63	2.08	2.67	2.90	1yr	2.36	2.79	3.26	3.95	4.62	1yr
2yr	0.35	0.53	0.67	0.88	1.10	1.39	2yr	0.95	1.28	1.61	2.03	2.55	3.21	3.56	2yr	2.84	3.42	3.92	4.66	5.31	2yr
5yr	0.41	0.64	0.81	1.08	1.38	1.76	5yr	1.19	1.60	2.05	2.58	3.24	4.07	4.53	5yr	3.60	4.35	4.97	5.93	6.65	5yr
10yr	0.47	0.73	0.93	1.26	1.64	2.10	10yr	1.41	1.90	2.45	3.10	3.89	4.86	5.43	10yr	4.31	5.22	5.95	7.11	7.88	10yr
25yr	0.56	0.88	1.12	1.55	2.05	2.66	25yr	1.77	2.39	3.11	3.94	4.95	6.17	6.92	25yr	5.46	6.66	7.55	9.05	9.87	25yr
50yr	0.62	1.00	1.29	1.81	2.43	3.19	50yr	2.10	2.84	3.75	4.75	5.95	7.39	8.32	50yr	6.54	8.00	9.04	10.87	11.71	50yr
100yr	0.72	1.17	1.50	2.13	2.89	3.81	100yr	2.50	3.37	4.48	5.69	7.13	8.85	10.00	100yr	7.83	9.62	10.84	13.05	13.90	100yr
200yr	0.82	1.34	1.74	2.49	3.44	4.56	200yr	2.97	4.01	5.38	6.84	8.57	10.61	12.04	200yr	9.39	11.57	12.99	15.68	16.50	200yr
500yr	1.00	1.64	2.13	3.09	4.33	5.78	500yr	3.74	5.05	6.85	8.72	10.91	13.49	15.38	500yr	11.94	14.79	16.51	20.00	20.71	500yr

Lower Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.24	0.37	0.46	0.62	0.76	0.84	1yr	0.65	0.82	1.14	1.43	1.76	2.39	2.46	1yr	2.12	2.37	2.89	3.50	4.01	1yr
2yr	0.33	0.51	0.63	0.85	1.05	1.25	2yr	0.90	1.23	1.44	1.90	2.46	3.10	3.43	2yr	2.74	3.30	3.78	4.49	5.14	2yr
5yr	0.39	0.60	0.74	1.02	1.29	1.50	5yr	1.12	1.46	1.72	2.23	2.87	3.73	4.13	5yr	3.30	3.97	4.54	5.42	6.11	5yr
10yr	0.43	0.66	0.82	1.15	1.48	1.71	10yr	1.28	1.67	1.93	2.51	3.22	4.29	4.76	10yr	3.80	4.58	5.22	6.21	6.96	10yr
25yr	0.50	0.76	0.94	1.34	1.77	2.03	25yr	1.53	1.98	2.28	2.95	3.75	5.14	5.73	25yr	4.55	5.51	6.26	7.40	8.25	25yr
50yr	0.55	0.84	1.04	1.50	2.02	2.32	50yr	1.74	2.27	2.57	3.33	4.22	5.89	6.57	50yr	5.21	6.32	7.18	8.42	9.37	50yr
100yr	0.61	0.93	1.16	1.68	2.30	2.64	100yr	1.99	2.58	2.91	3.58	4.74	6.77	7.54	100yr	5.99	7.25	8.24	9.55	10.65	100yr
200yr	0.69	1.04	1.31	1.90	2.65	3.01	200yr	2.29	2.94	3.30	4.00	5.35	7.76	8.65	200yr	6.87	8.32	9.45	10.81	12.08	200yr
500yr	0.80	1.19	1.54	2.23	3.17	3.58	500yr	2.74	3.50	3.88	4.63	6.27	9.30	10.35	500yr	8.23	9.95	11.33	12.69	14.28	500yr

Upper Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.31	0.48	0.59	0.79	0.97	1.13	1yr	0.84	1.11	1.32	1.76	2.24	2.86	3.14	1yr	2.53	3.02	3.50	4.29	5.02	1yr
2yr	0.36	0.56	0.69	0.93	1.15	1.35	2yr	0.99	1.32	1.56	2.06	2.66	3.34	3.71	2yr	2.96	3.57	4.09	4.86	5.52	2yr
5yr	0.45	0.69	0.86	1.18	1.50	1.78	5yr	1.30	1.74	2.04	2.63	3.35	4.43	4.98	5yr	3.92	4.79	5.42	6.45	7.20	5yr
10yr	0.54	0.84	1.04	1.45	1.87	2.19	10yr	1.62	2.14	2.54	3.19	4.02	5.51	6.24	10yr	4.88	6.00	6.73	8.03	8.82	10yr
25yr	0.71	1.07	1.34	1.91	2.51	2.88	25yr	2.17	2.82	3.36	4.11	5.11	7.32	8.42	25yr	6.48	8.09	8.97	10.76	11.55	25yr
50yr	0.85	1.30	1.62	2.33	3.13	3.56	50yr	2.70	3.48	4.16	4.99	6.13	9.11	10.57	50yr	8.06	10.16	11.13	13.44	14.18	50yr
100yr	1.04	1.58	1.98	2.85	3.92	4.39	100yr	3.38	4.29	5.16	6.33	7.35	11.32	13.28	100yr	10.02	12.77	13.82	16.82	17.43	100yr
200yr	1.27	1.91	2.42	3.51	4.89	5.41	200yr	4.22	5.29	6.41	7.73	8.81	14.10	16.70	200yr	12.48	16.06	17.18	21.05	21.44	200yr
500yr	1.65	2.46	3.17	4.60	6.54	7.13	500yr	5.64	6.97	8.53	10.08	11.21	18.85	22.64	500yr	16.68	21.77	22.89	28.39	28.21	500yr





SOILS MAP AND TEST PIT LOGS APPENDIX B:



MAP LEGEND MAP INFORMATION The soil surveys that comprise your AOI were mapped at Area of Interest (AOI) 1:25,000. Area of Interest (AOI) C/D Soils Warning: Soil Map may not be valid at this scale. D Soil Rating Polygons Enlargement of maps beyond the scale of mapping can cause Not rated or not available Α misunderstanding of the detail of mapping and accuracy of soil Water Features line placement. The maps do not show the small areas of A/D contrasting soils that could have been shown at a more detailed Streams and Canals В scale. Transportation B/D Rails Please rely on the bar scale on each map sheet for map С Interstate Highways C/D Source of Map: Natural Resources Conservation Service **US Routes** Web Soil Survey URL: D Major Roads Coordinate System: Web Mercator (EPSG:3857) Not rated or not available Local Roads Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Soil Rating Lines Background Aerial Photography Albers equal-area conic projection, should be used if more A/D accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. B/D Soil Survey Area: Middlesex County, Massachusetts Survey Area Data: Version 20, Jun 9, 2020 C/D Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Not rated or not available Date(s) aerial images were photographed: Sep 11, 2019—Oct 5, Soil Rating Points The orthophoto or other base map on which the soil lines were Α compiled and digitized probably differs from the background A/D imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. В B/D

Natural Resources
Conservation Service

Web Soil Survey National Cooperative Soil Survey

Hydrologic Soil Group

		_		
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
1	Water		7.3	47.2%
253B	Hinckley loamy sand, 3 to 8 percent slopes	А	7.2	46.4%
626B	Merrimac-Urban land complex, 0 to 8 percent slopes	A	0.8	5.4%
631C	Charlton-Urban land- Hollis complex, 3 to 15 percent slopes, rocky	А	0.2	1.1%
Totals for Area of Inter	est	1	15.5	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher



	Town of Arlington				
	Owner Name				
	210 Lowell Street				
	Street Address	244	Map/Lot #		
	Arlington	MA	02474		
	City	State	Zip Code		
В.	Site Information				
1.	(Check one)	grade Repair Tes	t pits for drainage pu	irposes	
2.	Soil Survey Available? X Yes No	If yes:		Web Soil Survey Source	253B Soil Map Unit
	Hinckley Loamy Sand				
	Soil Name	Soil Limitations			
	Sandy and gravelly glaciofluvial deposits				
	Soil Parent material	Landform			
3.	Surficial Geological Report Available? X Yes No	If yes: MassGIS Oliv	ver		
		Year Published/	/Source	Map Unit	
	Sand and gravel / till and bedrock				
	Description of Geologic Map Unit:				
4.	Flood Rate Insurance Map Within a regulatory	y floodway? \square Yes \square No)		
5.	Within a velocity zone?				
6.	Within a Mapped Wetland Area?	No If yes, Mass	GIS Wetland Data		and Type
7.		08/06/20 Month/Day/ Year	Range: Abo	ve Normal 🗓 N	Normal Below Normal
0	Other references reviewed:				



ACC 240				•						•			
C. On-	Site Revi	ew (minim	um of two hole	es requ	iired at ever	y propo	sed prin	nary and r	eserve disp	osal area))		
Deep	Observation	n Hole Numb	er: <u>TP-1</u>	08/06 Date	5/20	7:30	AM	70*, su	ınny				
·			Hole #	Date	3.7	Time		Weather		Latitude		Longitude:	
1. Land	Use Farki	ing lot oodland, agricultu	ural field, vacant lot, e	etc.)	None Vegetation			Many large	es (e.g., cobbles,	stones, boulder	rs. etc.)	0-2 Slope (%)	
De	, -		See attached sketch		r ogotatio				.e (e.g., ee.z.ee,	otooo, bouluo.	.0, 010.)	0.565 (75)	
2. Soil F	Parent Materia	al: <u>Till</u>			1	ndform		Deel	l	(CII CII DC	FC TO)		
. 5.	,	•	W . D .	> 25					tion on Landscar			. 25	
3. Dista	nces from:	•	n Water Body _				•		feet		•	>25 feet	
			Property Line _				•	Vell <u>N/A</u>				feet	
1. Unsuita	able Material	s Present: L] Yes 🗓 No	If Yes:	☐ Disturbed S	Soil 🗌	Fill Materia	ıl 🗌 '	Weathered/Fra	ctured Rock	☐ Bedr	rock	
5 Groui	ndwater Ohse	erved: X Yes			If ves	: 68"	Danth Was	unio au franco Dit		Danth C	`**	utan in I lala	
o. Oroui	iawatoi Obot	51VCG. [21] 1CG			ii yoo			eping from Pit	_	Depth S	standing vva	iter in Hole	
	<u> </u>	T	Τ	I		Soil Log	<i>.</i>	Fragments	T		1		
Depth (in)	Soil Horizon	Soil Texture	Soil Matrix: Color-	Redoximorphic Fea		w by Volume		Volume	Soil Structure	Soil Consistence		Other	
Deptii (iii)	/Layer	(USDA	Moist (Munsell)	Depth	Color	Percent	Gravel	Cobbles & Stones	Son Structure	(Moist)		Other	
0-27	Fill												
27-38			103/02/2										
21-36	A	Sandy Loam	10YR3/2						Massive	Friable			
38-44	В	Sandy Loam	10YR3/4						Massive	Friable			
30 11	ь	Sandy Loam	1011(3/1		High and				TVIUSSI V C	TTIAUIC			
44-84	С	Sandy Loam	10YR5/2	44"	Low Chroma	>2	2	10	Massive	Friable			
		1			1								
Addit	ional Notes:												



ACC 240				•						•		
C. On-	Site Revi	iew (minim	um of two hole	es requ	iired at ever	y propo	sed prin	nary and r	eserve disp	osal area))	
Deep	Observation	n Hole Numb	er: <u>TP-2</u>	08/06 Date	/20	7:45	AM	70*, su	ınny			
·			Hole #	Date		Time		Weather		Latitude		Longitude:
1. Land	Use Farki	ing lot oodland, agricultu	ural field, vacant lot, e	etc.)	None Vegetation			Many large	es (e.g., cobbles,	stones, boulder	rs. etc.)	0-2 Slope (%)
Do	, •		see attached sketch	,	vogotation			ourrace otoric	.o (c.g., cobbics,	otorico, boulder	10, 010.)	Ciopo (70)
2. Soil F	Parent Materia	al: <u>Till</u>			1	ndform		- Dee:		(CIL CIL DC	FC TC)	
				× 25					tion on Landscap			. 25
3. Dista	nces from:	•	n Water Body _				·		feet		•	>25 feet
			Property Line _				_	Vell N/A			-	feet
1. Unsuita	able Material	s Present:] Yes 🗓 No	If Yes:	☐ Disturbed S	oil 🗌	Fill Materia	ıl 🔲 '	Weathered/Fra	ctured Rock	☐ Bedr	ock
5 Groui	ndwater Ohse	erved: Yes	X No		If ves	,-	Destile Mes			Danith O	N	tanda Hala
J. Gloui	nawater Obse	erved res	E NO		ii yes			eping from Pit	_	Depth S	standing Wa	ter in Hole
	1	Г	Г	Τ		Soil Log			T	I	1	
Depth (in)	Soil Horizon /Layer	Soil Texture (USDA	Soil Matrix: Color- Moist (Munsell)	- Redoximorphic Feat		% by volume		Soil Structure	Soil	Other		
Depth (in)				Depth	Color	Percent	Gravel	Cobbles & Stones	Son Structure	(Moist)		Other
								0.000				
0-16	Fill											
16-30		G 1 T	10VD2/2						Mari	F		
10-30	A	Sandy Loam	10YR3/2		TT: 1 1				Massive	Friable		
30-43	В	Sandy Loam	10YR6/6	30"	High and Low Chroma	>2			Massive	Friable		
30 43	В	Sandy Loani	10110/0		Low Cilionia				Widsive	THADIC		
43-60	С	Sandy Loam	10YR5/3				2	10	Massive	Friable		
								1				
Additi	ional Notes:											




Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

Deck	Observation	n Hole Numb		08/06	5/20	8:00 /	AM	_70*, su					
	Park	ing lot	Hole #	Date	None	Time		Weather Many large		Latitude		Longitude: 0-2	
I. Land	Use $\frac{1 \text{ ark}}{\text{(e.g., we}}$	oodland, agricultu	ural field, vacant lot, e	etc.)	Vegetation				s (e.g., cobbles,	stones, boulder	rs, etc.)	Slope (%)	
De	scription of Lo	ocation: S	See attached sketch	·	-							. , ,	
2. Soil F	Parent Materia	al: <u>Till</u>				ndform		Posi	tion on Landscap	e (SII SH BS	FS TS)		
Nieta	nces from:	Oner	n Water Body	>25 fo			rainaga M		feet	•	•	>25 feet	
. Dista	nices nom.	•	· -				-	-				<u> </u>	
Lloouit	abla Matarial		Property Line $_$								Other	feet	
. Onsult	abie ivialeriai	s rieseiil. L	JIES [∆] INU	ii res:		OII 🔲 l	riii iviateriai	· 📙 \	veamered/Fra	ciurea Rock	⊔ вес	JIOCK	
. Grou	ndwater Obse	erved: Yes	X No		If yes	:	Depth Wee	ping from Pit		Depth S	tanding W	Vater in Hole	
						Soil Log		. 5	_		3		
				Red	loximorphic Fea	Ecatures Coars		Fragments		Soil			
Depth (in)	Soil Horizon /Layer	Soil Texture (USDA	re Soil Matrix: Color- Moist (Munsell)		1	·		Volume Cobbles &		Consistence		Other	
	,	(232).		Depth	Color	Percent	Gravel	Stones		(Moist)			
							1						
0-9	Fill												
0-9	Fill												
0-9 9-25	Fill B	Sandy Loam	10YR6/6						Massive	Friable			
9-25					High and				Massive	Friable			
		Sandy Loam Sandy Loam		32"	High and Low Chroma	>2	2	10	Massive Massive	Friable Friable			
9-25	В			32"	_	>2	2	10					
9-25	В			32"	_	>2	2	10					
9-25	В			32"	_	>2	2	10					
9-25	В			32"	_	>2	2	10					
9-25	В			32"	_	>2	2	10					
9-25	В			32"	_	>2	2	10					

Additional Notes:



A 100 Person										•			
C. On-	Site Revi	iew (minim	num of two hole	es requ	iired at ever	y propo	sed prin	nary and r	eserve disp	osal area))		
Deep	Observation	n Hole Numb	er: _TP-4_	08/06	/20	8:30	AM	70*, su	ınny				
·			Hole #	Date		Time		Weather		Latitude		Longitude:	
1. Land	Use Parki	ing lot	ural field, vacant lot, e	atc)	None Vegetation			Many large	e boulders es (e.g., cobbles,	etones houlder	re etc.)	0-2 Slope (%)	
	(ö.g., 		See attached sketch		vegetation			Surface Storie	es (e.g., cobbles,	Stories, boulder	13, 610.)	Slope (70)	
De	scription of Lo	ocation	see attached sketch	1									
2. Soil F	Parent Materia	al: <u>Till</u>				ndform		Deet		(CII CII DC	FC TC)		
	_			× 25					tion on Landscap			. 25	
3. Dista	nces from:	•	n Water Body _				•		feet			<u>>25</u> feet	
			Property Line _				_	Vell N/A	feet	(Other	feet	
4. Unsuita	able Material	s Present:] Yes 🗓 No	If Yes:	☐ Disturbed S	ioil 🗌	Fill Materia	ıl 🔲 '	Weathered/Fra	ctured Rock	Bec	lrock	
5 Groun	ndwator Obco	erved: Yes	s 🗓 No		If you	· •							
J. Gloui	nuwater Obse	erveu. 🔝 Tes	S A INU					eping from Pit	-	Depth S	Standing W	ater in Hole	
	T	ľ	1	1		Soil Log	<u> </u>		1	ı	ı		
Daniel Co.	Soil Horizon	Soil Texture	Soil Matrix: Color-	Redoximorphic Featu		tures	es Coarse Fragments % by Volume		Coll Church	Soil		Other	
Depth (in)	/Layer	(USDA	Moist (Munsell)	Depth	Color	Percent	Gravel	Cobbles & Stones	Soil Structure	(Moist)		Other	
0-12	Fill												
					High and								
12-61	C	Sandy Loam	10YR5/3	24"	Low Chroma	>2	2	10	Massive	Friable			
_													
		ı	1	1	1	<u>l</u>	1		I	l	<u>l</u>		
Addit	ional Notes:												



F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

and the state of t	08/06/20					
Signature of Soil Evaluator	Date					
William Hall, P.E., S.E. 13592	06/31/21					
Typed or Printed Name of Soil Evaluator / License #	Expiration Date of License					
Leyna Tobey - Woodard & Curran	N/A					
Name of Approving Authority Witness	Approving Authority					

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with <u>Percolation Test Form 12</u>.


Field Diagrams: Use this area for field diagrams:

See attached sketch






APPENDIX C: **STORMWATER FIGURES**



JOB NO: 0233115.00 DATE: OCTOBER 2020 SCALE: AS NOTED




PHASE

ARLINGTON RESERVOIR

JOB NO: 0233115.00 DATE: OCTOBER 2020 SCALE: AS NOTED



APPENDIX D: **HYDROCAD STORMWATER MODEL REPORTS**



Printed 10/6/2020 Page 2

Area Listing (all nodes)

Are	a CN	Description
(acres	5)	(subcatchment-numbers)
1.53	1 49	50-75% Grass cover, Fair, HSG A (1, 2)
1.31	7 63	Beach Sand, HSG A (1)
0.37	9 30	Brush, Good, HSG A (1, 2)
0.04	6 96	Dense Sand Path, HSG A (1)
0.64	6 98	Gravel parking, HSG A (1, 2)
0.23	4 98	Impervious Surface, HSG A (1, 2)
0.05	5 39	Open Space, Good, HSG A (>75% Grass Cover) (1)
1.20	7 98	Water Surface, HSG A (1)
5.41	6 70	TOTAL AREA

2020.10.06 Existing - Arlington Res
Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
5.416	HSG A	1, 2
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.000	Other	
5.416		TOTAL AREA

2020.10.06 Existing - Arlington Res
Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 4

Ground Covers (all nodes)

HSG-A	HSG-B	HSG-C	HSG-D	Other	Total	Ground	Subcatchment
 (acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Cover	Numbers
1.531	0.000	0.000	0.000	0.000	1.531	50-75% Grass cover, Fair	1, 2
1.317	0.000	0.000	0.000	0.000	1.317	Beach Sand	1
0.379	0.000	0.000	0.000	0.000	0.379	Brush, Good	1, 2
0.046	0.000	0.000	0.000	0.000	0.046	Dense Sand Path	1
0.646	0.000	0.000	0.000	0.000	0.646	Gravel parking	1, 2
0.234	0.000	0.000	0.000	0.000	0.234	Impervious Surface	1, 2
0.055	0.000	0.000	0.000	0.000	0.055	Open Space, Good	1
1.207	0.000	0.000	0.000	0.000	1.207	Water Surface	1
5.416	0.000	0.000	0.000	0.000	5.416	TOTAL AREA	

Type III 24-hr 1-Year Rainfall=2.67"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 5

Printed 10/6/2020

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=0.58"

Tc=6.0 min CN=71 Runoff=2.96 cfs 0.251 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=0.33"

Tc=6.0 min CN=64 Runoff=0.04 cfs 0.006 af

Link DP-1: Reservoir and Swimming Area Inflow=2.96 cfs 0.251 af

Primary=2.96 cfs 0.251 af

Link DP-2: Ditch Inflow=0.04 cfs 0.006 af

Primary=0.04 cfs 0.006 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.257 af Average Runoff Depth = 0.57" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 6


Summary for Subcatchment 1: Subcatchment 1

Runoff = 2.96 cfs @ 12.10 hrs, Volume= 0.251 af, Depth= 0.58"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Α	rea (sf)	CN	Description					
		14,435	30	Brush, Good, HSG A					
*		57,370	63	Beach Sand	d, HSG A				
*		1,998	96	Dense San	d Path, HS	G A			
		63,530	49	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel parking, HSG A					
*		9,994	98	Impervious Surface, HSG A					
		52,585	98	Water Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)			
	2	27,252	71	Weighted A	verage				
	1	39,746		61.49% Per	vious Area				
		87,506		38.51% Imp	ervious Ar	ea			
				•					
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)				
<u></u>	6.0	•				Direct Entry,			

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 7


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.04 cfs @ 12.13 hrs, Volume= 0.006 af, Depth= 0.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Α	rea (sf)	CN	Description					
		2,076	30	Brush, Good, HSG A					
	3,179 49 50-75% Grass cover, Fair, HSG A				50-75% Grass cover, Fair, HSG A				
*		3,211	98	Gravel parking, HSG A					
		215	98	Impervious	Surface, H	HSG A			
		8,681	64	Weighted Average					
		5,255		60.53% Pervious Area					
		3,426		39.47% Imp	pervious Ar	rea			
	Tc	Length	Slope	e Velocity	Capacity	Description			
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)	<u> </u>			
	6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 8

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 0.58" for 1-Year event

Inflow = 2.96 cfs @ 12.10 hrs, Volume= 0.251 af

Primary = 2.96 cfs @ 12.10 hrs, Volume= 0.251 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 9

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 0.33" for 1-Year event

Inflow = 0.04 cfs @ 12.13 hrs, Volume= 0.006 af

Primary = 0.04 cfs @ 12.13 hrs, Volume= 0.006 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 2-Year Rainfall=3.21"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 10

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=0.88"

Tc=6.0 min CN=71 Runoff=4.93 cfs 0.384 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=0.56"

Tc=6.0 min CN=64 Runoff=0.10 cfs 0.009 af

Link DP-1: Reservoir and Swimming Area Inflow=4.93 cfs 0.384 af

Primary=4.93 cfs 0.384 af

Link DP-2: Ditch Inflow=0.10 cfs 0.009 af

Primary=0.10 cfs 0.009 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.394 af Average Runoff Depth = 0.87" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 11


Summary for Subcatchment 1: Subcatchment 1

Runoff = 4.93 cfs @ 12.10 hrs, Volume= 0.384 af, Depth= 0.88"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Α	rea (sf)	CN	Description					
		14,435	30	Brush, Good, HSG A					
*		57,370	63	Beach Sand	Beach Sand, HSG A				
*		1,998	96	Dense Sand Path, HSG A					
		63,530	49	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	Gravel parking, HSG A				
*		9,994	98	Impervious	Impervious Surface, HSG A				
		52,585	98	Water Surfa	Water Surface, HSG A				
*		2,413	39	Open Space	Open Space, Good, HSG A (>75% Grass Cover)				
	2	27,252	71	Weighted A	verage				
	1	39,746		61.49% Per	vious Area				
		87,506		38.51% Imp	ervious Ar	ea			
	Tc	Length	Slop	e Velocity	Capacity	Description			
_	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 12


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.10 cfs @ 12.11 hrs, Volume= 0.009 af, Depth= 0.56"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Α	rea (sf)	CN	Description					
		2,076	30	Brush, Good, HSG A					
	3,179 49 50-75% Grass cover, Fair, HSG A				50-75% Grass cover, Fair, HSG A				
*		3,211	98	Gravel parking, HSG A					
		215	98	Impervious	Surface, H	HSG A			
		8,681	64	Weighted Average					
		5,255		60.53% Pervious Area					
		3,426		39.47% Imp	pervious Ar	rea			
	Tc	Length	Slope	e Velocity	Capacity	Description			
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)	<u> </u>			
	6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 13

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 0.88" for 2-Year event

Inflow = 4.93 cfs @ 12.10 hrs, Volume= 0.384 af

Primary = 4.93 cfs @ 12.10 hrs, Volume= 0.384 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 14

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 0.56" for 2-Year event

Inflow = 0.10 cfs @ 12.11 hrs, Volume= 0.009 af

Primary = 0.10 cfs @ 12.11 hrs, Volume= 0.009 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 10-Year Rainfall=4.86"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 15

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=2.01"

Tc=6.0 min CN=71 Runoff=12.11 cfs 0.874 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=1.49"

Tc=6.0 min CN=64 Runoff=0.33 cfs 0.025 af

Link DP-1: Reservoir and Swimming Area Inflow=12.11 cfs 0.874 af Primary=12.11 cfs 0.874 af

1 11111ai y = 12.11 013 0.074 ai

Link DP-2: Ditch Inflow=0.33 cfs 0.025 af

Primary=0.33 cfs 0.025 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.899 af Average Runoff Depth = 1.99" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 16


Summary for Subcatchment 1: Subcatchment 1

Runoff = 12.11 cfs @ 12.09 hrs, Volume= 0.874 af, Depth= 2.01"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Α	rea (sf)	CN	Description					
		14,435	30	Brush, Good, HSG A					
*		57,370	63	Beach Sand	d, HSG A				
*		1,998	96	Dense Sand	Dense Sand Path, HSG A				
		63,530	49	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	Gravel parking, HSG A				
*		9,994	98	Impervious	Impervious Surface, HSG A				
		52,585	98	Water Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)			
	2	27,252	71	Weighted A	verage				
	1	39,746		61.49% Per	vious Area	1			
		87,506		38.51% Imp	ervious Ar	ea			
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)				
<u></u>	6.0		•			Direct Entry,			

Subcatchment 1: Subcatchment 1



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 17


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.33 cfs @ 12.10 hrs, Volume= 0.025 af, Depth= 1.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Α	rea (sf)	CN	Description					
-		2,076	30	Brush, Good, HSG A					
		3,179	49	, ,					
*		3,211	98	Gravel parking, HSG A					
		215	98	Impervious	Surface, H	HSG A			
		8,681	64	Weighted Average					
		5,255		60.53% Pervious Area					
		3,426		39.47% Imp	pervious Ar	ırea			
	Tc	Length	Slop	e Velocity	Capacity	/ Description			
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 18

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 2.01" for 10-Year event

Inflow = 12.11 cfs @ 12.09 hrs, Volume= 0.874 af

Primary = 12.11 cfs @ 12.09 hrs, Volume= 0.874 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 19

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 1.49" for 10-Year event

Inflow = 0.33 cfs @ 12.10 hrs, Volume= 0.025 af

Primary = 0.33 cfs @ 12.10 hrs, Volume= 0.025 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 25-Year Rainfall=6.17"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 20

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=3.04"

Tc=6.0 min CN=71 Runoff=18.53 cfs 1.320 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=2.39"

Tc=6.0 min CN=64 Runoff=0.54 cfs 0.040 af

Link DP-1: Reservoir and Swimming Area Inflow=18.53 cfs 1.320 af

Primary=18.53 cfs 1.320 af

Link DP-2: Ditch Inflow=0.54 cfs 0.040 af

Primary=0.54 cfs 0.040 af

Total Runoff Area = 5.416 ac Runoff Volume = 1.360 af Average Runoff Depth = 3.01" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 21


Summary for Subcatchment 1: Subcatchment 1

Runoff = 18.53 cfs @ 12.09 hrs, Volume= 1.320 af, Depth= 3.04"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Α	rea (sf)	CN	Description					
		14,435	30	Brush, Good, HSG A					
*		57,370	63	Beach Sand	Beach Sand, HSG A				
*		1,998	96	Dense Sand Path, HSG A					
		63,530	49	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	Gravel parking, HSG A				
*		9,994	98	Impervious	Impervious Surface, HSG A				
		52,585	98	Water Surfa	Water Surface, HSG A				
*		2,413	39	Open Space	Open Space, Good, HSG A (>75% Grass Cover)				
	2	27,252	71	Weighted A	verage				
	1	39,746		61.49% Per	vious Area				
		87,506		38.51% Imp	ervious Ar	ea			
	Tc	Length	Slop	e Velocity	Capacity	Description			
_	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 1: Subcatchment 1



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 22


Summary for Subcatchment 2: Subcatchment 2

Runoff 0.54 cfs @ 12.09 hrs, Volume= 0.040 af, Depth= 2.39"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Ar	ea (sf)	CN	Description					
		2,076	30	Brush, Good, HSG A					
		3,179	49	49 50-75% Grass cover, Fair, HSG A					
*		3,211	98	Gravel parking, HSG A					
		215	98	Impervious Surface, HSG A					
		8,681	64	Weighted Average					
		5,255		60.53% Pervious Area					
		3,426		39.47% Imp	ervious Ar	ea			
	Tc	Length	Slope	e Velocity	Capacity	Description			
(m	nin)	(feet)	(ft/ft) (ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



Type III 24-hr 25-Year Rainfall=6.17"

Printed 10/6/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC Page 23

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 3.04" for 25-Year event

Inflow = 18.53 cfs @ 12.09 hrs, Volume= 1.320 af

Primary = 18.53 cfs @ 12.09 hrs, Volume= 1.320 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 24

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 2.39" for 25-Year event

Inflow = 0.54 cfs @ 12.09 hrs, Volume= 0.040 af

Primary = 0.54 cfs @ 12.09 hrs, Volume= 0.040 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 100-Year Rainfall=8.85" Printed 10/6/2020

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 25

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=5.33"

Tc=6.0 min CN=71 Runoff=32.53 cfs 2.315 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=4.47"

Tc=6.0 min CN=64 Runoff=1.04 cfs 0.074 af

Link DP-1: Reservoir and Swimming Area Inflow=32.53 cfs 2.315 af

Primary=32.53 cfs 2.315 af

Link DP-2: Ditch Inflow=1.04 cfs 0.074 af

Primary=1.04 cfs 0.074 af

Total Runoff Area = 5.416 ac Runoff Volume = 2.389 af Average Runoff Depth = 5.29" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 26


Summary for Subcatchment 1: Subcatchment 1

Runoff = 32.53 cfs @ 12.09 hrs, Volume= 2.315 af, Depth= 5.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Α	rea (sf)	CN	Description					
		14,435	30	Brush, Good, HSG A					
*		57,370	63	Beach Sand	d, HSG A				
*		1,998	96	Dense Sand	Dense Sand Path, HSG A				
		63,530	49	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	Gravel parking, HSG A				
*		9,994	98	Impervious	Impervious Surface, HSG A				
		52,585	98	Water Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)			
	2	27,252	71	Weighted A	verage				
	1	39,746		61.49% Per	vious Area	1			
		87,506		38.51% Imp	ervious Ar	ea			
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)				
<u></u>	6.0		•			Direct Entry,			

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 27


Summary for Subcatchment 2: Subcatchment 2

Runoff = 1.04 cfs @ 12.09 hrs, Volume= 0.074 af, Depth= 4.47"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Α	rea (sf)	CN	Description				
		2,076 30 Brush, Good, HSG A						
		3,179	49	50-75% Grass cover, Fair, HSG A				
*		3,211	98	Gravel parking, HSG A				
		215	98	Impervious	Surface, H	HSG A		
		8,681	64	4 Weighted Average				
		5,255		60.53% Pervious Area				
		3,426		39.47% Imp	pervious Ar	rea		
	Tc	Length	Slope	e Velocity	Capacity	Description		
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)			
	6.0					Direct Entry,		

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 28

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 5.33" for 100-Year event

Inflow = 32.53 cfs @ 12.09 hrs, Volume= 2.315 af

Primary = 32.53 cfs @ 12.09 hrs, Volume= 2.315 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 29

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 4.47" for 100-Year event


Inflow = 1.04 cfs @ 12.09 hrs, Volume= 0.074 af

Primary = 1.04 cfs @ 12.09 hrs, Volume= 0.074 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch





Printed 10/6/2020 Page 2

Area Listing (selected nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
1.573	39	>75% Grass cover, Good, HSG A (1A, 1B, 2)
1.029	63	Beach Sand, HSG A (1A)
0.304	30	Brush, Good, HSG A (1A)
0.467	98	Impervious Surface, HSG A (1A, 1B)
0.184	39	Permeable Playground Surface, Good, HSG A (1A)
0.521	98	Porous Pavement, HSG A (1A, 1B)
0.138	96	Stone Dust, HSG A (1A)
1.200	98	Water Surface, HSG A (1A)
5.416	68	TOTAL AREA

2020.10.06 Proposed - Arlington ResPrepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 3

Soil Listing (selected nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
5.416	HSG A	1A, 1B, 2
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.000	Other	
5.416		TOTAL AREA

2020.10.06 Proposed - Arlington ResPrepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 4

Ground Covers (selected nodes)

HSG-A	HSG-B	HSG-C	HSG-D	Other	Total	Ground	Subcatch
(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Cover	Numbers
1.573	0.000	0.000	0.000	0.000	1.573	>75% Grass cover, Good	
1.029	0.000	0.000	0.000	0.000	1.029	Beach Sand	
0.304	0.000	0.000	0.000	0.000	0.304	Brush, Good	
0.467	0.000	0.000	0.000	0.000	0.467	Impervious Surface	
0.184	0.000	0.000	0.000	0.000	0.184	Permeable Playground Surface,	
						Good	
0.521	0.000	0.000	0.000	0.000	0.521	Porous Pavement	
0.138	0.000	0.000	0.000	0.000	0.138	Stone Dust	
1.200	0.000	0.000	0.000	0.000	1.200	Water Surface	
5.416	0.000	0.000	0.000	0.000	5.416	TOTAL AREA	

2020.10.06 Proposed - Arlington ResPrepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 5

Pipe Listing (selected nodes)

Line#	Node	In-Invert	Out-Invert	Length	Slope	n	Diam/Width	Height	Inside-Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	P1	162.15	162.05	20.0	0.0050	0.013	12.0	0.0	0.0

2020.10.06 Proposed - Arlington Res

Type III 24-hr 1-Year Rainfall=2.67"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 6

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=0.43"

Tc=6.0 min CN=67 Runoff=1.65 cfs 0.166 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=1.07"

Tc=6.0 min CN=81 Runoff=0.84 cfs 0.061 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.00"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.000 af

Pond P1: Porous Pavement Peak Elev=161.40' Storage=0 cf Inflow=0.84 cfs 0.061 af

Discarded=0.84 cfs 0.061 af Primary=0.00 cfs 0.000 af Outflow=0.84 cfs 0.061 af

Link DP-1: Reservoir and Swimming Area Inflow=1.65 cfs 0.166 af

Primary=1.65 cfs 0.166 af

Link DP-2: Ditch Inflow=0.00 cfs 0.000 af

Primary=0.00 cfs 0.000 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.227 af Average Runoff Depth = 0.50" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Printed 10/6/2020

Page 7


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff 1.65 cfs @ 12.11 hrs, Volume= 0.166 af, Depth= 0.43"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Good, HSG A					
*		44,830	63	Beach Sand	d, HSG A				
		56,001	39	>75% Gras	s cover, Go	ood, HSG A			
		19,764	98	Impervious	Surface, H	SG A			
*		1,800	98	Porous Pav	ement, HS	G A			
		52,292	98	Water Surfa	ace, HSG A				
*		6,010	96	Stone Dust,	HSG A				
*		8,011	39	Permeable	Playground	Surface, Good, HSG A			
	2	201,945	67	Weighted A	verage				
	1	28,089		63.43% Per	vious Area				
		73,856		36.57% Imp	ervious Ar	ea			
	Tc	Length	Slop	e Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Printed 10/6/2020

Page 8


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 0.84 cfs @ 12.09 hrs, Volume= 0.061 af, Depth= 1.07"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Area (sf) CN	Description	Description					
	8,41 ⁻	1 39	>75% Gras	>75% Grass cover, Good, HSG A					
	574	4 98	Impervious	Impervious Surface, HSG A					
*	20,888	98	Porous Pav	Porous Pavement, HSG A					
	29,873	3 81	Weighted A	Weighted Average					
	8,41 ⁻	1	28.16% Per	28.16% Pervious Area					
	21,462	2	71.84% Imp	ervious Ar	ea				
	Tc Leng	th Slo	pe Velocity	e Velocity Capacity Description					
	(min) (fee	et) (ft/	ft) (ft/sec)	(ft/sec) (cfs)					
	6.0			•	Direct Entry.				

Subcatchment 1B: Area Draining to Parking Lot



Page 9

Summary for Subcatchment 2: Subcatchment 2


[45] Hint: Runoff=Zero

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

_	Α	rea (sf)	CN I	Description					
		4,115	39 >	>75% Grass cover, Good, HSG A					
		4,115		100.00% Pervious Area					
	To	Length	Slope	Velocity	Canacity	Description			
	(min)	(feet)	(ft/ft)						
-	6.0	, ,	Direct Entry.						

Subcatchment 2: Subcatchment 2



Printed 10/6/2020

Page 10

Summary for Pond P1: Porous Pavement

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 1.07" for 1-Year event

Inflow = 0.84 cfs @ 12.09 hrs, Volume= 0.061 af

Outflow = 0.84 cfs @ 12.09 hrs, Volume= 0.061 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.40' @ 12.09 hrs Surf.Area= 21,411 sf Storage= 0 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 0.0 min (849.0 - 849.0)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Elevation	Surf.Area	Voids	Inc.Store	Cum.Store
(feet)	(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
162.23	21,411	0.0	0	0
162.48	21,411	40.0	2,141	2,141
162.81	21,411	30.0	2,120	4,261

Device	Routing	Invert	Outlet Devices	
#1	Primary	162.15'	12.0" Round Culvert	
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700	
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900	
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf	
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600	
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area	

Discarded OutFlow Max=1.19 cfs @ 12.09 hrs HW=161.40' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

1=Culvert (Controls 0.00 cfs)

2=Orifice/Grate (Controls 0.00 cfs)

Page 11

Pond P1: Porous Pavement



Page 12

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 0.37" for 1-Year event

Inflow = 1.65 cfs @ 12.11 hrs, Volume= 0.166 af

Primary = 1.65 cfs @ 12.11 hrs, Volume= 0.166 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Page 13

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.00" for 1-Year event

Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 2-Year Rainfall=3.21"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 14

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=0.69"

Tc=6.0 min CN=67 Runoff=3.15 cfs 0.267 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=1.48"

Tc=6.0 min CN=81 Runoff=1.18 cfs 0.084 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.00"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.000 af

Pond P1: Porous Pavement Peak Elev=161.40' Storage=1 cf Inflow=1.18 cfs 0.084 af

Discarded=1.17 cfs 0.084 af Primary=0.00 cfs 0.000 af Outflow=1.17 cfs 0.084 af

Link DP-1: Reservoir and Swimming Area Inflow=3.15 cfs 0.267 af

Primary=3.15 cfs 0.267 af

Link DP-2: Ditch Inflow=0.00 cfs 0.000 af

Primary=0.00 cfs 0.000 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.352 af Average Runoff Depth = 0.78" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Printed 10/6/2020 Page 15


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 3.15 cfs @ 12.10 hrs, Volume= 0.267 af, Depth= 0.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Α	rea (sf)	CN	Description						
		13,237	30	Brush, Goo	Brush, Good, HSG A					
*		44,830	63	Beach Sand, HSG A						
		56,001	39	>75% Gras	s cover, Go	ood, HSG A				
		19,764	98	Impervious	Surface, H	SG A				
*		1,800	98	Porous Pav	ement, HS	G A				
		52,292	98	Water Surfa	ace, HSG A	1				
*		6,010	96	Stone Dust,	HSG A					
*		8,011	39	Permeable	Playground	Surface, Good, HSG A				
	2	201,945	67	Weighted A	verage					
	1	28,089		63.43% Per	vious Area					
		73,856		36.57% Imp	ervious Ar	ea				
	Tc	Length	Slop	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)					
	6.0					Direct Entry,				

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Printed 10/6/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 16


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 1.18 cfs @ 12.09 hrs, Volume= 0.084 af, Depth= 1.48"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Area (sf) CN	Description	Description					
	8,41 ⁻	1 39	>75% Gras	>75% Grass cover, Good, HSG A					
	574	4 98	Impervious	Impervious Surface, HSG A					
*	20,888	98	Porous Pav	Porous Pavement, HSG A					
	29,873	3 81	Weighted A	Weighted Average					
	8,41 ⁻	1	28.16% Per	28.16% Pervious Area					
	21,462	2	71.84% Imp	ervious Ar	ea				
	Tc Leng	th Slo	pe Velocity	e Velocity Capacity Description					
	(min) (fee	et) (ft/	ft) (ft/sec)	(ft/sec) (cfs)					
	6.0			•	Direct Entry.				

Subcatchment 1B: Area Draining to Parking Lot



Page 17


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

A	rea (sf)	CN E	Description			
	4,115	39 >	>75% Grass cover, Good, HSG A			
	4,115	1	100.00% Pervious Area			
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
6.0					Direct Entry,	

Subcatchment 2: Subcatchment 2



Printed 10/6/2020 Page 18

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=547)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 1.48" for 2-Year event
Inflow = 1.18 cfs @ 12.09 hrs, Volume= 0.084 af
Outflow = 1.17 cfs @ 12.10 hrs, Volume= 0.084 af, Atten= 0%, Lag= 0.4 min
Discarded = 1.17 cfs @ 12.10 hrs, Volume= 0.084 af
Primary = 0.00 cfs @ 0.00 hrs. Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.40' @ 12.10 hrs Surf.Area= 21,411 sf Storage= 1 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 0.0 min (839.4 - 839.4)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	(sq-ft) (%) 21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.10 hrs HW=161.40' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Page 19

Pond P1: Porous Pavement



Printed 10/6/2020

Page 20

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 0.60" for 2-Year event

Inflow = 3.15 cfs @ 12.10 hrs, Volume= 0.267 af

Primary = 3.15 cfs @ 12.10 hrs, Volume= 0.267 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 21

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.00" for 2-Year event

Inflow = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af

Primary = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 10-Year Rainfall=4.86"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 22

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=1.71"

Tc=6.0 min CN=67 Runoff=8.92 cfs 0.659 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=2.86"

Tc=6.0 min CN=81 Runoff=2.30 cfs 0.164 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.17"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.001 af

Pond P1: Porous Pavement Peak Elev=161.46' Storage=515 cf Inflow=2.30 cfs 0.164 af

Discarded=1.19 cfs 0.164 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.164 af

Link DP-1: Reservoir and Swimming Area Inflow=8.92 cfs 0.659 af

Primary=8.92 cfs 0.659 af

Link DP-2: Ditch Inflow=0.00 cfs 0.001 af

Primary=0.00 cfs 0.001 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.824 af Average Runoff Depth = 1.83" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Page 23


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 8.92 cfs @ 12.09 hrs, Volume= 0.659 af, Depth= 1.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Α	rea (sf)	CN	Description				
		13,237	30	Brush, Good, HSG A				
*		44,830	63	Beach Sand	d, HSG A			
		56,001	39	>75% Gras	s cover, Go	ood, HSG A		
		19,764	98	Impervious	Surface, H	SG A		
*		1,800	98	Porous Pav	ement, HS	G A		
		52,292	98	Water Surfa	ace, HSG A			
*		6,010	96	Stone Dust, HSG A				
*		8,011	39	Permeable	Playground	Surface, Good, HSG A		
	2	201,945	67	Weighted A	verage			
	1	28,089		63.43% Per	vious Area			
		73,856		36.57% Imp	ervious Ar	ea		
	Tc	Length	Slop	e Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)			
	6.0					Direct Entry,		

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Page 24


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 2.30 cfs @ 12.09 hrs, Volume= 0.164 af, Depth= 2.86"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Area (sf) CN	Description				
	8,41 ⁻	1 39	>75% Gras	s cover, Go	ood, HSG A		
	574	4 98	Impervious	Impervious Surface, HSG A			
*	20,888	98	Porous Pav	ement, HS	G A		
	29,873	3 81	Weighted A	verage			
	8,41 ⁻	1	28.16% Per	28.16% Pervious Area			
	21,462	2	71.84% Imp	71.84% Impervious Area			
	Tc Leng	th Slo	pe Velocity	Capacity	Description		
	(min) (fee	et) (ft/	ft) (ft/sec)	(cfs)			
	6.0			•	Direct Entry.		

Subcatchment 1B: Area Draining to Parking Lot



Page 25


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.00 cfs @ 12.51 hrs, Volume= 0.001 af, Depth= 0.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

_	Α	rea (sf)	CN	Description			
		4,115	39	>75% Grass cover, Good, HSG A			
_		4,115		100.00% Pervious Area			
	Tc (min)	Length (feet)	Slope (ft/ft)	•	Capacity (cfs)	Description	
	6.0					Direct Entry,	

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 26

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=576)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 2.86" for 10-Year event 2.30 cfs @ 12.09 hrs, Volume= 0.164 af

Outflow = 1.19 cfs @ 12.09 hrs, Volume= 0.164 af, Atten= 48%, Lag= 0.1 min

Discarded = 1.19 cfs @ 12.09 hrs, Volume= 0.164 af Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.46' @ 12.23 hrs Surf.Area= 21,411 sf Storage= 515 cf

Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 1.6 min (821.9 - 820.3)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Elevation	Surf.Area	Voids	Inc.Store	Cum.Store
(feet)	(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
162.23	21,411	0.0	0	0
162.48	21,411	40.0	2,141	2,141
162.81	21,411	30.0	2,120	4,261

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	·		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.09 hrs HW=161.43' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Page 27

Pond P1: Porous Pavement



Page 28

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 1.49" for 10-Year event

Inflow = 8.92 cfs @ 12.09 hrs, Volume= 0.659 af

Primary = 8.92 cfs @ 12.09 hrs, Volume= 0.659 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Page 29

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.17" for 10-Year event

Inflow 0.00 cfs @ 12.51 hrs, Volume= 0.001 af

0.00 cfs @ 12.51 hrs, Volume= Primary 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 25-Year Rainfall=6.17"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 30

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=2.66"

Tc=6.0 min CN=67 Runoff=14.29 cfs 1.027 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=4.04"

Tc=6.0 min CN=81 Runoff=3.22 cfs 0.231 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.50"

Tc=6.0 min CN=39 Runoff=0.02 cfs 0.004 af

Pond P1: Porous Pavement Peak Elev=161.55' Storage=1,280 cf Inflow=3.22 cfs 0.231 af

Discarded=1.19 cfs 0.231 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.231 af

Link DP-1: Reservoir and Swimming Area Inflow=14.29 cfs 1.027 af

Primary=14.29 cfs 1.027 af

Link DP-2: Ditch Inflow=0.02 cfs 0.004 af

Primary=0.02 cfs 0.004 af

Total Runoff Area = 5.416 ac Runoff Volume = 1.262 af Average Runoff Depth = 2.80" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Page 31


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 14.29 cfs @ 12.09 hrs, Volume= 1.027 af, Depth= 2.66"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Α	rea (sf)	CN	Description				
		13,237	30	Brush, Good, HSG A				
*		44,830	63	Beach Sand	d, HSG A			
		56,001	39	>75% Gras	s cover, Go	ood, HSG A		
		19,764	98	Impervious	Surface, H	SG A		
*		1,800	98	Porous Pav	ement, HS	G A		
		52,292	98	Water Surfa	ace, HSG A	1		
*		6,010	96	Stone Dust, HSG A				
*		8,011 39 Permeable Playground Surface			Playground	Surface, Good, HSG A		
	2	201,945	67	Weighted A	verage			
	1	28,089		63.43% Per	vious Area			
	73,856 36.57% Imperv			36.57% Imp	ervious Ar	ea		
	Tc	Length	Slop	e Velocity	Capacity	Description		
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)			
	6.0					Direct Entry,		

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Page 32


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 3.22 cfs @ 12.09 hrs, Volume= 0.231 af, Depth= 4.04"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Α	rea (sf)	CN	Description				
_		8,411	39	>75% Grass cover, Good, HSG A				
		574	98	Impervious Surface, HSG A				
*		20,888	98	Porous Pav	ement, HS	G A		
		29,873	81	Weighted Average				
		8,411		28.16% Pervious Area				
		21,462		71.84% Impervious Area				
	Тс	Length	Slope	e Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)			
	6.0					Direct Entry.		

Subcatchment 1B: Area Draining to Parking Lot



2020.10.06 Proposed - Arlington Res

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 33


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.02 cfs @ 12.33 hrs, Volume= 0.004 af, Depth= 0.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

A	rea (sf)	CN E	Description				
	4,115	39 >	>75% Grass cover, Good, HSG A				
	4,115	100.00% Pervious Area					
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
6.0					Direct Entry,		

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

Printed 10/6/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 34

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=560)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 4.04" for 25-Year event

Inflow = 3.22 cfs @ 12.09 hrs, Volume= 0.231 af

Outflow = 1.19 cfs @ 12.04 hrs, Volume= 0.231 af, Atten= 63%, Lag= 0.0 min

Discarded = 1.19 cfs @ 12.04 hrs, Volume= 0.231 af

Primary = 0.00 cfs @ 0.00 hrs. Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.55' @ 12.35 hrs Surf.Area= 21,411 sf Storage= 1,280 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 4.6 min (815.0 - 810.4)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	(sq-ft) (%) 21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.04 hrs HW=161.43' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Page 35

Pond P1: Porous Pavement



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 36

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 2.32" for 25-Year event

Inflow = 14.29 cfs @ 12.09 hrs, Volume= 1.027 af

Primary = 14.29 cfs @ 12.09 hrs, Volume= 1.027 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Page 37

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.50" for 25-Year event

Inflow = 0.02 cfs @ 12.33 hrs, Volume= 0.004 af

Primary = 0.02 cfs @ 12.33 hrs, Volume= 0.004 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 100-Year Rainfall=8.85"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 38

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=4.84"

Tc=6.0 min CN=67 Runoff=26.30 cfs 1.868 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=6.55"

Tc=6.0 min CN=81 Runoff=5.13 cfs 0.374 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=1.53"

Tc=6.0 min CN=39 Runoff=0.13 cfs 0.012 af

Pond P1: Porous Pavement Peak Elev=161.81' Storage=3,521 cf Inflow=5.13 cfs 0.374 af

Discarded=1.19 cfs 0.374 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.374 af

Link DP-1: Reservoir and Swimming Area Inflow=26.30 cfs 1.868 af

Primary=26.30 cfs 1.868 af

Link DP-2: Ditch Inflow=0.13 cfs 0.012 af

Primary=0.13 cfs 0.012 af

Total Runoff Area = 5.416 ac Runoff Volume = 2.255 af Average Runoff Depth = 5.00" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 39


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 26.30 cfs @ 12.09 hrs, Volume= 1.868 af, Depth= 4.84"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Α	rea (sf)	CN	Description		
		13,237	30	Brush, Goo	d, HSG A	
*		44,830	63	Beach Sand	d, HSG A	
		56,001	39	>75% Gras	s cover, Go	ood, HSG A
		19,764	98	Impervious	Surface, H	SG A
*		1,800	98	Porous Pav	ement, HS	G A
		52,292	98	Water Surfa	ace, HSG A	1
*		6,010	96	Stone Dust,	HSG A	
*		8,011	39	39 Permeable Playground Surface, Good, HSG A		
	2	201,945	67	Weighted A	verage	
	1	28,089		63.43% Per	vious Area	
		73,856		36.57% Imp	ervious Ar	ea
	Tc	Length	Slop	e Velocity	Capacity	Description
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)	
	6.0					Direct Entry,

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



2020.10.06 Proposed - Arlington Res

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 40


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 5.13 cfs @ 12.09 hrs, Volume= 0.374 af, Depth= 6.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Α	rea (sf)	CN	Description				
_		8,411	39	>75% Grass cover, Good, HSG A				
		574	98	Impervious	Surface, H	SG A		
*		20,888	98	Porous Pav	ement, HS	G A		
		29,873	81	1 Weighted Average				
		8,411		28.16% Pervious Area				
		21,462		71.84% Impervious Area				
	Тс	Length	Slope	e Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)			
	6.0					Direct Entry.		

Subcatchment 1B: Area Draining to Parking Lot



2020.10.06 Proposed - Arlington Res

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 41


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.13 cfs @ 12.11 hrs, Volume= 0.012 af, Depth= 1.53"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

A	rea (sf)	CN E	escription				
	4,115	39 >	>75% Grass cover, Good, HSG A				
	4,115	1	100.00% Pervious Area				
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
6.0					Direct Entry,		

Subcatchment 2: Subcatchment 2



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 42

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=514)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 6.55" for 100-Year event

Inflow = 5.13 cfs @ 12.09 hrs, Volume= 0.374 af

Outflow = 1.19 cfs @ 11.92 hrs, Volume= 0.374 af, Atten= 77%, Lag= 0.0 min

Discarded = 1.19 cfs @ 11.92 hrs, Volume= 0.374 af

Primary = 0.00 cfs @ 0.00 hrs. Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.81' @ 12.48 hrs Surf.Area= 21,411 sf Storage= 3,521 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 14.9 min (811.7 - 796.9)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	(sq-ft) (%) 21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 11.92 hrs HW=161.43' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)


-1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 43

Pond P1: Porous Pavement



Page 44

2020.10.06 Proposed - Arlington Res

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 4.21" for 100-Year event

Inflow = 26.30 cfs @ 12.09 hrs, Volume= 1.868 af

Primary = 26.30 cfs @ 12.09 hrs, Volume= 1.868 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 45

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 1.53" for 100-Year event

Inflow = 0.13 cfs @ 12.11 hrs, Volume= 0.012 af

Primary = 0.13 cfs @ 12.11 hrs, Volume= 0.012 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch





APPENDIX E: OPERATIONS & MAINTENANCE PLAN

STORMWATER MANAGEMENT SYSTEM OPERATION & MAINTENANCE PLAN

This Stormwater Management System Operations & Maintenance Plan (the Plan) outlines measures that are essential for maintaining an effective stormwater management system at the Arlington Reservoir, located at 210 Lowell Street in Arlington, Massachusetts (the Site). Periodic and scheduled inspections and maintenance measures are recommended to prevent deficiencies and for proper performance of the stormwater management system. Failure to implement these measures can reduce the hydraulic capacity and the pollutant removal efficiency of stormwater measures resulting in a poor quality of stormwater runoff discharging from the Site.

RESPONSIBLE PARTY & ESTIMATED ANNUAL BUDGET

The party responsible for implementing this Plan and identifying the source of necessary funds is as follows:

Town of Arlington, Massachusetts – Department of Public Works 51 Grove Street Arlington, MA 02476 Telephone: (781) 316-3301

GOOD HOUSEKEEPING

The Site will be maintained as clean and orderly. Routine inspections of the Site for debris and sediment accumulations shall be performed. Debris and sediment shall be disposed of in accordance with local and State requirements.

INSPECTIONS & MAINTENANCE MEASURES

Stormwater management is provided by porous pavement sections, as illustrated on the Site Plans. Routine inspections and maintenance of the stormwater management system shall be performed in accordance with this Operation & Maintenance Plan. These measures are recommended to prevent deficiencies within the system that may result in poor quality of stormwater runoff.

A sample Inspection Form is attached and is recommended for use during inspections of the stormwater management system. The form includes a table that outlines specific inspection and maintenance measures, in addition to the following information that can be recorded by the inspector during the inspection. Completed Inspections Forms shall be kept at the Site to enable both Department of Public Works staff members and regulatory agencies to ensure that operation of the system is in compliance with this Operation & Maintenance Plan.

SOLID WASTE CONTAINMENT

Trash and recycling receptacles will be provided throughout the Site, as necessary. Receptacles should remain covered to prevent exposure with stormwater and to ensure waste will remain inside the receptacle. Waste collection must be performed regularly.

LANDSCAPE MANAGEMENT

Lawn and landscaped areas shall be inspected for patches of dead vegetation and erosion. If these conditions are observed, affected areas shall be stabilized and replanted with vegetation to prevent sediment from entering the stormwater management system.

The following measures shall be followed to minimize the potential for stormwater runoff pollution due to overwatering, dead vegetation and erosion, direct disposal of lawn clippings, and over-application of materials such as fertilizers and pesticides.

Lawn Mowing

The following mowing practices are recommended:

Maintain sharp mower blades.

- Typically, avoid cutting grass shorter than 2 to 3 inches in height, to minimize weed growth. Grass can be cut lower in the spring and fall to stimulate root growth but should not be cut shorter than 1½ inches.
- Do not dispose of grass clippings within the stormwater management system.
- Employ practices to minimize the potential for grass clippings to enter the stormwater management system.

Fertilizers & Pesticides

Use of pesticides and fertilizers should be minimized to the extent practicable. Application of these materials may degrade the quality of stormwater runoff and should therefore be applied cautiously. In addition, fertilizers and pesticides shall not be applied prior to rain events. These materials should be stored under cover to prevent their exposure to stormwater.

PERVIOUS AREA MANAGEMENT

Winter Operations

Remove accumulated snow after winter storm events to keep the site's parking lots open for operations and maintenance activities. Snow shall not be stored within pervious areas.

Plows with poly cutting blades are required for snow removal. With their use, no alterations to typical snow removal activities are required. Sand will prematurely clog the porous pavement system and should not be used for deicing. Magnesium Chloride is an alternative material that can be used for deicing, if necessary. Snow melts faster on porous pavement than traditional pavement, as melting water does not remain on the surface to insulate the remaining ice.

Pervious Pavement

The pervious pavement system shall be monitored for permeability and maintained with an industrial wet vacuum sweeper at east twice a year or more frequently, as needed. The frequency of cleanings will vary depending on Site conditions including frequency of traffic, local climate, and surrounding environment but should be performed once in the Spring and once in the Fall (after leaves have fallen but before the first snow fall) to assure the pavement's long function life.

Damage to the surface of the porous pavement can be repaired by using a concrete saw to remove the damaged area and installing new porous pavement in its place.

STORMWATER MANAGEMENT SYSTEM INSPECTION FORM

Town of Arlington, Massachusetts Arlington Reservoir 210 Lowell Street Arlington, MA 02474

name of inspector:				
Date/Time:				
Weather:				
Date of Last Inspection:				
_				
Items Inspected (refer to Table	and provide additional	sheets if necessary):		
	T 1			
Comments & Corrective Action	is Taken (provide addition	al sneets if necessary):	,	

Table 1 – Operations & Maintenance Measures

	Porous Pavement						
Objective: Maintain the i	nfiltration and storage capacity of the porous pavement section.						
Frequency	Measure						
Ongoing/As Needed	Monitor the surface of the porous pavement to proper drainage is achieved during storm events.						
Quarterly	Remove sediment and organic debris on the porous pavement surface using a vacuum sweeper.						
Bi-Annually (once in Spring and once in Fall)	 Inspect the surface of the porous pavement for deterioration or clogging. Assess the infiltration capacity of the porous pavement sections. 						
Additional Comments	 Do not stockpile snow on porous pavement surface. This will require additional maintenance and vacuuming. Do not sand over porous pavement surface. 						



APPENDIX F: STORMWATER POLLUTION PREVENTION PLAN



APPENDIX G: MASSDEP CHECKLIST FOR STORMWATER REPORT



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.





A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the Massachusetts Stormwater Handbook. The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals. This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

offormation presented in the Stormwater Checklist is accurate and that the information presented in the stormwater Report accurately reflects conditions at the site as of the date of this permit application.					
Registered Professional Engineer Block and Signature					
O'construct and Date					
Signature and Date					
Checklist					
Project Type: Is the application for new development, redevelopment, or a mix of new and edevelopment?					
New development					
☑ Redevelopment					
Mix of New Development and Redevelopment					



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

env	rironmentally sensitive design and LID Techniques were considered during the planning and design of project:
	No disturbance to any Wetland Resource Areas
	Site Design Practices (e.g. clustered development, reduced frontage setbacks)
\boxtimes	Reduced Impervious Area (Redevelopment Only)
\boxtimes	Minimizing disturbance to existing trees and shrubs
	LID Site Design Credit Requested:
	☐ Credit 1
	☐ Credit 2
	☐ Credit 3
\boxtimes	Use of "country drainage" versus curb and gutter conveyance and pipe
	Bioretention Cells (includes Rain Gardens)
	Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
	Treebox Filter
	Water Quality Swale
	Grass Channel
	Green Roof
	Other (describe):
Sta	ndard 1: No New Untreated Discharges
\boxtimes	No new untreated discharges
	Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
	Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued) Standard 2: Peak Rate Attenuation Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding. Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm. Calculations provided to show that post-development peak discharge rates do not exceed predevelopment rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24hour storm. Standard 3: Recharge Soil Analysis provided. Required Recharge Volume calculation provided. Required Recharge volume reduced through use of the LID site Design Credits. Sizing the infiltration, BMPs is based on the following method: Check the method used. Static Simple Dynamic Dynamic Field¹ Runoff from all impervious areas at the site discharging to the infiltration BMP. Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume. Recharge BMPs have been sized to infiltrate the Required Recharge Volume. Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason: Site is comprised solely of C and D soils and/or bedrock at the land surface Solid Waste Landfill pursuant to 310 CMR 19.000 Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable. Calculations showing that the infiltration BMPs will drain in 72 hours are provided. Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Cł	necklist (continued)
Sta	andard 3: Recharge (continued)
	The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
	Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.
Sta	ındard 4: Water Quality
The	e Long-Term Pollution Prevention Plan typically includes the following: Good housekeeping practices; Provisions for storing materials and waste products inside or under cover; Vehicle washing controls; Requirements for routine inspections and maintenance of stormwater BMPs; Spill prevention and response plans; Provisions for maintenance of lawns, gardens, and other landscaped areas; Requirements for storage and use of fertilizers, herbicides, and pesticides; Pet waste management provisions; Provisions for operation and management of septic systems; Provisions for solid waste management; Snow disposal and plowing plans relative to Wetland Resource Areas; Winter Road Salt and/or Sand Use and Storage restrictions; Street sweeping schedules; Provisions for prevention of illicit discharges to the stormwater management system; Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL; Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan; List of Emergency contacts for implementing Long-Term Pollution Prevention Plan. A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent. Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge: is within the Zone II or Interim Wellhead Protection Area is near or to other critical areas is near or to other critical areas is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
	The Required Water Quality Volume is reduced through use of the LID site Design Credits.
	Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if

applicable, the 44% TSS removal pretreatment requirement, are provided.



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Cł	necklist (continued)
Sta	ndard 4: Water Quality (continued)
	The BMP is sized (and calculations provided) based on:
	☐ The ½" or 1" Water Quality Volume or
	☐ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
	The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
	A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.
Sta	ndard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)
	The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report. The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted <i>prior</i> to the discharge of stormwater to the post-construction stormwater BMPs.
\boxtimes	The NPDES Multi-Sector General Permit does <i>not</i> cover the land use.
	LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
	All exposure has been eliminated.
	All exposure has <i>not</i> been eliminated and all BMPs selected are on MassDEP LUHPPL list.
	The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.
Sta	ndard 6: Critical Areas
	The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
\boxtimes	Critical areas and BMPs are identified in the Stormwater Report.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

\boxtimes	Practicable as a:			
	☐ Limited Project			
	 Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area. Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff 			
	☐ Bike Path and/or Foot Path☑ Redevelopment Project			
	Redevelopment portion of mix of new and redevelopment.			
	Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report. The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.			

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued) Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued) The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has not been included in the Stormwater Report but will be submitted **before** land disturbance begins. ☐ The project is *not* covered by a NPDES Construction General Permit. The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report. ☐ The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins. Standard 9: Operation and Maintenance Plan The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information: Name of the stormwater management system owners; Party responsible for operation and maintenance; Schedule for implementation of routine and non-routine maintenance tasks; ☐ Plan showing the location of all stormwater BMPs maintenance access areas; Description and delineation of public safety features; Estimated operation and maintenance budget; and Operation and Maintenance Log Form. The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions: A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs; A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions. Standard 10: Prohibition of Illicit Discharges ☐ The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;

NO Illicit Discharge Compliance Statement is attached but will be submitted *prior to* the discharge of

An Illicit Discharge Compliance Statement is attached;

any stormwater to post-construction BMPs.



woodardcurran.com commitment & integrity drive results



Notice of Intent – Additional Information Arlington Reservoir Phase 2 Implementation

30 December 2020

This memo is to address three topics addressing the landscape during the December 17th Conservation Commission hearing:

Stabilized crushed granite path system requested by the Lexington Conservation Commission & representative examples in the area

It was mentioned on the site walk held on Friday, September 4, 2020 with members of both the Arlington & Lexington Conservation Commission that the Lexington Conservation Commission does not consider a stabilized stonedust material to be a porous pavement system. The Commission prefers a stabilized crushed granite pavement surface. The difference between the two is in the specifying of a stonedust product which could be comprised of a 3/8" minus crushed quartz-based stone versus a 3/8" minus crushed granite. Both are blended with a water-activated binder.

Read Custom Soils is a local purveyor (Wareham, MA) of engineered and blended soils who specializes in providing this type of soils, including Organic-Lock (or approved equal). Organic-Lock, is a stabilized product which meets the Lexington requirements. Organic-Lock as provided by Read Custom Soils comes in 5 different colors each sourced from a different quarry. The "natural gray" color is sourced from a West Roxbury granite quarry, and therefore meeting the Lexington Commission's request for stabilized crushed granite.

It is worth noting that this stabilized pathway system is used in limited area within the Arlington portion of the Res recreation area. The vast majority of the trail encircling the Res is proposed to be comprised of a crushed stone surface with no stabilizer. The grades for most of the pathways are flat enough that the stabilized is not necessary. The only places within Arlington where the stabilized crushed granite system is proposed are:

- a. The sloped walkway connecting Drake Village to the perimeter trail. We have proposed the stabilizer here as the trail connection is just under 5% and we do not want the fine material to move with stormwater.
- b. The pathway connecting the concrete beach walkway along the south embankment of the swimming area. We have proposed the stabilizer in this location as the pathway has water on both sides and we want to be sure the fine material does not wash into either the swimming area or the Res.
- c. The trail which parallels the main parking lot between the lot and the Res. In this location we want to ensure that the 3/8-inch material does not migrate into the porous pavement system. We have also separated the two pavements with a 12-inch flush concrete curb to help separate the systems.



The most local example of the stabilized crushed granite is at the New Visitor Center at Walden Pond in Concord. The pathways adjacent to the parking lot and around the reconstruction cabin are comprised of stabilized crush granite. https://www.organic-lock.com/portfolio_page/walden-pond/

Additional information on the stabilized pathway system can be found at: http://readcustomsoils.com/stabilized-soil/
https://www.organic-lock.com/decomposed-granite-stabilizer/

2. Tree replacements for trees proposed to be removed

Section 24 (Vegetation Removal & Replacement) of the Town's Wetland Protection Regulations requires that trees removed within the Conservation Commission's jurisdiction (resource areas) shall be replaced based on the schedule established on page 35 of the Regulations. We have reflected that schedule on Sheet L1.1 of our plans submitted to the Commission. This schedule shows that there are a total of 25 trees being removed, which requires a replacement of 44 trees based on caliper inch of removal.

Trees are only being removed if they are in a hazard condition or if they will be impacted by the proposed improvements to the extent that they will not survive. Per the project's planting plan (sheets series L4.1-L4.5), tree plantings are being located in the following locations:

- To add shade to the landscape around the beach area
- To complement the row of trees between the main parking and Lowell Street
- To accent and provide shade in the playground
- To accent the entry and screen the filtration building from the man parking
- To revegetate the areas around the perimeter targeted for invasive species management.

Th vast majority of tree species proposed for planning (plant schedules are located on sheets L4.2A and L4.4) are species native to Massachusetts.

3. The main parking lot's history being used as a snow storage area by the Arlington Department of Public Works.

After the Conservation Commission hearing, Joe Connelly, Arlington Recreation Director, spoke to Michael Rademacher, Arlington DPW Director. Rademacher has committed to not using the new parking lot for snow storage in the future.

End of memo



Amherst Office 15 Research Drive Amherst, Massachusetts 01002 Tel 413.256.0202 Fax 413.256.1092

MEMO

To: Arlington Conservation Commission

Copy to Lexington Conservation Commission

Date: December 31, 2020

From: Mickey Marcus

RE: Revised Plans and information for Arlington Restoration Master Plan Phase II

File: DEP File: 091-0327


SWCA File: 60780


Dear Commission Members:


At our last hearing, several plan revisions were requested by the Conservation Commission, and these have been provided in this memo, and the attachments. These include a revised stormwater report, revisions to the site plans, and clarifications on construction materials and methods of invasive species control.


- 1) Information on Lexington's stabilized granite requirements. A memo from KZLA is attached providing information on this path material and representative examples in the area.
- 2) Recalculate stormwater calculations using NOAA Atlas 14+. A revised stormwater report dated December 2020 is attached. This report has been prepared by Woodard & Curran Engineers and is stamped by Denise Cameron, PE.
- 3) Review removal/replacement of trees. The KZLA memo addresses this item and the planting plans (Sheets L4.1 and L4.5 have been revised. These plan revisions are attached.
- <u>4) Add erosion controls (silt sack) around turf area in parking lot to prevent siltation.</u> The civil site plans have been revised to show compost filter erosion controls socks, and stone rip rap at the outfall pipes. These are shown Plan C1.0 and C2.0. Both revised plans are attached.
- 5) Propose alternatives to glyphosate. The recommended alternatives approved for use by the DEP include Garlon and Milestone. For the Phragmites and Reed Canary Grass we propose using Clearcast, also approved by MADEP. The Commission also asked for application methods other than spraying. For the woody plants we recommend stem cutting with the immediate wipe or wick application of the herbicide to the cut stems. A dye added to the herbicide mix may be used to show which stems have been treated. For the herbaceous plants, a glove-wipe application may be used (e.g. on swallowwort, reed canary grass). For several species such as the Phragmites, Japanese knotweed, and multiflora rose, the preferred treatment is a spray application.

- <u>6) Coordinate with DPW to ensure parking lot is not a snow dump.</u> This item has been addressed in the KZLA memo. The Town DPW has committed not to use the new parking lot for snow storage in the future.
- 7) Possibly schedule another site visit, weather dependent. The project team will be available to meet with any Commission Members or Staff during the NOI review, prior to construction, or during the construction. A site walk with the Town of Lexington Conservation Commission is scheduled for Saturday January 2, 2021.
- 8) Revise parking lot O&M Plan to include regenerative air sweeper. The stormwater report O&M plan has been revised and this item is addressed on page 194 of the stormwater report. Regenerative air sweeping is recommended twice each year, or as needed.
- 9) Revise invasive management to include as much cut-and-dab, not spray, as possible. This is addressed in item number 5. All woody invasive plants will use the cut stem treatment and will not use spray for herbicide application.
- 10) Update plan set with changes (erosion controls, plan has erosion control matting near flared end, but rip rap might be better). These changes have been made as requested by the Commission and they are included on the attached plan revisions by Woodard & Curran Engineers and item #4.









24x36 SHEET EXISTING -GROUND 50' MIN. SURFACE/ WORK AREA PAVEMENT 2"-3" DENSE GRADED ─ CRUSHED STONE -6" DIVERSION RIDGE GEOTEXTILE FABRIC -WHERE UPGRADIENT SLOPE EXCEEDS 5% <u>SECTION</u> PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP's), INCLUDING 50' MIN. ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED AS WELL AS REMOVING ANY PROTRUDING ROCKS, STUMPS OR ROOTS. DURING THE GROWING SEASON (APRIL 15-SEPTEMBER 15) USE RECP'S ON THE BASE OF GRASSED WATERWAYS, SOIL SLOPES HAVING A 10' MIN. RADIUS -GRADE GREATER THAT 15%, OR ANYWHERE WHERE HAY MULCH HAS PROVEN TO BE INEFFECTIVE AT CONTROLLING SHEET EROSION. RECP'S ARE A MANUFACTURED COMBINATION TOE OF DIVERSION -OF MULCH AND NETTING DESIGNED TO PREVENT EROSION AND RETAIN SOIL MOISTURE. RIDGE (TYP.) FOR OVER WINTER PROTECTION, APPLY RECP'S ON THE BASE AND SIDE SLOPES OF GRASSED DIVERSION RIDGE -WATERWAYS AND ON SLOPES STEEPER THAN AN 8% GRADE. 2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECP'S IN A 6" DEEP X 6" WIDE COMPOST FILTER SOCKS TRENCH WITH APPROXIMATELY 12" OF RECP'S EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP's WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" PAVEMENT APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF RECP's - WOODEN STAKE BACK OVER SEED AND COMPACTED SOIL. SECURE RECP'S OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE 3. ROLL THE RECP's (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. RECP's WILL 1. STOCKPILES SHALL BE SURROUNDED BY COMPOST FILTER SOCKS. UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP'S MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE 2. STOCKPILES SHALL HAVE A MAXIMUM 2:1 (H: V) SIDE SLOPE. LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS 3. REPAIR OR REPLACE DAMAGED COMPOST FILTER SOCKS DUE TO 1. GRADE TOWARDS SEDIMENT BARRIER WHEN NECESSARY TO MANAGE FLOW. CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN. CONSTRUCTION ACTIVITIES OR STOCKPILE MITIGATION. INCREASE MINIMUM LENGTH TO 100' WHERE TRACKED SEDIMENTS CONTAIN LESS THAN 80% SAND OR AS NECESSARY FOR HEAVY CONSTRUCTION. 4. THE EDGES OF PARALLEL RECP'S MUST BE STAPLED WITH APPROXIMATELY 2" - 5" OVERLAP DEPENDING ON RECP's TYPE. TEMPORARY SOIL STOCKPILE STABILIZED CONSTRUCTION ENTRANCE/EXIT 5. CONSECUTIVE RECP'S SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE RECP's WIDTH. NOTE: *IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE RECP's. 6. UNTIL GRASS IS ABUNDANT, INSPECT PERIODICALLY AND AFTER EACH RAINSTORM TO CHECK FOR EROSION. IMMEDIATELY REPAIR AND ADD MORE MULCH UNTIL GRASSES ARE FIRMLY ESTABLISHED. DO NOT MOW THE FIRST YEAR. ROLLED EROSION CONTROL MATTING - CHINKING ROCK - PLATE ROCK ROCKWORK TO MEETING -(LENGTH TO DEPTH RATIO SHALL (TYPICAL) SURROUNDING EXISTING BE GREATER THAN 2.5:1) FINISHED GRADE - MORTAR PAD BETWEEN STORM PIPE AND ROCKS ABUTTING PIPE (NO POINT LOADS) - CONCRETE PIPE FLARED END SECTION AND OPTIONAL TRASH GUARD PIPE — BASE ROCK BELOW -STORM PIPE FOR LENGTH OF OUTFALL PIPE MORTAR PAD TO SEAL BELOW PIPE -APPROVED COMPACTED - PROPOSED JOINT BETWEEN CONCRETE FLARED END SECTION AND CONCRETE PIPE SECTION SUBGRADE RIPRAP APRON SECTION A-A MATCH SURROUNDING X" HAND-PLACED -SIDE SLOPE STONE RIPRAP 1. GEOTEXTILE FABRIC OR FILTER MATERIAL SHALL BE PLACED BETWEEN RIPRAP AND SOIL. FLARED END SECTION -DIA. (IN) | 12" | 18" | 24" | 30" | 36" | 48" WIDTH (W) $\begin{vmatrix} 2'-4'' & 3'-5'' & 4'-6'' & 5'-7'' & 6'-8'' & 7'-10'' \end{vmatrix}$ EXTEND STONE CHANNEL -TO MEET EXISTING/ RIPRAP APRON DIA.(IN) PROPOSED GRADE (MIN.) TYPE 12"-24" 10' 6' | 16' 24"-48" 12' RIPRAP APRON OUTLET PROTECTION AT FLARED END ATE: NOVEMBER 2020 NOT TO SCALE SCALE: 1"=30' HEET: 2 OF 2 CHECK GRAPHIC SCALE BEFORE USING 248 of 479



STORMWATER MANAGEMENT REPORT

Arlington Reservoir – Phase 2



40 Shattuck Road | Suite 110 Andover, Massachusetts 01810 800.426.4262

woodardcurran.com COMMITMENT & INTEGRITY DRIVE RESULTS

0233115.00 **Town of Arlington Massachusetts**October 2020

Revised December 2020



TABLE OF CONTENTS

SEC	PAG	PAGE NO.		
1.	PROJECT	T DESCRIPTION	1-1	
	1.1 1.2 1.2 1.2 1.2	.2 Topography	1-1 1-1 1-2 1-2	
2.		/ATER EVALUATION		
	2.1 2.2 2.2 2.2 2.2 2.2 2.3 2.4	Stormwater Modeling Methodology Hydraulic Model Description 1 Design Points 2 Pre-Development Conditions 3 Post-Development Conditions	2-1 2-1 2-1 2-2 2-3 2-3	
3.		NOCE WITH STORMWATER MANAGEMENT STANDARDS		
	3.1 3.2 3.3 3.4 3.5 3.6 3.7 3.8 3.9 3.10	Standard 1: No New Untreated Discharges. Standard 2: Peak Rate Attenuation	3-1 3-2 3-2 3-2 3-3 3-3	
		TABLES		
Table 2-1: Design Rainfall Data				
Appei Appei Appei Appei Appei	ndix A: ndix B: ndix C: ndix D: ndix E: ndix F: ndix G:	Environmental Resource Documentation Soils Map and Test Pit Logs Stormwater Figures HydroCAD Stormwater Model Reports Operations & Maintenance Plan Stormwater Pollution Prevention Plan MassDEP Checklist for Stormwater Report		



1. PROJECT DESCRIPTION

1.1 Introduction

On behalf of the Town of Arlington, Massachusetts (the Town), Woodard & Curran, Inc. (Woodard & Curran) has prepared this Stormwater Management Report for the proposed improvements to the Arlington Reservoir, located at 210 Lowell Street in Arlington, Massachusetts (the Site). The Town is proposing to revitalize the eastern shore of the Arlington Reservoir recreation area. Weston & Sampson Engineers, Inc. (Weston and Sampson), on behalf of the Town of Arlington, developed a Master Plan for the Reservoir in 2018. This proposed project encompasses Phase 2 of the Master Plan and improvements include installing porous pavement over the approximately 0.5-acre gravel parking area in the southern portion of the site, installation of new ADA-accessible pathways, a new play area, a multi-use court, a boat launch, and several other Site improvements as shown on the Post-Development Watershed Figure located in Appendix C. The impacts of these improvements to the Site's stormwater drainage patterns are summarized in this report.

1.2 Existing Conditions

A Site Locus Plan on a United States Geological Survey (USGS) Quadrangle Map depicting the project location has been provided in **Appendix A**. Arlington Reservoir is a 65-acre man-made recreational and stormwater-control pond on the Arlington and Lexington Town border. About half of the reservoir's open water is located in the Town of Lexington, however, the Town of Arlington owns and manages the reservoir. The earthen dam around the southern edge of the Reservoir is approximately 600 yards long and up to 14 feet tall. The water within the Reservoir discharges into Mill Brook through a sluice gate.

In 1935, the Town of Arlington constructed a sandy beach on the Reservoir's eastern shore. In the late 1970s, the Town completed improvements to the beach and added an embankment to separate the swimming area from the rest of the Reservoir. The beach now includes a filtered, chlorinated swimming area with a ramp for ADA accessibility, a bathhouse, vending machines, a concession area, and a playground. The Reservoir also has a one-mile walking trail around its perimeter, open to the public throughout the year.

1.2.1 Land Cover and Soils

Land cover and soils datasets were used to develop hydrologic curve numbers. Land cover was determined by a site visit conducted on September 3, 2020 and review of aerial photography and site survey data. A more detailed examination of the existing land cover within individual drainage subcatchments can be found in section 2.2.2. All existing impervious areas located within the Town of Lexington that are proposed to be replaced with a pervious land cover are required to be considered open space in good condition for stormwater calculations purposes per Lexington's Stormwater Management Regulations.

Soil characteristics were observed during test pit evaluations conducted in August 2020 and supplemented with information obtained from the United States Department of Agriculture's (USDA's) most recent Web Soil Survey. A Site map showing soil types and hydrologic soil group classifications within the project vicinity from the USDA's Web Soil Survey is located in **Appendix B**.

Test pits were conducted by Civil Design Consultants, Inc. (CDCI) of Methuen, Massachusetts on August 6, 2020 to evaluate the subsurface soil conditions and identify the estimated seasonal high groundwater table elevation. In all four borings conducted, CDCI observed a surface layer of fill ranging from 9 to 27 inches in depth, followed by a sandy loam layer extending to the bottom of each test pit. From these test pits, it was determined that at its highest elevation in the 0.5-acre parking lot, the seasonal high groundwater table is located approximately at elevation 159.40. Woodard & Curran used this data to locate the proposed stormwater best management practices (BMPs) at elevations with at



least two feet of separation from groundwater. Bedrock was not encountered during test pitting activities. The test pit logs and location figure provided by CDCI are located in **Appendix B**.

1.2.2 Topography

Subcatchment boundaries were delineated using the site survey performed and prepared by Weston & Sampson in December 2017. Topographically, the eastern shore of the Reservoir generally slopes downward from Lowell Street towards the Reservoir, with the exception of the southern-most portion of the 0.5-acre gravel parking area, which slopes downwards towards a ditch just north of the property located at 202 Lowell Street.

In both the pre- and post-development Site conditions, stormwater travels across the Site via overland flow and discharges into one of three Design Points: Arlington Reservoir, the on-Site swimming area, and the ditch located north of 202 Lowell Street. The Design Points and contributing areas are further described in Section 2.2.1. and are depicted in the Pre- and Post-Development Watershed Figures in **Appendix C**.

1.2.3 Resource and Critical Areas

Woodard & Curran reviewed Massachusetts Geographic Information System (MassGIS) data, the Massachusetts Department of Environmental Protection's (MassDEP's) Habitat of Potential Regional and Statewide Importance maps, the Massachusetts Stormwater Handbook, the Massachusetts Year 2016 Integrated List of Waters, and the Federal Emergency Management Agency's (FEMA's) National Flood Hazard Layer (NFHL) database. The findings of our review are below:

- The Massachusetts Endangered Species Act (MESA) protects rare species and their habitats by prohibiting the taking of any plant or animal species listed as Endangered, Threatened, or Special Concern by the Massachusetts Division of Fisheries & Wildlife. MESA review is required by the Natural Heritage & Endangered Species Program (NHESP) for projects and activities located within a Priority or Estimated Habitat of Rare Species. Review of the MassGIS Data shows there are no Priority or Estimated Habitats within the Project Area; therefore, the project is not subject to MESA review.
- Per MassGIS Data, there are no Certified or Potential Vernal Pools within or near the project area.
- Per MassGIS Data, the project is not located within any Areas of Critical Environmental Concern.
- Per the MassDEP's Habitat of Potential Regional and Statewide Importance maps for the Towns of Arlington and Lexington, the project in not located within a Habitat of Regional or Statewide Importance.
- Per the Massachusetts Stormwater Handbook, critical areas include Outstanding Resource Waters and Special Resource Waters, recharge areas for public water supplies, bathing beaches, cold-water fisheries, and shellfish growing areas. Review of MassGIS Data indicated that the Arlington Reservoir is not located within a resource area, however, the Swimming Area on the eastern shore of the Reservoir is classified as a bathing beach, as defined in 105 CMR 445, and thus a critical area.
- Per the Massachusetts Year 2016 Integrated List of Waters, Mill Brook, which receives discharges from Arlington Reservoir via a sluice gate on the southern portion of the Reservoir, is classified as a Category 5 water, meaning the waterbody requires a Total Maximum Daily Load (TMDL) restriction. Mill Brook's impairment of concern is Escherichia Coli (E. Coli). Proposed site improvements are not likely to increase E. Coli levels in Arlington Reservoir, and thus contributing to Mill Brook's impairment.



• Per FEMA's NFHL database, the majority of the Site is located within an area of minimal flood hazard (Zone X). The Reservoir's shoreline and the isolated swimming area are located within special flood hazard areas (Zone AE). The FEMA NFHL FIRMette Map is located in **Appendix A**.

Measures taken to address the presence of a critical area on-Site are detailed in Section 3.6. Critical areas have specific stormwater analysis guidelines, requiring the use of certain pollution prevention measures and BMPs to the maximum extent practicable for redevelopment projects.

1.3 Proposed Project Work

The proposed project consists of paving the approximately 0.5-acre gravel parking area in the southern portion of the site, renovation of the existing bathhouse and concessions building, installation of new ADA-accessible concrete pathways, lifeguard stands, picnic tables, a playground, multi-use court, boat launch, check-in shelter, and several other surficial Site improvements. Construction activities are expected to begin in March 2021 and end in November 2021.



2. STORMWATER EVALUATION

2.1 Stormwater Modeling Methodology

TR-55/TR-20 methodology was used to develop a hydrologic model of the site. Woodard & Curran used the computer program entitled HydroCAD Version 10.0, developed by HydroCAD Software Solutions, LLC in order to create and analyze the site hydrology. The analysis was conducted in order to establish the peak rates of runoff and estimated runoff volume from the project site. This was accomplished to evaluate pre- and post-development conditions during various storm events. Contributing drainage areas were identified and soils, surface cover, watershed slope, and flow paths were evaluated to develop the necessary HydroCAD model input parameters. A minimum Time of Concentration (Tc) of 6 minutes was used in the calculations, as applicable.

Drainage calculations were performed for the pre- and post-development conditions for the 1-, 2-, 10-, 25-, and 100-year 24-hour Type III storm events, and are included in **Appendix D**, in accordance with the Town of Arlington's, Town of Lexington's, and the Massachusetts Department of Environmental Protection's Stormwater Management Regulations. The total rainfall for each of the storm events was based upon data published by the Northeast Regional Climate Center (NRCC) and Natural Resources Conservation Service (NRCS) entitled *Extreme Precipitation in New York and New England* found at http://precip.eas.cornell.edu/. The total precipitation depth for the project site associated with each rainfall event is outlined in **Table 2-1**, below.

Table 2-1: Design Rainfall Data

Type III 24-Hour Storm Event (Frequency)	Rainfall Depth (Inches)
1-Year	2.67
2-Year	3.21
10-Year	4.86
25-Year	6.17
100-Year	8.85

A copy of the NRCC and NRCS Extreme Precipitation Table for the project Site is included in **Appendix A**.

In addition to the above analysis, this site was also evaluated using National Oceanic and Atmospheric Administration (NOAA) Atlas plus rainfall depth and distribution data. Discussion and a summary of results for this additional analysis can be found in **Section 2.4** and model result data can also be found in **Appendix D**

2.2 Hydraulic Model Description

A stormwater model has been developed to compare the peak runoff rates from the pre-development site to the peak runoff rates anticipated from the post-development site. As further described herein, the model demonstrates that the post-development runoff rates will not exceed pre-development rates.

2.2.1 Design Points

Existing and proposed subcatchments were delineated in order to compare pre- and post-development peak rates of runoff. Although the size of each subcatchment differs slightly between the existing and proposed site conditions, the total area analyzed between the two conditions remained the same. A Design Point was established for each



watershed, symbolizing the area's ultimate stormwater discharge location. For this analysis, two watershed areas were identified, and therefore two Design Points were chosen, as follows:

- Design Point 1 (DP-1): represents runoff discharging to the Arlington Reservoir and Swimming Area.
- Design Point 2 (DP-2): represents runoff discharging to the ditch located north of the property at 202 Lowell Street.

The locations of the Design Points do not differ in the pre- and post-development analyses, as seen in the figures located in **Appendix C**.

2.2.2 Pre-Development Conditions

The pre-development project area consists of a swimming area, sandy beach, bathhouse, vending machines, concession area, playground, pump station building, walking paths, benches, lifeguard stands, a 0.5-acre gravel parking lot, a small paved parking lot, and various other Site features. Existing grassed areas on-Site were modeled to be in "fair" condition, as much of the grassed surfaces are currently covered in beach sand and therefore are not likely infiltrating groundwater as efficiently as grass in "good" condition would be.

Per Article 15 – Storm Water Mitigation of the Town of Arlington's Title V – Regulations Upon the Use of Private Property Bylaws, impervious surfaces are defined as "a hard-surfaced, human-made area that does not readily absorb or retain water, preventing the infiltration of storm water runoff; including but not limited to...parking and driveway areas..." Upon review of existing conditions at the site, it appears the 0.5-acre gravel parking lot on the southern half of the Site exhibits the hydrologic characteristics one would expect with an impervious surface. Ponded water has been observed on the gravel surface several days after rain events due to its inability to infiltrate to the soil below. Based on this review and Article 15 of the Town of Arlington's Title V Bylaws, the gravel parking area has been considered impervious for the purposes of this stormwater analysis.

The pre-development watershed area is approximately 5.42 acres in size. There are no existing stormwater BMPs on-Site; stormwater runoff from the three subcatchments within the project area is conveyed via overland flow to their respective design points, as described below:

- Subcatchment 1: Subcatchment 1 encompasses the northern portion of the Site, including the playground, beach, and parking lots. Stormwater runoff from subcatchment 1 flows via overland flow from east to west before discharging into the Arlington Reservoir and Swimming Area (DP-1), which is classified by MassDEP as a critical area. The area is approximately 5.22 acres in size; land cover is primarily comprised of grass, beach sand, surface water, and impervious gravel with smaller areas of brush, impervious structures, and sand pathways. The calculated weighted curve number for this subcatchment is 71.
- Subcatchment 2: Subcatchment 2 encompasses the southern-most portion of the 0.5-acre gravel parking area. Stormwater runoff from subcatchment 3 flows via overland flow from north to south before discharging into the ditch just north of the property at 202 Lowell Street (DP-2). The area is approximately 0.20 acre in size; land cover is primarily comprised of impervious gravel, grass, and brush, with smaller areas of impervious surfaces. The calculated weighted curve number for this subcatchment is 64.

The subcatchment areas and their associated design points are illustrated on the Pre-Development Watershed Figure provided in **Appendix C** of this Report.



2.2.3 Post-Development Conditions

The post-development project area will consist of a swimming area, sandy beach, renovated bathhouse, vending machine, and concession area, a newly-paved picnic pavilion and drop-off area, a new check-in area, permeable multi-surface athletic court, playground, lifeguard stands, walking paths, restored grass areas, 21,500 square-foot porous pavement parking lot, and various other Site features. The new walking paths around the project area will be ADA-accessible and will allow increased Site access not currently provided in the Site's existing condition. The porous pavement parking lot is described in further detail in Section 2.2.4.

Similar to the pre-development model, the post-development watershed area is also 5.42 acres in size. Stormwater runoff from the two subcatchments will flow to its respective design points, as described below:

- Subcatchment 1: Subcatchment 1 will encompass the northern portion of the Site, including the playground, beach, and parking lots. Stormwater runoff from subcatchment 1 will flow via overland flow from east to west before either discharging directly into Arlington Reservoir and Swimming Area (DP-1) or into the porous pavement system proposed for installation over the Site's southern parking area. Stormwater entering the porous pavement system will either infiltrate into the ground or, during large storm events, will be collected by the system's underdrain and discharged towards Arlington Reservoir. The subcatchment area will be approximately 5.32 acres in size; land cover will be primarily comprised of grass, surface water, beach sand, porous asphalt pavement, and various impervious surfaces (including standard asphalt pavement, concrete walkways, and structures), with smaller areas of brush, permeable playground and athletic court surfaces, and stone dust. The calculated weighted curve number for this subcatchment is 69.
- Subcatchment 2: Subcatchment 2 will encompass the area south of the porous pavement parking area. Stormwater runoff from subcatchment 2 will flow via overland flow from north to south before discharging into the ditch just north of the property at 202 Lowell Street (DP-2). The area will be approximately 0.10 acre in size; land cover will be entirely comprised of grass. The calculated weighted curve number for this subcatchment is 39.

The subcatchment areas and their associated design points are illustrated on the Post-Development Watershed Figure provided in **Appendix D** of this Report.

2.2.4 Low Impact Development Technique – Porous Pavement

Porous pavement was selected as a Low Impact Development (LID) technique for this Site in accordance with the Arlington Reservoir Master Plan written by Weston & Sampson in 2018. The proposed 21,500 square-foot porous pavement parking lot will replace the existing impervious gravel lot, which will provide a stabilized parking area and minimize the amount of maintenance required to upkeep the parking lot and reduce the amount sediment transported into Arlington Reservoir during post-construction conditions. Stormwater directed to the porous pavement will filter through the system's asphalt, choker, and pea gravel courses and enter the reservoir course, designed to provide storage capacity while stormwater infiltrates into the soils beneath the system. The bottom of the reservoir course was designed at elevation 161.40, providing a 2-foot separation from the highest seasonal high groundwater table elevation observed during test pitting activities conducted at the Site. A four-inch PVC underdrain and three grate inlets will be installed within the western-most portion of the system's reservoir course to provide an outlet for stormwater during extreme storm events. The invert of these outlets was designed at the 100-year storm elevation within the porous pavement BMP, meaning rainfall greater than the 100-year storm will flow through the reservoir course of the pavement system to the PVC underdrain and grate inlets and will discharge to the Arlington Reservoir (DP-1).

Volume 1, Chapter 1 of the Massachusetts Stormwater Handbook does not list porous pavement as an approved stormwater BMP for discharges near bathing beaches and Volume 2, Chapter 2 of the Handbook states that porous



pavement shall be set back at least 100 feet from surface waters to receive any water quality credit. Existing Site constraints, including the lack of available area to install stormwater BMPs and the proximity to surface water across the entire project area, inhibit the use of many typical BMPs. Although porous pavement is not a listed BMP for bathing beaches, its use can be implemented within the project area and it will improve stormwater treatment at the Site by increasing water quality volume, annual recharge, and removal of total suspended solids (TSS) in the post-development Site condition.



2.3 Peak Discharge Rates and Runoff Volumes

The tables below summarize the pre- and post-development peak discharge rates and runoff volumes for each Design Point.

Table 2-2: Pre- and Post-Development Peak Discharge Rates

Design	1-	year (cf	s)	2-	year (c	fs)	10-	year (c	fs)	25	year (cfs	3)	100-	year (cfs	5)
Point	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ
DP-1	2.96	1.65	-1.31	4.93	3.15	-1.78	12.11	8.92	-3.19	18.53	14.29	-4.24	32.53	26.30	-6.23
DP-2	0.04	0.00	-0.04	0.10	0.00	-0.10	0.33	0.00	-0.33	0.54	0.02	-0.52	1.04	0.13	-0.91

Note: Δ stands for net difference between the pre- and post-development rates.

Table 2-3: Pre- and Post-Development Runoff Volumes

Design	1	-year (a	f)	2.	year (af)	10	year (a	f)	25	i-year (a	f)	100	0-year (a	ıf)
Point	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ	Pre	Post	Δ
DP-1	0.25	0.17	-0.08	0.38	0.27	-0.11	0.87	0.66	-0.21	1.32	1.03	-0.29	2.32	1.87	-0.45
DP-2	0.00	0.00	0.00	0.00	0.00	0.00	0.03	0.00	-0.03	0.04	0.00	-0.04	0.07	0.01	-0.06

Note: Δ stands for net difference between the pre- and post-development volumes.

Table 2-2 demonstrates a decrease in peak discharge rates between the existing and proposed site conditions for all scenarios shown above; **Table 2-3** demonstrates a decrease in runoff volumes between the existing and proposed site conditions for all scenarios shown above. Complete copies of the pre- and post-development HydroCAD computer model outputs demonstrating that peak discharge rates and runoff volumes decrease between the existing and proposed Site conditions are included in **Appendix D**.



2.4 NOAA Atlas 14 Plus Evaluation

Currently, the Massachusetts Department of Environmental Protection (MassDEP) is considering changing their current regulations to specify the use of NOAA Atlas 14 Plus data for use in stormwater modeling. Overall the modeling methodology will stay the same as described in Section 4.1, but updated rainfall depths and distribution curves have been established in order to better capture the effect of climate change along with the addition of several years of new data. The rainfall totals are calculated by multiplying the Upper Confidence of the standard NOAA Atlas 14 precipitation frequency estimates by 0.9. Rainfall depths used in this analysis can be found below in **Table 2-4**. In addition to the rainfall depths, NOAA guidelines stipulate the use of rainfall distributions curves created by the NRCS Water Quality and Quantity Development Team. These curves are based on geographic area and specifies the use of rainfall distribution curve "D" for areas in Arlington and Lexington, MA. Results of the NOAA Atlas 14 Plus analysis can be found below in **Table 2-5**.

Table 2-4: Design Rainfall Data

NOAA 24-Hour Storm Event (Frequency)	Rainfall Depth (Inches)
1-Year	2.93
2-Year	3.64
10-Year	5.79
25-Year	7.48
100-Year	10.35

Table 2-5: NOAA Atlas 14 Plus Results

Rainfall		DP-1			DP-2	
Event	Pre(cfs)	Post(cfs)	Δ	Pre(cfs)	Post(cfs)	Δ
1	3.86	2.38	-1.48	0.07	0.00	-0.07
2	6.51	4.47	-2.04	0.15	0.00	-0.15
10	15.91	12.22	-3.69	0.46	0.01	-0.45
25	24.00	19.13	-4.87	0.75	0.06	-0.69
100	38.24	31.54	-6.70	1.27	0.21	-1.06

As can be seen in **Table 2-5**, the results from the NOAA Atlas 14 Plus analysis closely mirror those of the previous NRCC Extreme Precipitation results. Furthermore, the analysis does not give any reason for concern about the stormwater system due to the larger rainfall depths calculated from the NOAA data. While the total rainfall depths are significantly different, especially seen during large events, the rainfall distributions used with the NOAA data create similar peak flowrates as seen with NRCC Extreme Precipitation data used with a Soil Conservation Service (SCS) Type III rainfall distribution.



3. COMPLIANCE WITH STORMWATER MANAGEMENT STANDARDS

Volume 1, Chapter 1 of the Massachusetts Stormwater Handbook states:

"For purposes of the Stormwater Management Standards, redevelopment projects are defined to include...maintenance and improvement of existing roadways, including widening less than a single lane, adding shoulders, correcting substandard intersections, improving existing drainage systems, and repaving."

By this definition, the Arlington Reservoir Phase 2 project is considered a redevelopment project, meaning certain Standards included in the Massachusetts Stormwater Handbook only need to be met to the maximum extent practicable (as defined by Standard 7). The following sections further detail applicability of these Stormwater Management Standards and demonstrates that the proposed Arlington Reservoir – Phase 2 Project complies with these requirements.

3.1 Standard 1: No New Untreated Discharges

"No new stormwater conveyances (e.g. outfalls) will discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth."

In the existing site condition, stormwater is generally transported via overland flow towards the Arlington Reservoir and Swimming Area (DP-1) and the ditch just north of the property at 202 Lowell Street (DP-2). Runoff from the project area is not currently treated prior to discharge. The proposed site improvements will not create any new untreated stormwater discharges and will result in a net decrease in impervious area of approximately 18,000 square feet. Stormwater runoff from Site will be either conveyed via overland flow to Design Points, similar to existing condition drainage patterns, or will be treated by a new porous pavement system prior to infiltrating into the ground or, during extreme storms greater than the 100-year event, discharging into the Arlington Reservoir (DP-1) after filter treatment. There are no proposed untreated stormwater discharges that will cause erosion in or to wetlands or waters of the Commonwealth. This Standard has been met.

3.2 Standard 2: Peak Rate Attenuation

"Stormwater management systems shall be designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates."

Calculations are provided to show that the post-development peak discharge rates do not exceed pre-development rates for the 1-, 2-, 10-, 25-, and 100-year 24-hour storm events. A detailed description of both the existing and proposed Site conditions are located in Section 2.2 of this report. Copies of the existing and proposed HydroCAD computer model outputs demonstrating that this standard has been met are included in **Appendix D**.

3.3 Standard 3: Recharge

"Loss of annual recharge to groundwater shall be eliminated or minimized through the use of infiltration measures including environmentally sensitive site design, low impact development techniques, stormwater best management practices, and good operation and maintenance. At a minimum, the annual recharge from the post-development site shall approximate the annual recharge from pre-development conditions based on soil type. This condition is met when the stormwater management system is designed to infiltrate the required volume as determined in accordance with the Massachusetts Stormwater Handbook."

The proposed improvements will decrease the amount of impervious area across the project Site by approximately 18,000 square feet. No additional groundwater recharge volume is required, however, installation of porous pavement over the existing gravel parking lot in the southern portion of the Site and restoration of grass areas throughout the Site



are proposed as part of this project. The porous pavement and restored grass areas will increase stormwater infiltration, and therefore annual recharge, in the post-development Site condition.

3.4 Standard 4: Water Quality

"Stormwater management systems shall be designed to remove 80% of the average annual post-construction load of Total Suspended Solids (TSS). This Standard is met when: (a) Suitable practices for source control and pollution prevention are identified in long-term pollution prevention plan, and thereafter implemented and maintained; (b) Structural stormwater best management practices are sized to capture the required water quality volume determined in accordance with the Massachusetts Stormwater Handbook; and (c) Pretreatment is provided in accordance with the Massachusetts Stormwater Handbook."

Existing Site conditions provide 0% TSS removal. The Town of Arlington is proposing to install a porous pavement system over the existing gravel parking lot in the southern portion of the Site. The system will increase water quality volume and remove TSS from the stormwater runoff produced from the proposed parking lot area and the adjacent grass area to the east sloping downward from Lowell Street in the post-development Site condition. During storm events, stormwater will filter through the porous pavement system's asphalt, choker, and pea gravel courses and enter the reservoir course, designed to provide storage capacity while stormwater infiltrates into the soils beneath the system.

According to Volume 2, Chapter 2 of the Massachusetts Stormwater Handbook, porous pavement systems can remove up to 80% of TSS if the reservoir course is designed to hold the Site's required water quality volume and to drain within 72 hours of a storm event. The proposed Site improvements will decrease the amount of impervious area across the project Site by approximately 18,000 square feet, and therefore no additional water quality volume is required on-Site. However, the porous pavement system's reservoir course has been designed to store the 100-year storm event and to drain within 26 hours of the 100-year event. Therefore, it can be assumed that the proposed porous pavement system will remove up to 80% of the TSS in stormwater runoff discharging to the system. On other parts of the proposed project Site, this Standard is met to the maximum extent practicable by not creating any new untreated stormwater discharges.

An Operations and Maintenance Plan is provided in **Appendix E**, which specifies suitable practices for source control and long-term pollution prevention.

3.5 Standard 5: Land Uses with Higher Potential Pollutant Loads

"For land uses with higher potential pollutant loads, source control and pollution prevention shall be implemented in accordance with the Massachusetts Stormwater Handbook to eliminate or reduce the discharge of stormwater runoff from such land uses to the maximum extent practicable. If through source control and/or pollution prevention all land uses with higher potential pollutant loads cannot be completely protected from exposure to rain, snow, snow melt, and stormwater runoff, the proponent shall use the specific structural stormwater BMPs determined by the Department to be suitable for such uses as provided in the Massachusetts Stormwater Handbook."

The proposed project is not considered a Land Use with Higher Potential Pollutant Loads; therefore, this standard does not apply.

3.6 Standard 6: Critical Areas

"Stormwater discharges within the Zone II or Interim Wellhead Protection Area of a public water supply and stormwater discharges near or to any other critical area require the use of the specific source control and pollution prevention measures and the specific structural stormwater best management practices determined by the Department to be suitable for managing discharges to such areas as provided in the Massachusetts Stormwater Handbook."



Per the Massachusetts Stormwater Handbook, the Arlington Reservoir and associated Swimming Area on the eastern shore of the Reservoir are classified as critical areas. These surface water features are described throughout this report as DP-1 and will receive stormwater discharges from subcatchment 1 in the post-development Site condition. Critical areas have specific stormwater analysis guidelines, requiring the use of certain pollution prevention measures and BMPs to the maximum extent practicable for redevelopment projects. Compliance with these guidelines is discussed below:

- Standard 6 requires BMP trains discharging to critical areas to remove 80% of TSS prior to discharge. There are no existing stormwater BMPs located in subcatchment 1. In the proposed Site condition, the majority of stormwater runoff from subcatchment 1 will travel, via overland flow, to the Reservoir and Swimming Area by passing over grassed areas and beach sand prior to discharging into DP-1. This stormwater runoff will not be treated by a stormwater BMP, similar to existing Site conditions. Stormwater runoff produced from the proposed porous parking lot area and the adjacent grass area to the east sloping downward from Lowell Street will filter through the porous pavement system, during which 80% of TSS will be removed.
- A water quality depth of one-inch (1") must be used for water quality volume calculations in critical areas. The proposed Site improvements will decrease the amount of impervious area across the project Site by approximately 18,000 square feet, and therefore no additional water quality volume is required on-Site.

The proposed Site improvements meet this Standard to the maximum extent practicable.

3.7 Standard 7: Redevelopment

"A redevelopment project is required to meet the following Stormwater Management Standards only to the maximum extent practicable: Standard 2, Standard 3, and the pretreatment and structural best management practice requirements of Standards 4, 5 and 6. Existing stormwater discharges shall comply with Standard 1 only to the maximum extent practicable. A redevelopment project shall also comply with all other requirements of the Stormwater Management Standards and improve existing conditions."

The proposed project is considered a redevelopment project and will decrease the overall impervious area on Site by approximately 18,000 square feet. The proposed work fully complies with Stormwater Management Standards 1, 2, 3, 5, 8, 9, and 10, and complies, to the maximum extent practicable, with Standards 4 and 6 as described herein.

3.8 Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

"A plan to control construction related impacts including erosion, sedimentation, and other pollutant sources during construction and land disturbance activities (construction period erosion, sedimentation, and pollution prevention plan) shall be developed and implemented."

A plan to control construction-related impacts, specifically erosion and sedimentation, has been developed and is included in **Appendix F**. The proposed project has been designed to minimize land disturbance and preserve existing vegetation to the maximum extent practicable. The proposed construction BMPs have been designed in accordance with Massachusetts Erosion and Sediment Control BMPs Handbook published by MassDEP.

The Contractor will be responsible for implementing the specified erosion and sedimentation control methods. These measures will be maintained and kept in place until the disturbed areas of the project have fully stabilized. In addition, a U.S. Environmental Protection Agency (EPA) National Pollutant Discharge Elimination System (NPDES) Construction General Permit is required whenever construction activities will disturb one or more acres; the proposed project will disturb approximately 5.42 acres.



3.9 Standard 9: Operation and Maintenance Plan

"A long-term operation and maintenance plan shall be developed and implemented to ensure that stormwater management systems function as designed."

A long-term Operation and Maintenance Plan is included in **Appendix E** of this report.


3.10 Standard 10: Prohibition of Illicit Discharges

Standard 10 states that "All illicit discharges to the stormwater management system are prohibited."

The project will not result in any new illicit discharges. An Illicit Discharge Compliance Statement will be submitted prior to construction.



ENVIRONMENTAL RESOURCE DOCUMENTATION APPENDIX A:



NOTES:

1. BASE MAP TAKEN FROM UNITED STATES GEOLOGICAL SERVICES, DATED 2018. ACCESSED ON SEPTEMBER 15, 2020.

40 Shattuck Road, Suite 110 Andover, Massachusetts 01810 866.702.6371 | www.woodardcurran.com

COMMITMENT & INTEGRITY DRIVE RESULTS

ARLINGTON RESERVOIR PHASE 2 LOCUS MAP

DESIGNED BY: LLT DRAWN BY: LLT CHECKED BY: BSM 2020.09.15 LOCUS MAP.dw TOWN OF ARLINGTON, MA 51 GROVE STREET ARLINGTON, MA 02476

ARLINGTON RESERVOIR 265 of 479 GURE 1 210 LOWELL ST, ARLINGTON, MA

JOB NO: 0233115.00 DATESEPTEMBER 202


1DWLRODO (DRRG-EDUGIDHU)51WWH




HHOG


XCPSS+GDCGXCRC+UCL+GDUHDVFDCCRW EHXHGIRU

UHJYO DWRU\ SYUSRAHY



Habitat of Potential Regional or Statewide Importance Town of ARLINGTON, MA





The MassDEPs Massachusetts Wildlife Habitat Protection Guidance for Inland Wetlands, June 2006 adopted a new approach for assessing wildlife habitat impacts associated with work in wetlands. This approach utilizes maps developed at the University of Massachusetts Amherst using the Conservation Assessment and Prioritization System (CAPS). The maps depict Habitat of Potential Regional or Statewide Importance that may trigger more intensive levels of review. For more information on how to assess wildlife habitat impacts, see Section III of the Guidance document: http://www.mass.gov/dep/water/laws/wldhab.pdf.

Miles

The CAPS model assesses the ecological integrity of Massachusetts landscape features as influenced by environmental stressor metrics (e.g. pollution, fragmentation). CAPS relies on data that are broadly available across Massachusetts. Ecological features which are not consistently surveyed or uniformly available, such as certified vernal pools, rare species, and contamination sites are not included in CAPS. When available, this more specific ecological information may be used in conjunction with the CAPS outputs to better understand particular sites in Massachusetts and support informed conservation decision-making. For more information on the statewide maps produced by the CAPS model, see: http://www.masscaps.org.


These maps are funded in part by the Massachusetts Executive Office of Energy and Environmental Affairs, the Massachusetts Department of Environmental Protection and the U.S. Environmental Protection Agency under section 104 (b)(3) of the U.S. Clean Water Act. Environmental data sources include the Office of Geographic and Environmental Information (MassGIS).





Habitat of Potential Regional or Statewide Importance Town of LEXINGTON, MA





The MassDEPs Massachusetts Wildlife Habitat Protection Guidance for Inland Wetlands, June 2006 adopted a new approach for assessing wildlife habitat impacts associated with work in wetlands. This approach utilizes maps developed at the University of Massachusetts Amherst using the Conservation Assessment and Prioritization System (CAPS). The maps depict Habitat of Potential Regional or Statewide Importance that may trigger more intensive levels of review. For more information on how to assess wildlife habitat impacts, see Section III of the Guidance document: http://www.mass.gov/dep/water/laws/wldhab.pdf.

The CAPS model assesses the ecological integrity of Massachusetts landscape features as influenced by environmental stressor metrics (e.g. pollution, fragmentation). CAPS relies on data that are broadly available across Massachusetts. Ecological features which are not consistently surveyed or uniformly available, such as certified vernal pools, rare species, and contamination sites are not included in CAPS. When available, this more specific ecological information may be used in conjunction with the CAPS outputs to better understand particular sites in Massachusetts and support informed conservation decision-making. For more information on the statewide maps produced by the CAPS model, see: http://www.masscaps.org.

These maps are funded in part by the Massachusetts Executive Office of Energy and Environmental Affairs, the Massachusetts Department of Environmental Protection and the U.S. Environmental Protection Agency under section 104 (b)(3) of the U.S. Clean Water Act. Environmental data sources include the Office of Geographic and Environmental Information (MassGIS).





Extreme Precipitation Tables

Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

Smoothing Yes

State Massachusetts

Location

Longitude 71.187 degrees West 42.428 degrees North

Elevation 0 feet

Date/Time Thu, 10 Sep 2020 11:23:56 -0400

Extreme Precipitation Estimates

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.28	0.43	0.53	0.70	0.87	1.10	1yr	0.75	1.04	1.28	1.63	2.08	2.67	2.90	1yr	2.36	2.79	3.26	3.95	4.62	1yr
2yr	0.35	0.53	0.67	0.88	1.10	1.39	2yr	0.95	1.28	1.61	2.03	2.55	3.21	3.56	2yr	2.84	3.42	3.92	4.66	5.31	2yr
5yr	0.41	0.64	0.81	1.08	1.38	1.76	5yr	1.19	1.60	2.05	2.58	3.24	4.07	4.53	5yr	3.60	4.35	4.97	5.93	6.65	5yr
10yr	0.47	0.73	0.93	1.26	1.64	2.10	10yr	1.41	1.90	2.45	3.10	3.89	4.86	5.43	10yr	4.31	5.22	5.95	7.11	7.88	10yr
25yr	0.56	0.88	1.12	1.55	2.05	2.66	25yr	1.77	2.39	3.11	3.94	4.95	6.17	6.92	25yr	5.46	6.66	7.55	9.05	9.87	25yr
50yr	0.62	1.00	1.29	1.81	2.43	3.19	50yr	2.10	2.84	3.75	4.75	5.95	7.39	8.32	50yr	6.54	8.00	9.04	10.87	11.71	50yr
100yr	0.72	1.17	1.50	2.13	2.89	3.81	100yr	2.50	3.37	4.48	5.69	7.13	8.85	10.00	100yr	7.83	9.62	10.84	13.05	13.90	100yr
200yr	0.82	1.34	1.74	2.49	3.44	4.56	200yr	2.97	4.01	5.38	6.84	8.57	10.61	12.04	200yr	9.39	11.57	12.99	15.68	16.50	200yr
500yr	1.00	1.64	2.13	3.09	4.33	5.78	500yr	3.74	5.05	6.85	8.72	10.91	13.49	15.38	500yr	11.94	14.79	16.51	20.00	20.71	500yr

Lower Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.24	0.37	0.46	0.62	0.76	0.84	1yr	0.65	0.82	1.14	1.43	1.76	2.39	2.46	1yr	2.12	2.37	2.89	3.50	4.01	1yr
2yr	0.33	0.51	0.63	0.85	1.05	1.25	2yr	0.90	1.23	1.44	1.90	2.46	3.10	3.43	2yr	2.74	3.30	3.78	4.49	5.14	2yr
5yr	0.39	0.60	0.74	1.02	1.29	1.50	5yr	1.12	1.46	1.72	2.23	2.87	3.73	4.13	5yr	3.30	3.97	4.54	5.42	6.11	5yr
10yr	0.43	0.66	0.82	1.15	1.48	1.71	10yr	1.28	1.67	1.93	2.51	3.22	4.29	4.76	10yr	3.80	4.58	5.22	6.21	6.96	10yr
25yr	0.50	0.76	0.94	1.34	1.77	2.03	25yr	1.53	1.98	2.28	2.95	3.75	5.14	5.73	25yr	4.55	5.51	6.26	7.40	8.25	25yr
50yr	0.55	0.84	1.04	1.50	2.02	2.32	50yr	1.74	2.27	2.57	3.33	4.22	5.89	6.57	50yr	5.21	6.32	7.18	8.42	9.37	50yr
100yr	0.61	0.93	1.16	1.68	2.30	2.64	100yr	1.99	2.58	2.91	3.58	4.74	6.77	7.54	100yr	5.99	7.25	8.24	9.55	10.65	100yr
200yr	0.69	1.04	1.31	1.90	2.65	3.01	200yr	2.29	2.94	3.30	4.00	5.35	7.76	8.65	200yr	6.87	8.32	9.45	10.81	12.08	200yr
500yr	0.80	1.19	1.54	2.23	3.17	3.58	500yr	2.74	3.50	3.88	4.63	6.27	9.30	10.35	500yr	8.23	9.95	11.33	12.69	14.28	500yr

Upper Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.31	0.48	0.59	0.79	0.97	1.13	1yr	0.84	1.11	1.32	1.76	2.24	2.86	3.14	1yr	2.53	3.02	3.50	4.29	5.02	1yr
2yr	0.36	0.56	0.69	0.93	1.15	1.35	2yr	0.99	1.32	1.56	2.06	2.66	3.34	3.71	2yr	2.96	3.57	4.09	4.86	5.52	2yr
5yr	0.45	0.69	0.86	1.18	1.50	1.78	5yr	1.30	1.74	2.04	2.63	3.35	4.43	4.98	5yr	3.92	4.79	5.42	6.45	7.20	5yr
10yr	0.54	0.84	1.04	1.45	1.87	2.19	10yr	1.62	2.14	2.54	3.19	4.02	5.51	6.24	10yr	4.88	6.00	6.73	8.03	8.82	10yr
25yr	0.71	1.07	1.34	1.91	2.51	2.88	25yr	2.17	2.82	3.36	4.11	5.11	7.32	8.42	25yr	6.48	8.09	8.97	10.76	11.55	25yr
50yr	0.85	1.30	1.62	2.33	3.13	3.56	50yr	2.70	3.48	4.16	4.99	6.13	9.11	10.57	50yr	8.06	10.16	11.13	13.44	14.18	50yr
100yr	1.04	1.58	1.98	2.85	3.92	4.39	100yr	3.38	4.29	5.16	6.33	7.35	11.32	13.28	100yr	10.02	12.77	13.82	16.82	17.43	100yr
200yr	1.27	1.91	2.42	3.51	4.89	5.41	200yr	4.22	5.29	6.41	7.73	8.81	14.10	16.70	200yr	12.48	16.06	17.18	21.05	21.44	200yr
500yr	1.65	2.46	3.17	4.60	6.54	7.13	500yr	5.64	6.97	8.53	10.08	11.21	18.85	22.64	500yr	16.68	21.77	22.89	28.39	28.21	500yr





SOILS MAP AND TEST PIT LOGS APPENDIX B:



MAP LEGEND MAP INFORMATION The soil surveys that comprise your AOI were mapped at Area of Interest (AOI) 1:25,000. Area of Interest (AOI) C/D Soils Warning: Soil Map may not be valid at this scale. D Soil Rating Polygons Enlargement of maps beyond the scale of mapping can cause Not rated or not available Α misunderstanding of the detail of mapping and accuracy of soil Water Features line placement. The maps do not show the small areas of A/D contrasting soils that could have been shown at a more detailed Streams and Canals В scale. Transportation B/D Rails Please rely on the bar scale on each map sheet for map С Interstate Highways Source of Map: Natural Resources Conservation Service Web Soil Survey URL: C/D US Routes D Major Roads Coordinate System: Web Mercator (EPSG:3857) Not rated or not available Local Roads Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Soil Rating Lines Background Aerial Photography Albers equal-area conic projection, should be used if more A/D accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. B/D Soil Survey Area: Middlesex County, Massachusetts Survey Area Data: Version 20, Jun 9, 2020 C/D Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Sep 11, 2019—Oct 5, Not rated or not available Soil Rating Points The orthophoto or other base map on which the soil lines were Α compiled and digitized probably differs from the background A/D imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. В B/D



Web Soil Survey National Cooperative Soil Survey

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
1	Water		7.3	47.2%
253B	Hinckley loamy sand, 3 to 8 percent slopes	А	7.2	46.4%
626B	Merrimac-Urban land complex, 0 to 8 percent slopes	A	0.8	5.4%
631C	Charlton-Urban land- Hollis complex, 3 to 15 percent slopes, rocky	A	0.2	1.1%
Totals for Area of Inter	rest		15.5	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher



	Town of Arlington				
	Owner Name				
	210 Lowell Street				
	Street Address	244	Map/Lot #		
	Arlington	MA	02474		
	City	State	Zip Code		
В.	Site Information				
1.	(Check one)	grade Repair Tes	t pits for drainage pu	irposes	
2.	Soil Survey Available? X Yes No	If yes:		Web Soil Survey Source	253B Soil Map Unit
	Hinckley Loamy Sand				
	Soil Name	Soil Limitations			
	Sandy and gravelly glaciofluvial deposits				
	Soil Parent material	Landform			
3.	Surficial Geological Report Available? X Yes No	If yes: MassGIS Oliv	ver		
		Year Published/	/Source	Map Unit	
	Sand and gravel / till and bedrock				
	Description of Geologic Map Unit:				
4.	Flood Rate Insurance Map Within a regulatory	y floodway? \square Yes \square No)		
5.	Within a velocity zone?				
6.	Within a Mapped Wetland Area?	No If yes, Mass	GIS Wetland Data		and Type
7.		08/06/20 Month/Day/ Year	Range: Abo	ve Normal 🗓 N	Normal Below Normal
0	Other references reviewed:				



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review (minimum of two holes required at every proposed primary and reserve disposal area) **Deep Observation Hole Number:** TP-1 08/06/20 7:30 AM 70*, sunny Date Time Weather Latitude Longitude: Many large boulders Parking lot None 0-21. Land Use (e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%) See attached sketch Description of Location: Soil Parent Material: Landform Position on Landscape (SU, SH, BS, FS, TS) >25 feet >25 feet Distances from: Open Water Body Drainage Way N/A feet Wetlands >10 feet Property Line Drinking Water Well N/A feet Other feet 4. Unsuitable Materials Present: Yes X No If Yes: Disturbed Soil Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock 5. Groundwater Observed: X Yes □ No If yes: 68" Depth Weeping from Pit Depth Standing Water in Hole Soil Log Coarse Fragments **Redoximorphic Features** Soil Soil Horizon Soil Matrix: Color-% by Volume Soil Texture Depth (in) Soil Structure Consistence Other /Layer (USDA Moist (Munsell) Cobbles & Depth Color Percent Gravel (Moist) Stones 0-27Fill 27-38 Α Sandy Loam 10YR3/2 Massive Friable 38-44 В 10YR3/4 Sandy Loam Massive Friable High and >2 Friable C 10YR5/2 44" 10 Massive Sandy Loam Low Chroma 44-84

Additional Notes:



ACC 240				•						•		
C. On-	Site Revi	ew (minim	um of two hole	es requ	iired at ever	y propo	sed prin	nary and r	eserve disp	osal area))	
Deep	Observation	n Hole Numb	er: _TP-2_	08/06 Date	/20	7:45	AM	70*, su	ınny			
·			Hole #	Date		Time		Weather		Latitude		Longitude:
1. Land	Use Parki	ing lot	ural field, vacant lot, e	etc)	None Vegetation			Many large	e boulders es (e.g., cobbles,	stones houlder	rs etc)	0-2 Slope (%)
	(c.g., w		See attached sketch		vegetation			ourrace otoric	.s (c.g., cobbics,	Stories, boulder	13, 010.)	Giope (70)
2. Soil F	Parent Materia	al: <u>Till</u>			1	ndform		Deel		(CII CII DC	F0 T0\	
. 5	,	•	D. I	×25					tion on Landscar			. 25
3. Dista	nces from:	•	n Water Body _				•		feet			<u>>25</u> feet
			Property Line _				•	Vell <u>N/A</u>				feet
1. Unsuita	able Material	s Present:] Yes 🗓 No	If Yes:	☐ Disturbed S	Soil 🗌	Fill Materia	ıl 🗌 '	Weathered/Fra	ctured Rock	Bed	lrock
5 Groui	ndwater Obse	erved: Yes	X No		If ves	·-	Desirile Marie			Davide 0	M = 1 1 A /	atania Hala
o. Oloui	nawater Obse	rved. 🔲 163	A NO		ii yes			eping from Pit	_	Depth S	standing vv	ater in Hole
	T	T	Т	1		Soil Log	<i>-</i>	Fragments	T	I	T .	
Depth (in)	Soil Horizon	Soil Texture	Soil Matrix: Color-	Red	loximorphic Fea	tures		Volume	Soil Structure	Soil		Other
Depth (in)	/Layer	(USDA	Moist (Munsell)	Depth	Color	Percent	Gravel	Cobbles & Stones	Son Structure	(Moist)		Other
0-16	Fill											
16-30		G 1 T	10VD2/2						Marie	F		
10-30	A	Sandy Loam	10YR3/2		TT: 1 1				Massive	Friable		
30-43	В	Sandy Loam	10YR6/6	30"	High and Low Chroma	>2			Massive	Friable		
30 43	Б	Sandy Loani	10110/0		Low Cilionia				Widsive	THADIC		
43-60	С	Sandy Loam	10YR5/3				2	10	Massive	Friable		
]				1				
Additi	ional Notes:											



A. 6.3.00				•						•		
C. On-	Site Revi	iew (minim	num of two hole	es requ	iired at ever	y propo	sed prin	mary and r	eserve disp	osal area))	
Deep	Observation	n Hole Numb	er : <u>TP-3</u>	08/06	5/20	8:00 4	AM	70*, sı	ınny		_	
_			Hole #	Date		Time		Weather		Latitude	L	ongitude:
1. Land	Use Farki	ing lot oodland, agricultu	ural field, vacant lot, e	etc.)	None Vegetation			Many large	e boulders es (e.g., cobbles,	stones, boulder	rs. etc.)	0-2 Slope (%)
Do	, •		See attached sketch	•	rogotation			Curiaco Ciorio	,o (o.g., ooss.oo,	otorioo, bouldor	10, 010.)	C.Opo (70)
2. Soil F	Parent Materia	al: <u>Till</u>			1	ndform		Dool	*: ll	- CIL CIL DC	EC TO)	
D:		0.00	· Matai Dail	<u> </u>					tion on Landscar			.05
3. Distai	nces from:	•	n Water Body _				•	-	feet		_	>25 feet
			Property Line _				-	Vell N/A			Other _	
1. Unsuita	able Material	s Present: _] Yes 🗓 No	If Yes:	☐ Disturbed S	Soil 🗌	Fill Materia	al 🗌	Weathered/Fra	ctured Rock	☐ Bedro	ock
5 Groui	ndwater Obse	erved: Yes	x X No		If ves	·	Donth Woo	eping from Pit		Donth C	tonding Wot	or in Holo
). O loui	iawator Obot	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			ıı yoc			eping from Pit	_	Depin S	standing vvai	ei in noie
		_	Ī	T		Soil Log		Fragments	1	<u> </u>	T	
Depth (in)	Soil Horizon	Soil Texture	Soil Matrix: Color-	Red	loximorphic Fea	tures		Volume	Soil Structure	Soil		Other
Deptii (iii)	/Layer	(USDA	Moist (Munsell)	Depth	Color	Percent	Gravel	Cobbles & Stones	oon on acture	(Moist)		Other
0.0	EIII											
0-9	Fill											
9-25	В	Sandy Loam	10YR6/6						Massive	Eniolala		
					High and				Massive	Friable		
25-55	C	Sandy Loam	10YR5/3	32"	Low Chroma	>2	2	10	Massive	Friable		
										7714676		
							1					
Additi	ional Notes:											



			num of two hole					70*, su		,		
Беср	Deep Observation Hole Number: TP-4 Hole # Parking lot		Hole #	Date None		8:30 <i>I</i> Time			•	Latitude		Longitude: 0-2
1. Land Use Farking for (e.g., woodland, agricultural field, vacant lot, et			tc.) Vegetation			Many large boulders Surface Stones (e.g., cobbles, stones, boulders, etc.)			rs, etc.)	Slope (%)		
Des	scription of Lo	ocation: S	See attached sketch									
2. Soil P	arent Materia	al: <u>Till</u>								(011 011 00		
		_		. 25		ndform			tion on Landscap			
Distar	nces from:	· ·	n Water Body _						feet		tlands	<u>>25</u> feet
		1	Property Line _	>10 fe	et	Drinking	g Water W	/ell <u>N/A</u>	feet	(Other	feet
4. Unsuita	ble Material	s Present:] Yes 🗓 No	If Yes: [☐ Disturbed S	Soil 🗌 I	Fill Materia	ı 🔲 '	Weathered/Fra	ctured Rock	□Ве	drock
5. Grour	ndwater Obse	erved: Yes	s 🗓 No		If yes	s:	Depth Wee	ping from Pit	_	Depth S	Standing V	Vater in Hole
						Soil Log	I					
Depth (in)	Soil Horizon /Layer	Soil Texture (USDA	Soil Matrix: Color- Moist (Munsell)	Redoximorphic Featur		tures	Coarse Fragments % by Volume		Soil Structure	Soil	Other	
				Depth	Color	Percent	Gravel	Cobbles & Stones	Son Structure	(Moist)		Other
0-12	Fill											
12-61	С	Sandy Loam	10YR5/3	24"	High and Low Chroma	>2	2	10	Massive	Friable		
Additi	onal Notes	1	1	<u> </u>		<u>I</u>	I	1		<u> </u>	<u> </u>	



Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

F. Certification

I certify that I am currently approved by the Department of Environmental Protection pursuant to 310 CMR 15.017 to conduct soil evaluations and that the above analysis has been performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017. I further certify that the results of my soil evaluation, as indicated in the attached Soil Evaluation Form, are accurate and in accordance with 310 CMR 15.100 through 15.107.

and the state of t	08/06/20		
Signature of Soil Evaluator	Date		
William Hall, P.E., S.E. 13592	06/31/21		
Typed or Printed Name of Soil Evaluator / License #	Expiration Date of License		
Leyna Tobey - Woodard & Curran	N/A		
Name of Approving Authority Witness	Approving Authority		

Note: In accordance with 310 CMR 15.018(2) this form must be submitted to the approving authority within 60 days of the date of field testing, and to the designer and the property owner with <u>Percolation Test Form 12</u>.


Field Diagrams: Use this area for field diagrams:

See attached sketch





APPENDIX C: **STORMWATER FIGURES**






PHASE ARLINGTON RESERVOIR

JOB NO: 0233115.00 DATE: OCTOBER 2020 SCALE: AS NOTED



APPENDIX D: **HYDROCAD STORMWATER MODEL REPORTS**









Printed 10/6/2020 Page 2

Area Listing (all nodes)

Ar	ea CN	Desc	ription
(acre	es)	(sub	catchment-numbers)
1.5	31 49	50-7	5% Grass cover, Fair, HSG A (1, 2)
1.3	17 63	Beac	h Sand, HSG A (1)
0.3	79 30	Brus	n, Good, HSG A (1, 2)
0.0	46 96	Dens	e Sand Path, HSG A (1)
0.6	46 98	Grav	el parking, HSG A (1, 2)
0.2	34 98	Impe	rvious Surface, HSG A (1, 2)
0.0	55 39	Oper	Space, Good, HSG A (>75% Grass Cover) (1)
1.2	07 98	Wate	r Surface, HSG A (1)
5.4	16 70	TOTA	AL AREA

2020.10.06 Existing - Arlington Res
Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
5.416	HSG A	1, 2
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.000	Other	
5.416		TOTAL AREA

Printed 10/6/2020

Page 4

Ground Covers (all nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
1.531	0.000	0.000	0.000	0.000	1.531	50-75% Grass cover, Fair	1, 2
1.317	0.000	0.000	0.000	0.000	1.317	Beach Sand	1
0.379	0.000	0.000	0.000	0.000	0.379	Brush, Good	1, 2
0.046	0.000	0.000	0.000	0.000	0.046	Dense Sand Path	1
0.646	0.000	0.000	0.000	0.000	0.646	Gravel parking	1, 2
0.234	0.000	0.000	0.000	0.000	0.234	Impervious Surface	1, 2
0.055	0.000	0.000	0.000	0.000	0.055	Open Space, Good	1
1.207	0.000	0.000	0.000	0.000	1.207	Water Surface	1
5.416	0.000	0.000	0.000	0.000	5.416	TOTAL AREA	

Type III 24-hr 1-Year Rainfall=2.67"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 5

Printed 10/6/2020

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=0.58"

Tc=6.0 min CN=71 Runoff=2.96 cfs 0.251 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=0.33"

Tc=6.0 min CN=64 Runoff=0.04 cfs 0.006 af

Link DP-1: Reservoir and Swimming Area Inflow=2.96 cfs 0.251 af

Primary=2.96 cfs 0.251 af

Link DP-2: Ditch Inflow=0.04 cfs 0.006 af

Primary=0.04 cfs 0.006 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.257 af Average Runoff Depth = 0.57" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Printed 10/6/2020

Page 6


Summary for Subcatchment 1: Subcatchment 1

Runoff = 2.96 cfs @ 12.10 hrs, Volume= 0.251 af, Depth= 0.58"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Α	rea (sf)	CN	Description						
		14,435	30	Brush, Good, HSG A						
*		57,370	63	Beach Sand	d, HSG A					
*		1,998	96	Dense Sand Path, HSG A						
		63,530	49	50-75% Grass cover, Fair, HSG A						
*		24,927	98	Gravel park	Gravel parking, HSG A					
*		9,994	98	Impervious	Impervious Surface, HSG A					
		52,585	98	Water Surface, HSG A						
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)				
	2	27,252	71	Weighted A	verage					
	1	39,746		61.49% Per	vious Area					
		87,506		38.51% Imp	ervious Ar	ea				
				•						
	Tc	Length	Slop	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)					
<u></u>	6.0	•				Direct Entry,				

Subcatchment 1: Subcatchment 1



Page 7


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.04 cfs @ 12.13 hrs, Volume= 0.006 af, Depth= 0.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Α	rea (sf)	CN	Description						
		2,076	30	Brush, Goo	d, HSG A					
		3,179	49	50-75% Grass cover, Fair, HSG A						
*		3,211	98	Gravel parking, HSG A						
		215	98	Impervious	Surface, H	HSG A				
		8,681	64	Weighted Average						
		5,255		60.53% Pervious Area						
		3,426		39.47% Imp	pervious Ar	rea				
	Tc	Length	Slope	e Velocity	Capacity	Description				
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)	<u> </u>				
	6.0					Direct Entry,				

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 8

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 0.58" for 1-Year event

Inflow = 2.96 cfs @ 12.10 hrs, Volume= 0.251 af

Primary = 2.96 cfs @ 12.10 hrs, Volume= 0.251 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 9

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 0.33" for 1-Year event

Inflow = 0.04 cfs @ 12.13 hrs, Volume= 0.006 af

Primary = 0.04 cfs @ 12.13 hrs, Volume= 0.006 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 2-Year Rainfall=3.21"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 10

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=0.88"

Tc=6.0 min CN=71 Runoff=4.93 cfs 0.384 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=0.56"

Tc=6.0 min CN=64 Runoff=0.10 cfs 0.009 af

Link DP-1: Reservoir and Swimming Area Inflow=4.93 cfs 0.384 af

Primary=4.93 cfs 0.384 af

Link DP-2: Ditch Inflow=0.10 cfs 0.009 af

Primary=0.10 cfs 0.009 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.394 af Average Runoff Depth = 0.87" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Printed 10/6/2020 Page 11


Summary for Subcatchment 1: Subcatchment 1

Runoff = 4.93 cfs @ 12.10 hrs, Volume= 0.384 af, Depth= 0.88"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Α	rea (sf)	CN	Description						
		14,435	30	Brush, Goo	d, HSG A					
*		57,370	63	Beach Sand	Beach Sand, HSG A					
*		1,998	96	Dense Sand	Dense Sand Path, HSG A					
		63,530	49	50-75% Grass cover, Fair, HSG A						
*		24,927	98	Gravel park	Gravel parking, HSG A					
*		9,994	98	Impervious	Impervious Surface, HSG A					
		52,585	98	Water Surfa	Water Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)				
	2	27,252	71	Weighted A	verage					
	1	39,746		61.49% Per	vious Area	1				
		87,506		38.51% Imp	ervious Ar	ea				
	Tc	Length	Slop	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)					
<u></u>	6.0 Direct Entry,									

Subcatchment 1: Subcatchment 1



Page 12


Summary for Subcatchment 2: Subcatchment 2

0.10 cfs @ 12.11 hrs, Volume= 0.009 af, Depth= 0.56" Runoff

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Α	rea (sf)	CN	Description								
-		2,076	30	Brush, Goo	Brush, Good, HSG A							
		3,179	49	50-75% Grass cover, Fair, HSG A								
*		3,211	98	Gravel parking, HSG A								
	215 98 Impervious Surface, HSG A											
		8,681	64	Weighted A	Weighted Average							
		5,255		60.53% Pervious Area								
		3,426		39.47% Imp	pervious Ar	ırea						
	Tc	Length	Slop	e Velocity	Capacity	/ Description						
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)							
	6.0					Direct Entry,						

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 13

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 0.88" for 2-Year event

Inflow = 4.93 cfs @ 12.10 hrs, Volume= 0.384 af

Primary = 4.93 cfs @ 12.10 hrs, Volume= 0.384 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 14

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 0.56" for 2-Year event

Inflow = 0.10 cfs @ 12.11 hrs, Volume= 0.009 af

Primary = 0.10 cfs @ 12.11 hrs, Volume= 0.009 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 10-Year Rainfall=4.86"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 15

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=2.01"

Tc=6.0 min CN=71 Runoff=12.11 cfs 0.874 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=1.49"

Tc=6.0 min CN=64 Runoff=0.33 cfs 0.025 af

Link DP-1: Reservoir and Swimming Area Inflow=12.11 cfs 0.874 af

Primary=12.11 cfs 0.874 af

Link DP-2: Ditch Inflow=0.33 cfs 0.025 af

Primary=0.33 cfs 0.025 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.899 af Average Runoff Depth = 1.99" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Page 16


Summary for Subcatchment 1: Subcatchment 1

Runoff = 12.11 cfs @ 12.09 hrs, Volume= 0.874 af, Depth= 2.01"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Α	rea (sf)	CN	Description						
		14,435	30	Brush, Goo	d, HSG A					
*		57,370	63	Beach Sand	Beach Sand, HSG A					
*		1,998	96	Dense Sand	Dense Sand Path, HSG A					
		63,530	49	50-75% Grass cover, Fair, HSG A						
*		24,927	98	Gravel park	Gravel parking, HSG A					
*		9,994	98	Impervious	Impervious Surface, HSG A					
		52,585	98	Water Surfa	Water Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)				
	2	27,252	71	Weighted A	verage					
	1	39,746		61.49% Per	vious Area	1				
		87,506		38.51% Imp	ervious Ar	ea				
	Tc	Length	Slop	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)					
<u></u>	6.0 Direct Entry,									

Subcatchment 1: Subcatchment 1



Page 17


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.33 cfs @ 12.10 hrs, Volume= 0.025 af, Depth= 1.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Aı	rea (sf)	CN	Description						
		2,076	30	Brush, Goo	d, HSG A					
		3,179	49	50-75% Grass cover, Fair, HSG A						
*		3,211	98	Gravel parking, HSG A						
	215 98 Impervious Surface, HSG A									
		8,681	64	Veighted Average						
		5,255		60.53% Pervious Area						
		3,426		39.47% Imp	ervious Ar	rea				
	Тс	Length	Slope	Velocity	Capacity	Description				
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)					
	6.0					Direct Entry,				

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 18

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 2.01" for 10-Year event

Inflow = 12.11 cfs @ 12.09 hrs, Volume= 0.874 af

Primary = 12.11 cfs @ 12.09 hrs, Volume= 0.874 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 19

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 1.49" for 10-Year event

Inflow = 0.33 cfs @ 12.10 hrs, Volume= 0.025 af

Primary = 0.33 cfs @ 12.10 hrs, Volume= 0.025 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 25-Year Rainfall=6.17"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 20

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=3.04"

Tc=6.0 min CN=71 Runoff=18.53 cfs 1.320 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=2.39"

Tc=6.0 min CN=64 Runoff=0.54 cfs 0.040 af

Link DP-1: Reservoir and Swimming Area Inflow=18.53 cfs 1.320 af

Primary=18.53 cfs 1.320 af

Link DP-2: Ditch Inflow=0.54 cfs 0.040 af

Primary=0.54 cfs 0.040 af

Total Runoff Area = 5.416 ac Runoff Volume = 1.360 af Average Runoff Depth = 3.01" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 21


Summary for Subcatchment 1: Subcatchment 1

Runoff = 18.53 cfs @ 12.09 hrs, Volume= 1.320 af, Depth= 3.04"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Α	rea (sf)	CN	Description						
		14,435	30	Brush, Goo	d, HSG A					
*		57,370	63	Beach Sand	Beach Sand, HSG A					
*		1,998	96	Dense Sand Path, HSG A						
		63,530	49	50-75% Grass cover, Fair, HSG A						
*		24,927	98	Gravel park	Gravel parking, HSG A					
*		9,994	98	Impervious	Impervious Surface, HSG A					
		52,585	98	Water Surfa	Water Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)				
	2	27,252	71	Weighted A	verage					
	1	39,746		61.49% Per	vious Area					
		87,506		38.51% Imp	ervious Ar	ea				
	Tc	Length	Slop	e Velocity	Capacity	Description				
_	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)					
	6.0 Direct Entry,									

Subcatchment 1: Subcatchment 1



Page 22


Summary for Subcatchment 2: Subcatchment 2

Runoff 0.54 cfs @ 12.09 hrs, Volume= 0.040 af, Depth= 2.39"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Aı	rea (sf)	CN	Description							
		2,076	30	Brush, Goo	d, HSG A						
		3,179	49	9 50-75% Grass cover, Fair, HSG A							
*		3,211	98	Gravel parking, HSG A							
	215 98 Impervious Surface, HSG A										
		8,681	64	Weighted A	Weighted Average						
		5,255		60.53% Pervious Area							
		3,426		39.47% Imp	pervious Ar	ırea					
	Tc	Length	Slop	e Velocity	Capacity	/ Description					
(n	nin)	(feet)	(ft/ft) (ft/sec)	(cfs)						
	6.0					Direct Entry,					

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 23

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 3.04" for 25-Year event

Inflow = 18.53 cfs @ 12.09 hrs, Volume= 1.320 af

Primary = 18.53 cfs @ 12.09 hrs, Volume= 1.320 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 24

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 2.39" for 25-Year event

Inflow = 0.54 cfs @ 12.09 hrs, Volume= 0.040 af

Primary = 0.54 cfs @ 12.09 hrs, Volume= 0.040 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Type III 24-hr 100-Year Rainfall=8.85"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 25

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1: Subcatchment 1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=5.33"

Tc=6.0 min CN=71 Runoff=32.53 cfs 2.315 af

Subcatchment 2: Subcatchment 2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=4.47"

Tc=6.0 min CN=64 Runoff=1.04 cfs 0.074 af

Link DP-1: Reservoir and Swimming Area Inflow=32.53 cfs 2.315 af

Primary=32.53 cfs 2.315 af

Link DP-2: Ditch Inflow=1.04 cfs 0.074 af

Primary=1.04 cfs 0.074 af

Total Runoff Area = 5.416 ac Runoff Volume = 2.389 af Average Runoff Depth = 5.29" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 26


Summary for Subcatchment 1: Subcatchment 1

Runoff = 32.53 cfs @ 12.09 hrs, Volume= 2.315 af, Depth= 5.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Α	rea (sf)	CN	Description						
		14,435	30	Brush, Good, HSG A						
*		57,370	63	Beach Sand	d, HSG A					
*		1,998	96	Dense Sand Path, HSG A						
		63,530	49	50-75% Grass cover, Fair, HSG A						
*		24,927	98	Gravel park	Gravel parking, HSG A					
*		9,994	98	Impervious	Impervious Surface, HSG A					
		52,585	98	Water Surface, HSG A						
*		2,413	39	Open Space	e, Good, H	SG A (>75% Grass Cover)				
	2	27,252	71	Weighted A	verage					
	1	39,746		61.49% Per	vious Area					
		87,506		38.51% Imp	ervious Ar	ea				
				•						
	Tc	Length	Slop	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)					
<u></u>	6.0	•				Direct Entry,				

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 27


Summary for Subcatchment 2: Subcatchment 2

Runoff = 1.04 cfs @ 12.09 hrs, Volume= 0.074 af, Depth= 4.47"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Aı	rea (sf)	CN	Description						
		2,076	30	Brush, Goo	d, HSG A					
		3,179	49	9 50-75% Grass cover, Fair, HSG A						
*		3,211	98	Gravel parking, HSG A						
		215	·							
		8,681	64	Weighted Average						
		5,255		60.53% Pervious Area						
		3,426		39.47% Imp	ervious Ar	ea				
	Тс	Length	Slope	Velocity	Capacity	Description				
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)					
	6.0					Direct Entry,				

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 28

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 5.33" for 100-Year event

Inflow = 32.53 cfs @ 12.09 hrs, Volume= 2.315 af

Primary = 32.53 cfs @ 12.09 hrs, Volume= 2.315 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 29

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 4.47" for 100-Year event


Inflow = 1.04 cfs @ 12.09 hrs, Volume= 0.074 af

Primary = 1.04 cfs @ 12.09 hrs, Volume= 0.074 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch





Printed 10/6/2020 Page 2

Area Listing (selected nodes)

Area	ı CN	Description
(acres))	(subcatchment-numbers)
1.573	39	>75% Grass cover, Good, HSG A (1A, 1B, 2)
1.029	63	Beach Sand, HSG A (1A)
0.304	30	Brush, Good, HSG A (1A)
0.467	98	Impervious Surface, HSG A (1A, 1B)
0.184	. 39	Permeable Playground Surface, Good, HSG A (1A)
0.521	98	Porous Pavement, HSG A (1A, 1B)
0.138	96	Stone Dust, HSG A (1A)
1.200	98	Water Surface, HSG A (1A)
5.416	68	TOTAL AREA

Printed 10/6/2020

Page 3

Soil Listing (selected nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
5.416	HSG A	1A, 1B, 2
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.000	Other	
5.416		TOTAL AREA

Printed 10/6/2020

Page 4

Subcatch Numbers

Ground Covers (selected nodes)

HSG-A	HSG-B	HSG-C	HSG-D	Other	Total	Ground
 (acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Cover
1.573	0.000	0.000	0.000	0.000	1.573	>75% Grass cover, Good
1.029	0.000	0.000	0.000	0.000	1.029	Beach Sand
0.304	0.000	0.000	0.000	0.000	0.304	Brush, Good
0.467	0.000	0.000	0.000	0.000	0.467	Impervious Surface
0.184	0.000	0.000	0.000	0.000	0.184	Permeable Playground Surface,
						Good
0.521	0.000	0.000	0.000	0.000	0.521	Porous Pavement
0.138	0.000	0.000	0.000	0.000	0.138	Stone Dust
1.200	0.000	0.000	0.000	0.000	1.200	Water Surface
5.416	0.000	0.000	0.000	0.000	5.416	TOTAL AREA

Printed 10/6/2020

Page 5

Pipe Listing (selected nodes)

Line#	Node	In-Invert	Out-Invert	Length	Slope	n	Diam/Width	Height	Inside-Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	P1	162.15	162.05	20.0	0.0050	0.013	12.0	0.0	0.0

2020.10.06 Proposed - Arlington Res

Type III 24-hr 1-Year Rainfall=2.67"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 6

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=0.43"

Tc=6.0 min CN=67 Runoff=1.65 cfs 0.166 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=1.07"

Tc=6.0 min CN=81 Runoff=0.84 cfs 0.061 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.00"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.000 af

Pond P1: Porous Pavement Peak Elev=161.40' Storage=0 cf Inflow=0.84 cfs 0.061 af

Discarded=0.84 cfs 0.061 af Primary=0.00 cfs 0.000 af Outflow=0.84 cfs 0.061 af

Link DP-1: Reservoir and Swimming Area Inflow=1.65 cfs 0.166 af

Primary=1.65 cfs 0.166 af

Link DP-2: Ditch Inflow=0.00 cfs 0.000 af

Primary=0.00 cfs 0.000 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.227 af Average Runoff Depth = 0.50" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Page 7


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 1.65 cfs @ 12.11 hrs, Volume= 0.166 af, Depth= 0.43"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Goo	Brush, Good, HSG A				
*		44,830	63	Beach Sand	d, HSG A				
		56,001	39	>75% Gras	s cover, Go	ood, HSG A			
		19,764	98	Impervious	Surface, H	SG A			
*		1,800	98	Porous Pav	ement, HS	GA			
		52,292	98	Water Surfa	ace, HSG A	1			
*		6,010	96	Stone Dust	HSG A				
*		8,011	39 Permeable Playground Surface, Good, HSG A						
	2	201,945	67	Weighted A	verage				
	1	28,089		63.43% Per	vious Area				
		73,856		36.57% Imp	ervious Ar	ea			
				•					
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/ft	t) (ft/sec)	(cfs)	•			
	6.0	•	•			Direct Entry,			

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Printed 10/6/2020 Page 8


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 0.84 cfs @ 12.09 hrs, Volume= 0.061 af, Depth= 1.07"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

	Α	rea (sf)	CN	Description				
		8,411	39	>75% Gras	s cover, Go	ood, HSG A		
		574	98	mpervious	Surface, H	SG A		
*		20,888	98	Porous Pavement, HSG A				
		29,873	81	Weighted Average				
		8,411	2	28.16% Pervious Area				
		21,462		71.84% Impervious Area				
	_							
	Tc	Length	Slope	,	Capacity	Description		
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	6.0					Direct Entry,		

Subcatchment 1B: Area Draining to Parking Lot



Page 9

Summary for Subcatchment 2: Subcatchment 2


[45] Hint: Runoff=Zero

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.67"

A	rea (sf)	CN [Description				
	4,115	39 >	>75% Grass cover, Good, HSG A				
	4,115	,	100.00% Pervious Area				
To	Longth	Slope	Volocity	Capacity	Description		
(min)	Length (feet)	(ft/ft)	(ft/sec)	(cfs)	Description		
6.0	, /		, ,		Direct Entry.		

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 10

Summary for Pond P1: Porous Pavement

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 1.07" for 1-Year event

Inflow = 0.84 cfs @ 12.09 hrs, Volume= 0.061 af

Outflow = 0.84 cfs @ 12.09 hrs, Volume= 0.061 af, Atten= 0%, Lag= 0.0 min

Discarded = 0.84 cfs @ 12.09 hrs, Volume= 0.061 af Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.40' @ 12.09 hrs Surf.Area= 21,411 sf Storage= 0 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 0.0 min (849.0 - 849.0)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Elevation	Surf.Area	Voids	Inc.Store	Cum.Store
(feet)	(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
162.23	21,411	0.0	0	0
162.48	21,411	40.0	2,141	2,141
162.81	21,411	30.0	2,120	4,261

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	-		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.09 hrs HW=161.40' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

1=Culvert (Controls 0.00 cfs)

2=Orifice/Grate (Controls 0.00 cfs)

Page 11

Pond P1: Porous Pavement



Printed 10/6/2020 Page 12

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 0.37" for 1-Year event

Inflow = 1.65 cfs @ 12.11 hrs, Volume= 0.166 af

Primary = 1.65 cfs @ 12.11 hrs, Volume= 0.166 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 13

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.00" for 1-Year event

Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 2-Year Rainfall=3.21" Printed 10/6/2020

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 14

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=0.69"

Tc=6.0 min CN=67 Runoff=3.15 cfs 0.267 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=1.48"

Tc=6.0 min CN=81 Runoff=1.18 cfs 0.084 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.00"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.000 af

Pond P1: Porous Pavement Peak Elev=161.40' Storage=1 cf Inflow=1.18 cfs 0.084 af

Discarded=1.17 cfs 0.084 af Primary=0.00 cfs 0.000 af Outflow=1.17 cfs 0.084 af

Link DP-1: Reservoir and Swimming Area Inflow=3.15 cfs 0.267 af

Primary=3.15 cfs 0.267 af

Link DP-2: Ditch Inflow=0.00 cfs 0.000 af

Primary=0.00 cfs 0.000 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.352 af Average Runoff Depth = 0.78" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Printed 10/6/2020 Page 15


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 3.15 cfs @ 12.10 hrs, Volume= 0.267 af, Depth= 0.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Goo	d, HSG A				
*		44,830	63	Beach Sand	d, HSG A				
		56,001	39	>75% Gras	s cover, Go	ood, HSG A			
		19,764	98	Impervious	Surface, H	SG A			
*		1,800	98	Porous Pav	ement, HS	G A			
		52,292	98	Water Surfa	ace, HSG A	1			
*		6,010	96	Stone Dust,	HSG A				
*		8,011	39	Permeable Playground Surface, Good, HSG A					
	2	201,945	67	Weighted A	verage				
	1	28,089		63.43% Per	vious Area				
	73,856 36.57% Impervious Area					ea			
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Printed 10/6/2020 Page 16


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 1.18 cfs @ 12.09 hrs, Volume= 0.084 af, Depth= 1.48"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

	Area (sf) CN	Description						
	8,41 ⁻	1 39	>75% Gras	s cover, Go	ood, HSG A				
	574	4 98	Impervious	mpervious Surface, HSG A					
*	20,888	98	Porous Pav	Porous Pavement, HSG A					
	29,873	3 81	Weighted Average						
	8,41 ⁻	1	28.16% Per	28.16% Pervious Area					
	21,462	2	71.84% Imp	71.84% Impervious Area					
	Tc Leng	th Slo	pe Velocity	Capacity	Description				
	(min) (fee	et) (ft/	ft) (ft/sec)	(cfs)					
	6.0			•	Direct Entry.				

Subcatchment 1B: Area Draining to Parking Lot



Page 17


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 2-Year Rainfall=3.21"

A	rea (sf)	CN E	Description						
	4,115	39 >	>75% Grass cover, Good, HSG A						
	4,115	1	100.00% Pervious Area						
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
6.0					Direct Entry,				

Subcatchment 2: Subcatchment 2



Printed 10/6/2020

Page 18

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=547)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 1.48" for 2-Year event
Inflow = 1.18 cfs @ 12.09 hrs, Volume= 0.084 af
Outflow = 1.17 cfs @ 12.10 hrs, Volume= 0.084 af, Atten= 0%, Lag= 0.4 min

Discarded = 1.17 cfs @ 12.10 hrs, Volume= 0.084 af Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.40' @ 12.10 hrs Surf.Area= 21,411 sf Storage= 1 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 0.0 min (839.4 - 839.4)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Elevation	Surf.Area	Voids	Inc.Store	Cum.Store
(feet)	(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
162.23	21,411	0.0	0	0
162.48	21,411	40.0	2,141	2,141
162.81	21,411	30.0	2,120	4,261

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.10 hrs HW=161.40' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Page 19

Pond P1: Porous Pavement



Page 20

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 0.60" for 2-Year event

Inflow = 3.15 cfs @ 12.10 hrs, Volume= 0.267 af

Primary = 3.15 cfs @ 12.10 hrs, Volume= 0.267 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Page 21

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.00" for 2-Year event

Inflow = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af

Primary = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 10-Year Rainfall=4.86"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020 Page 22

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=1.71"

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Tc=6.0 min CN=67 Runoff=8.92 cfs 0.659 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=2.86"

Tc=6.0 min CN=81 Runoff=2.30 cfs 0.164 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.17"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.001 af

Pond P1: Porous Pavement Peak Elev=161.46' Storage=515 cf Inflow=2.30 cfs 0.164 af

Discarded=1.19 cfs 0.164 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.164 af

Link DP-1: Reservoir and Swimming Area Inflow=8.92 cfs 0.659 af

Primary=8.92 cfs 0.659 af

Link DP-2: Ditch Inflow=0.00 cfs 0.001 af

Primary=0.00 cfs 0.001 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.824 af Average Runoff Depth = 1.83" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Page 23


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 8.92 cfs @ 12.09 hrs, Volume= 0.659 af, Depth= 1.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Goo	d, HSG A				
*		44,830	63	Beach Sand	d, HSG A				
		56,001	39	>75% Gras	s cover, Go	ood, HSG A			
		19,764	98	Impervious	Surface, H	SG A			
*		1,800	98	Porous Pav	ement, HS	G A			
		52,292	98	Water Surfa	ace, HSG A	1			
*		6,010	96	Stone Dust,	HSG A				
*		8,011	39	Permeable Playground Surface, Good, HSG A					
	2	201,945	67	Weighted A	verage				
	1	28,089		63.43% Per	vious Area				
	73,856 36.57% Impervious Area					ea			
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Page 24


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 2.30 cfs @ 12.09 hrs, Volume= 0.164 af, Depth= 2.86"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

	Α	rea (sf)	CN	Description						
_		8,411	39	>75% Gras	s cover, Go	ood, HSG A				
		574	98	Impervious	mpervious Surface, HSG A					
*		20,888	98	Porous Pavement, HSG A						
		29,873	81	Weighted Average						
		8,411		28.16% Pervious Area						
		21,462		71.84% Imp	ervious Ar					
			·							
	Тс	Length	Slope	e Velocity	Capacity	Description				
_	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)					
	6.0					Direct Entry.				

Subcatchment 1B: Area Draining to Parking Lot



Page 25


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.00 cfs @ 12.51 hrs, Volume= 0.001 af, Depth= 0.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.86"

A	rea (sf)	CN E	Description						
	4,115	39 >	>75% Grass cover, Good, HSG A						
	4,115	1	100.00% Pervious Area						
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
6.0					Direct Entry,				

Subcatchment 2: Subcatchment 2



Printed 10/6/2020

Page 26

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=576)

0.686 ac, 71.84% Impervious, Inflow Depth = 2.86" for 10-Year event Inflow Area = Inflow 2.30 cfs @ 12.09 hrs, Volume= 0.164 af

1.19 cfs @ 12.09 hrs, Volume= Outflow 0.164 af, Atten= 48%, Lag= 0.1 min

Discarded = 1.19 cfs @ 12.09 hrs, Volume= 0.164 af 0.00 hrs. Volume= 0.000 af Primary 0.00 cfs @

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.46' @ 12.23 hrs Surf.Area= 21,411 sf Storage= 515 cf

Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 1.6 min (821.9 - 820.3)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Elevation	Surf.Area	Voids	Inc.Store	Cum.Store
(feet)	(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
162.23	21,411	0.0	0	0
162.48	21,411	40.0	2,141	2,141
162.81	21,411	30.0	2,120	4,261

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	· ·		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.09 hrs HW=161.43' (Free Discharge) **T_3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

-1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Page 27

Pond P1: Porous Pavement



Page 28

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 1.49" for 10-Year event

Inflow 8.92 cfs @ 12.09 hrs, Volume= 0.659 af

8.92 cfs @ 12.09 hrs, Volume= Primary 0.659 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Page 29

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.17" for 10-Year event

Inflow = 0.00 cfs @ 12.51 hrs, Volume= 0.001 af

Primary = 0.00 cfs @ 12.51 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 25-Year Rainfall=6.17"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 30

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=2.66"

Tc=6.0 min CN=67 Runoff=14.29 cfs 1.027 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=4.04"

Tc=6.0 min CN=81 Runoff=3.22 cfs 0.231 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.50"

Tc=6.0 min CN=39 Runoff=0.02 cfs 0.004 af

Pond P1: Porous Pavement Peak Elev=161.55' Storage=1,280 cf Inflow=3.22 cfs 0.231 af

Discarded=1.19 cfs 0.231 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.231 af

Link DP-1: Reservoir and Swimming Area Inflow=14.29 cfs 1.027 af

Primary=14.29 cfs 1.027 af

Link DP-2: Ditch Inflow=0.02 cfs 0.004 af

Primary=0.02 cfs 0.004 af

Total Runoff Area = 5.416 ac Runoff Volume = 1.262 af Average Runoff Depth = 2.80" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

rinted 10/6/2020 Page 31


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 14.29 cfs @ 12.09 hrs, Volume= 1.027 af, Depth= 2.66"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Good, HSG A					
*		44,830	63	Beach Sand	d, HSG A				
		56,001	39	>75% Gras	s cover, Go	ood, HSG A			
		19,764	98	Impervious	Surface, H	SG A			
*		1,800	98	Porous Pav	ement, HS	G A			
		52,292	98	Water Surfa	ace, HSG A				
*		6,010	96	Stone Dust,	HSG A				
*		8,011	39	Permeable	Playground	Surface, Good, HSG A			
	2	201,945	67	Weighted A	verage				
	1	28,089		63.43% Per	vious Area				
		73,856		36.57% Imp	ervious Ar	ea			
	Тс	Length	Slop	e Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)				
6.0 Direct Entry,						Direct Entry,			

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Page 32


Summary for Subcatchment 1B: Area Draining to Parking Lot

3.22 cfs @ 12.09 hrs, Volume= 0.231 af, Depth= 4.04" Runoff

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

	Area (sf) CN	Description	Description					
	8,41 ⁻	1 39	>75% Gras	>75% Grass cover, Good, HSG A					
	574	4 98	Impervious	mpervious Surface, HSG A					
*	20,888	98	Porous Pav	Porous Pavement, HSG A					
	29,873	3 81	Weighted A	Weighted Average					
	8,41 ⁻	1	28.16% Per	28.16% Pervious Area					
	21,462	2	71.84% Imp	ervious Ar	ea				
	Tc Leng	th Slo	pe Velocity	Capacity	Description				
	(min) (fee	et) (ft/	ft) (ft/sec)	(cfs)					
	6.0			•	Direct Entry.				

Subcatchment 1B: Area Draining to Parking Lot



Printed 10/6/2020 Page 33


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.02 cfs @ 12.33 hrs, Volume= 0.004 af, Depth= 0.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 25-Year Rainfall=6.17"

A	rea (sf)	CN E	N Description						
	4,115	39 >	39 >75% Grass cover, Good, HSG A						
	4,115	1	100.00% Pervious Area						
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
6.0					Direct Entry,				

Subcatchment 2: Subcatchment 2



Printed 10/6/2020

Page 34

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=560)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 4.04" for 25-Year event

Inflow = 3.22 cfs @ 12.09 hrs, Volume= 0.231 af

Outflow = 1.19 cfs @ 12.04 hrs, Volume= 0.231 af, Atten= 63%, Lag= 0.0 min

Discarded = 1.19 cfs @ 12.04 hrs, Volume= 0.231 af

Primary = 0.00 cfs @ 0.00 hrs. Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.55' @ 12.35 hrs Surf.Area= 21,411 sf Storage= 1,280 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow) Center-of-Mass det. time= 4.6 min (815.0 - 810.4)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	(sq-ft) (%) 21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	·		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area


Discarded OutFlow Max=1.19 cfs @ 12.04 hrs HW=161.43' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater) 1=Culvert (Controls 0.00 cfs)

2=Orifice/Grate (Controls 0.00 cfs)

Page 35

Pond P1: Porous Pavement



Printed 10/6/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 36

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 2.32" for 25-Year event

Inflow = 14.29 cfs @ 12.09 hrs, Volume= 1.027 af

Primary = 14.29 cfs @ 12.09 hrs, Volume= 1.027 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Page 37

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.50" for 25-Year event

Inflow = 0.02 cfs @ 12.33 hrs, Volume= 0.004 af

Primary = 0.02 cfs @ 12.33 hrs, Volume= 0.004 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res

Type III 24-hr 100-Year Rainfall=8.85"

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 10/6/2020

Page 38

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment 1A: Subcatchment 1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=4.84"

Tc=6.0 min CN=67 Runoff=26.30 cfs 1.868 af

Subcatchment 1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=6.55"

Tc=6.0 min CN=81 Runoff=5.13 cfs 0.374 af

Subcatchment 2: Subcatchment 2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=1.53"

Tc=6.0 min CN=39 Runoff=0.13 cfs 0.012 af

Pond P1: Porous Pavement Peak Elev=161.81' Storage=3,521 cf Inflow=5.13 cfs 0.374 af

Discarded=1.19 cfs 0.374 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.374 af

Link DP-1: Reservoir and Swimming Area Inflow=26.30 cfs 1.868 af

Primary=26.30 cfs 1.868 af

Link DP-2: Ditch Inflow=0.13 cfs 0.012 af

Primary=0.13 cfs 0.012 af

Total Runoff Area = 5.416 ac Runoff Volume = 2.255 af Average Runoff Depth = 5.00" 59.60% Pervious = 3.228 ac 40.40% Impervious = 2.188 ac

Printed 10/6/2020

Page 39


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 26.30 cfs @ 12.09 hrs, Volume= 1.868 af, Depth= 4.84"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Α	rea (sf)	CN	Description						
		13,237	30	Brush, Good, HSG A						
* 44,830 63 Beach Sand, HSG A					Beach Sand, HSG A					
		56,001	39	>75% Gras	s cover, Go	ood, HSG A				
		19,764	98	Impervious	Surface, H	SG A				
*		1,800	98	Porous Pav	ement, HS	G A				
		52,292	98	Water Surfa	ace, HSG A	1				
*		6,010	96	Stone Dust,	Stone Dust, HSG A					
*		8,011	39	Permeable	Playground	Surface, Good, HSG A				
	2	201,945	67	Weighted A	verage					
	1	28,089		63.43% Per	vious Area					
		73,856		36.57% Imp	ervious Ar	ea				
	Tc	Length	Slop	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)					
6.0 Direct Entry,						Direct Entry,				

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Page 40


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 5.13 cfs @ 12.09 hrs, Volume= 0.374 af, Depth= 6.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

	Area (sf) CN	Description	Description					
	8,41 ⁻	1 39	>75% Gras	>75% Grass cover, Good, HSG A					
	574	4 98	Impervious	mpervious Surface, HSG A					
*	20,888	98	Porous Pav	Porous Pavement, HSG A					
	29,873	3 81	Weighted A	Weighted Average					
	8,41 ⁻	1	28.16% Per	28.16% Pervious Area					
	21,462	2	71.84% Imp	ervious Ar	ea				
	Tc Leng	th Slo	pe Velocity	Capacity	Description				
	(min) (fee	et) (ft/	ft) (ft/sec)	(cfs)					
	6.0			•	Direct Entry.				

Subcatchment 1B: Area Draining to Parking Lot



Page 41


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.13 cfs @ 12.11 hrs, Volume= 0.012 af, Depth= 1.53"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.85"

A	rea (sf)	CN E	Description					
	4,115	39 >	>75% Grass cover, Good, HSG A					
	4,115	1	100.00% Pervious Area					
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



Printed 10/6/2020 Page 42

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=514)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 6.55" for 100-Year event

Inflow = 5.13 cfs @ 12.09 hrs, Volume= 0.374 af

Outflow = 1.19 cfs @ 11.92 hrs, Volume= 0.374 af, Atten= 77%, Lag= 0.0 min

Discarded = 1.19 cfs @ 11.92 hrs, Volume= 0.374 af

Primary = 0.00 cfs @ 0.00 hrs. Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.81' @ 12.48 hrs Surf.Area= 21,411 sf Storage= 3,521 cf Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 14.9 min (811.7 - 796.9)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store			
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)			
161.40	21,411	0	0			
162.23	21,411	17,771	17,771			

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	(sq-ft) (%) 21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 11.92 hrs HW=161.43' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)


Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)

1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Page 43

Pond P1: Porous Pavement



2020.10.06 Proposed - Arlington Res

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 44

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 4.21" for 100-Year event

Inflow = 26.30 cfs @ 12.09 hrs, Volume= 1.868 af

Primary = 26.30 cfs @ 12.09 hrs, Volume= 1.868 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Page 45

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 1.53" for 100-Year event

Inflow = 0.13 cfs @ 12.11 hrs, Volume= 0.012 af

Primary = 0.13 cfs @ 12.11 hrs, Volume= 0.012 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Link DP-2: Ditch





	Δ	P	D	FI	N	ח	Ι¥	7	ח	١ (n	٨	I٦	П	N		ΙF	n	١.
1	м	_	_	ГΙ	v	.,	10			_		и	4 1		ıv	w		.,	١.

HYDROCAD STORMWATER MODEL REPORTS FOR ATLAS 14 PLUS ANALYSIS



Printed 12/30/2020

Page 2

Area Listing (all nodes)

Area	CN	Description	
(acres)		(subcatchment-numbers)	
1.531	49	50-75% Grass cover, Fair, HSG A (1, 2)	
1.317	63	Beach Sand, HSG A (1)	
0.379	30	Brush, Good, HSG A (1, 2)	
0.046	96	Dense Sand Path, HSG A (1)	
0.646	98	Gravel parking, HSG A (1, 2)	
0.234	98	Impervious Surface, HSG A (1, 2)	
0.055	39	Open Space, Good, HSG A (>75% Grass Cover) (1)	
1.207	98	Water Surface, HSG A (1)	
5.416	70	TOTAL AREA	

Printed 12/30/2020

Page 3

Soil Listing (all nodes)

Area (acres)	Soil Group	Subcatchment Numbers
5.416	HSG A	1, 2
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.000	Other	
5.416		TOTAL AREA

Printed 12/30/2020

Page 4

Ground Covers (all nodes)

	HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
_	,	,	, ,		, ,			
	1.531	0.000	0.000	0.000	0.000	1.531	50-75% Grass cover, Fair	1, 2
	1.317	0.000	0.000	0.000	0.000	1.317	Beach Sand	1
	0.379	0.000	0.000	0.000	0.000	0.379	Brush, Good	1, 2
	0.046	0.000	0.000	0.000	0.000	0.046	Dense Sand Path	1
	0.646	0.000	0.000	0.000	0.000	0.646	Gravel parking	1, 2
	0.234	0.000	0.000	0.000	0.000	0.234	Impervious Surface	1, 2
	0.055	0.000	0.000	0.000	0.000	0.055	Open Space, Good	1
	1.207	0.000	0.000	0.000	0.000	1.207	Water Surface	1
	5.416	0.000	0.000	0.000	0.000	5.416	TOTAL AREA	

Existing - Arlington Res Atlas 14 Plus

2020.10.06 Existing - Arlington Res Atlas Plus

Prepared by Woodard Curran

NRCC 24-hr D 1-Year Rainfall=2.93" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 5

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Subcatchment1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=0.72"

Tc=6.0 min CN=71 Runoff=3.86 cfs 0.313 af

Subcatchment2: Subcatchment2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=0.44"

Tc=6.0 min CN=64 Runoff=0.07 cfs 0.007 af

Link DP-1: Reservoir and Swimming Area Inflow=3.86 cfs 0.313 af

Primary=3.86 cfs 0.313 af

Link DP-2: Ditch Inflow=0.07 cfs 0.007 af

Primary=0.07 cfs 0.007 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.321 af Average Runoff Depth = 0.71" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Page 6

2020.10.06 Existing - Arlington Res Atlas Plus

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC


Summary for Subcatchment 1: Subcatchment 1

Runoff = 3.86 cfs @ 12.14 hrs, Volume= 0.313 af, Depth= 0.72"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 1-Year Rainfall=2.93"

	Ar	ea (sf)	CN	Description						
		14,435	30	Brush, Good, HSG A						
*	;	57,370	63	Beach Sand	d, HSG A					
*		1,998	96	Dense San	Dense Sand Path, HSG A					
	(63,530	49	50-75% Gra	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	ing, HSG A	A				
*		9,994	98	Impervious	Surface, H	HSG A				
	:	52,585	98	Water Surfa	Vater Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	HSG A (>75% Grass Cover)				
	2:	27,252	71	Weighted A	verage					
	1:	39,746		61.49% Pervious Area						
	;	87,506		38.51% Imp	ervious Ar	rea				
	Tc	Length	Slope	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/ft) (ft/sec)	(cfs)					
	6.0					Direct Entry				

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 7


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.07 cfs @ 12.14 hrs, Volume= 0.007 af, Depth= 0.44"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 1-Year Rainfall=2.93"

	Aı	rea (sf)	CN	Description							
		2,076	30	Brush, Goo	d, HSG A						
		3,179	49	50-75% Gra	ass cover, l	Fair, HSG A					
*		3,211	98	Gravel parking, HSG A							
		215	98	Impervious	mpervious Surface, HSG A						
		8,681	64	Weighted A	Veighted Average						
		5,255		60.53% Pervious Area							
		3,426		39.47% lmp	pervious Ar	ea					
	_				_						
	Тс	Length	Slope	,	Capacity	Description					
(1	min)	(feet)	(ft/ft	(ft/sec)	(cfs)						
	6.0					Direct Entry,					

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 8

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 0.72" for 1-Year event

Inflow = 3.86 cfs @ 12.14 hrs, Volume= 0.313 af

Primary = 3.86 cfs @ 12.14 hrs, Volume= 0.313 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 9

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 0.44" for 1-Year event

Inflow = 0.07 cfs @ 12.14 hrs, Volume= 0.007 af

Primary = 0.07 cfs @ 12.14 hrs, Volume= 0.007 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Existing - Arlington Res Atlas 14 Plus

2020.10.06 Existing - Arlington Res Atlas Plus

Prepared by Woodard Curran

NRCC 24-hr D 2-Year Rainfall=3.64" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 10

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Subcatchment1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=1.15"

Tc=6.0 min CN=71 Runoff=6.51 cfs 0.502 af

Subcatchment2: Subcatchment2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=0.78"

Tc=6.0 min CN=64 Runoff=0.15 cfs 0.013 af

Link DP-1: Reservoir and Swimming Area Inflow=6.51 cfs 0.502 af

Primary=6.51 cfs 0.502 af

Link DP-2: Ditch Inflow=0.15 cfs 0.013 af

Primary=0.15 cfs 0.013 af

Total Runoff Area = 5.416 ac Runoff Volume = 0.515 af Average Runoff Depth = 1.14" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 11


Summary for Subcatchment 1: Subcatchment 1

Runoff = 6.51 cfs @ 12.14 hrs, Volume= 0.502 af, Depth= 1.15"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 2-Year Rainfall=3.64"

	Ar	ea (sf)	CN	Description						
		14,435	30	Brush, Good, HSG A						
*	;	57,370	63	Beach Sand	d, HSG A					
*		1,998	96	Dense San	Dense Sand Path, HSG A					
	(63,530	49	50-75% Gra	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	ing, HSG A	A				
*		9,994	98	Impervious	Surface, H	HSG A				
	:	52,585	98	Water Surfa	Vater Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	HSG A (>75% Grass Cover)				
	2:	27,252	71	Weighted A	verage					
	1:	39,746		61.49% Pervious Area						
	;	87,506		38.51% Imp	ervious Ar	rea				
	Tc	Length	Slope	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/ft) (ft/sec)	(cfs)					
	6.0					Direct Entry				

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 12


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.15 cfs @ 12.14 hrs, Volume= 0.013 af, Depth= 0.78"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 2-Year Rainfall=3.64"

	Α	rea (sf)	CN	Description							
-		2,076	30	Brush, Goo	rush, Good, HSG A						
		3,179	49	50-75% Grass cover, Fair, HSG A							
*		3,211	98	Gravel parking, HSG A							
		215	98	Impervious Surface, HSG A							
		8,681	64	Weighted A	Veighted Average						
		5,255		60.53% Pervious Area							
		3,426		39.47% lm <mark>բ</mark>	pervious Ar	ea					
	Тс	Length	Slope	Velocity	Capacity	Description					
(min)	(feet)	(ft/ft	(ft/sec)	(cfs)						
	6.0					Direct Entry,					

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 13

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 1.15" for 2-Year event

Inflow = 6.51 cfs @ 12.14 hrs, Volume= 0.502 af

Primary = 6.51 cfs @ 12.14 hrs, Volume= 0.502 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 14

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 0.78" for 2-Year event

Inflow = 0.15 cfs @ 12.14 hrs, Volume= 0.013 af

Primary = 0.15 cfs @ 12.14 hrs, Volume= 0.013 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Existing - Arlington Res Atlas 14 Plus

2020.10.06 Existing - Arlington Res Atlas Plus

Prepared by Woodard Curran

NRCC 24-hr D 10-Year Rainfall=5.79" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 15

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Subcatchment1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=2.73"

Tc=6.0 min CN=71 Runoff=15.91 cfs 1.187 af

Subcatchment2: Subcatchment2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=2.11"

Tc=6.0 min CN=64 Runoff=0.46 cfs 0.035 af

Link DP-1: Reservoir and Swimming Area Inflow=15.91 cfs 1.187 af

Primary=15.91 cfs 1.187 af

Link DP-2: Ditch Inflow=0.46 cfs 0.035 af

Primary=0.46 cfs 0.035 af

Total Runoff Area = 5.416 ac Runoff Volume = 1.222 af Average Runoff Depth = 2.71" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 16


Summary for Subcatchment 1: Subcatchment 1

Runoff = 15.91 cfs @ 12.13 hrs, Volume= 1.187 af, Depth= 2.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 10-Year Rainfall=5.79"

	Ar	ea (sf)	CN	Description						
		14,435	30	Brush, Good, HSG A						
*	;	57,370	63	Beach Sand	d, HSG A					
*		1,998	96	Dense San	Dense Sand Path, HSG A					
	(63,530	49	50-75% Gra	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	ing, HSG A	A				
*		9,994	98	Impervious	Surface, H	HSG A				
	:	52,585	98	Water Surfa	Vater Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	HSG A (>75% Grass Cover)				
	2:	27,252	71	Weighted A	verage					
	1:	39,746		61.49% Pervious Area						
	;	87,506		38.51% Imp	ervious Ar	rea				
	Tc	Length	Slope	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/ft) (ft/sec)	(cfs)					
	6.0					Direct Entry				

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 17


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.46 cfs @ 12.13 hrs, Volume= 0.035 af, Depth= 2.11"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 10-Year Rainfall=5.79"

	Α	rea (sf)	CN	Description							
-		2,076	30	Brush, Goo	rush, Good, HSG A						
		3,179	49	50-75% Grass cover, Fair, HSG A							
*		3,211	98	Gravel parking, HSG A							
		215	98	Impervious Surface, HSG A							
		8,681	64	Weighted A	Veighted Average						
		5,255		60.53% Pervious Area							
		3,426		39.47% lm <mark>բ</mark>	pervious Ar	ea					
	Тс	Length	Slope	Velocity	Capacity	Description					
(min)	(feet)	(ft/ft	(ft/sec)	(cfs)						
	6.0					Direct Entry,					

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 18

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 2.73" for 10-Year event

Inflow = 15.91 cfs @ 12.13 hrs, Volume= 1.187 af

Primary = 15.91 cfs @ 12.13 hrs, Volume= 1.187 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 19

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 2.11" for 10-Year event

Inflow = 0.46 cfs @ 12.13 hrs, Volume= 0.035 af

Primary = 0.46 cfs @ 12.13 hrs, Volume= 0.035 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Existing - Arlington Res Atlas 14 Plus

2020.10.06 Existing - Arlington Res Atlas Plus

Prepared by Woodard Curran

NRCC 24-hr D 25-Year Rainfall=7.48" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 20

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Subcatchment1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=4.13"

Tc=6.0 min CN=71 Runoff=24.00 cfs 1.796 af

Subcatchment2: Subcatchment2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=3.37"

Tc=6.0 min CN=64 Runoff=0.75 cfs 0.056 af

Link DP-1: Reservoir and Swimming Area Inflow=24.00 cfs 1.796 af

Primary=24.00 cfs 1.796 af

Link DP-2: Ditch Inflow=0.75 cfs 0.056 af

Primary=0.75 cfs 0.056 af

Total Runoff Area = 5.416 ac Runoff Volume = 1.852 af Average Runoff Depth = 4.10" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 21


Summary for Subcatchment 1: Subcatchment 1

Runoff = 24.00 cfs @ 12.13 hrs, Volume= 1.796 af, Depth= 4.13"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 25-Year Rainfall=7.48"

	Α	rea (sf)	CN	Description							
		14,435	30	Brush, Goo	Brush, Good, HSG A						
*		57,370	63	Beach Sand	d, HSG A						
*		1,998	96	Dense San	Dense Sand Path, HSG A						
		63,530	49	50-75% Gra	50-75% Grass cover, Fair, HSG A						
*		24,927	98	Gravel park	ing, HSG A	4					
*		9,994	98	Impervious	Surface, H	SG A					
		52,585	98	Water Surfa	Nater Surface, HSG A						
*		2,413	39	Open Spac	Open Space, Good, HSG A (>75% Grass Cover)						
	2	27,252	71	Weighted A	verage						
	1	39,746		61.49% Per	vious Area	l					
		87,506		38.51% Imp	ervious Ar	ea					
				-							
	Tc	Length	Slop	e Velocity	Capacity	Description					
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)						
	6.0					Direct Entry,					

Subcatchment 1: Subcatchment 1



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 22


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.75 cfs @ 12.13 hrs, Volume= 0.056 af, Depth= 3.37"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 25-Year Rainfall=7.48"

	A	rea (sf)	CN I	Description							
Ī		2,076	30	Brush, Goo	rush, Good, HSG A						
		3,179	49	50-75% Grass cover, Fair, HSG A							
4	ŧ	3,211	98	Gravel parking, HSG A							
		215	98	Impervious Surface, HSG A							
		8,681	64 \	Weighted A	Veighted Average						
		5,255	(60.53% Pervious Area							
		3,426	,	39.47% Imp	ervious Ar	rea					
	Tc	Length	Slope	Velocity	Capacity	Description					
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		_				
	6.0					Direct Entry.					

Subcatchment 2: Subcatchment 2



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 23

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 4.13" for 25-Year event

Inflow = 24.00 cfs @ 12.13 hrs, Volume= 1.796 af

Primary = 24.00 cfs @ 12.13 hrs, Volume= 1.796 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 24

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 3.37" for 25-Year event

Inflow = 0.75 cfs @ 12.13 hrs, Volume= 0.056 af

Primary = 0.75 cfs @ 12.13 hrs, Volume= 0.056 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



Prepared by Woodard Curran

NRCC 24-hr D 100-Year Rainfall=10.35" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 25

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Subcatchment1 Runoff Area=227,252 sf 38.51% Impervious Runoff Depth=6.67"

Tc=6.0 min CN=71 Runoff=38.24 cfs 2.901 af

Subcatchment2: Subcatchment2 Runoff Area=8,681 sf 39.47% Impervious Runoff Depth=5.73"

Tc=6.0 min CN=64 Runoff=1.27 cfs 0.095 af

Link DP-1: Reservoir and Swimming Area Inflow=38.24 cfs 2.901 af

Primary=38.24 cfs 2.901 af

Link DP-2: Ditch Inflow=1.27 cfs 0.095 af

Primary=1.27 cfs 0.095 af

Total Runoff Area = 5.416 ac Runoff Volume = 2.997 af Average Runoff Depth = 6.64" 61.46% Pervious = 3.329 ac 38.54% Impervious = 2.088 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 26


Summary for Subcatchment 1: Subcatchment 1

Runoff = 38.24 cfs @ 12.13 hrs, Volume= 2.901 af, Depth= 6.67"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 100-Year Rainfall=10.35"

	Ar	ea (sf)	CN	Description						
		14,435	30	Brush, Good, HSG A						
*	;	57,370	63	Beach Sand	d, HSG A					
*		1,998	96	Dense San	Dense Sand Path, HSG A					
	(63,530	49	50-75% Gra	50-75% Grass cover, Fair, HSG A					
*		24,927	98	Gravel park	ing, HSG A	A				
*		9,994	98	Impervious	Surface, H	HSG A				
	:	52,585	98	Water Surfa	Vater Surface, HSG A					
*		2,413	39	Open Space	e, Good, H	HSG A (>75% Grass Cover)				
	2:	27,252	71	Weighted A	verage					
	1:	39,746		61.49% Pervious Area						
	;	87,506		38.51% Imp	ervious Ar	rea				
	Tc	Length	Slope	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/ft) (ft/sec)	(cfs)					
	6.0					Direct Entry				

Subcatchment 1: Subcatchment 1



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 27


Summary for Subcatchment 2: Subcatchment 2

Runoff = 1.27 cfs @ 12.13 hrs, Volume= 0.095 af, Depth= 5.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 100-Year Rainfall=10.35"

	Α	rea (sf)	CN I	Description						
Ī			_							
		3,179	Fair, HSG A							
4	ŧ	3,211	98	Gravel park	ing, HSG A	A				
		215	98	mpervious	Surface, H	HSG A				
		8,681	64 \	Weighted Average						
		5,255	(60.53% Pervious Area						
		3,426	,	39.47% Impervious Area						
	Тс	Length	Slope	Velocity	Capacity	Description				
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		_			
	6.0					Direct Entry.				

Subcatchment 2: Subcatchment 2





NRCC 24-hr D 100-Year Rainfall=10.35" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 28

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.217 ac, 38.51% Impervious, Inflow Depth = 6.67" for 100-Year event

Inflow = 38.24 cfs @ 12.13 hrs, Volume= 2.901 af

Primary = 38.24 cfs @ 12.13 hrs, Volume= 2.901 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 29

Summary for Link DP-2: Ditch


Inflow Area = 0.199 ac, 39.47% Impervious, Inflow Depth = 5.73" for 100-Year event


Inflow = 1.27 cfs @ 12.13 hrs, Volume= 0.095 af

Primary = 1.27 cfs @ 12.13 hrs, Volume= 0.095 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch





Printed 12/30/2020 Page 2

Area Listing (all nodes)

Area	CN	Description	
(acres)		(subcatchment-numbers)	
3.052	39	>75% Grass cover, Good, HSG A (1, 1A, 1B, 2)	
2.058	63	Beach Sand, HSG A (1, 1A)	
0.608	30	Brush, Good, HSG A (1, 1A)	
0.934	98	Impervious Surface, HSG A (1, 1A, 1B)	
0.184	39	Permeable Playground Surface, Good, HSG A (1A)	
0.184	39	Permeable Playground Surfaces, Good, HSG A (1)	
1.042	98	Porous Pavement, HSG A (1, 1A, 1B)	
0.276	96	Stone Dust, HSG A (1, 1A)	
2.401	98	Water Surface, HSG A (1, 1A)	
10.738	69	TOTAL AREA	

Printed 12/30/2020 Page 3

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
10.738	HSG A	1, 1A, 1B, 2
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
0.000	Other	
10.738		TOTAL AREA

Printed 12/30/2020 Page 4

> Subcato Number

Ground Covers (all nodes)

HSG-A	HSG-B	HSG-C	HSG-D	Other	Total	Ground
(acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Cover
 3.052	0.000	0.000	0.000	0.000	3.052	>75% Grass cover, Good
2.058	0.000	0.000	0.000	0.000	2.058	Beach Sand
0.608	0.000	0.000	0.000	0.000	0.608	Brush, Good
0.934	0.000	0.000	0.000	0.000	0.934	Impervious Surface
0.184	0.000	0.000	0.000	0.000	0.184	Permeable Playground Surface,
						Good
0.184	0.000	0.000	0.000	0.000	0.184	Permeable Playground Surfaces,
						Good
1.042	0.000	0.000	0.000	0.000	1.042	Porous Pavement
0.276	0.000	0.000	0.000	0.000	0.276	Stone Dust
2.401	0.000	0.000	0.000	0.000	2.401	Water Surface
10.738	0.000	0.000	0.000	0.000	10.738	TOTAL AREA

Printed 12/30/2020

Page 5

Pipe Listing (all nodes)

Line#	Node In-Invert		Out-Invert Length		Slope	n	Diam/Width	Height	Inside-Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	P1	162.15	162.05	20.0	0.0050	0.013	12.0	0.0	0.0

Page 6

2020.10.06 Proposed - Arlington Res Atlas Plus

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

NRCC 24-hr D 1-Year Rainfall=2.93" Printed 12/30/2020

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points Runoff by SCS TR-20 method, UH=SCS, Weighted-CN Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Runoff Area=231,818 sf 41.12% Impervious Runoff Depth=0.63" Subcatchment1: Total Subcatchment1

Tc=6.0 min CN=69 Runoff=3.32 cfs 0.281 af

Subcatchment1A: Subcatchment1 Runoff Area=201.945 sf 36.57% Impervious Runoff Depth=0.55"

Tc=6.0 min CN=67 Runoff=2.38 cfs 0.213 af

Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=1.26" Subcatchment1B: Area Draining to

Tc=6.0 min CN=81 Runoff=0.96 cfs 0.072 af

Subcatchment2: Subcatchment2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.00"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.000 af

Pond P1: Porous Pavement Peak Elev=161.40' Storage=0 cf Inflow=0.96 cfs 0.072 af

Discarded=0.96 cfs 0.072 af Primary=0.00 cfs 0.000 af Outflow=0.96 cfs 0.072 af

Link DP-1: Reservoir and Swimming Area Inflow=2.38 cfs 0.213 af

Primary=2.38 cfs 0.213 af

Link DP-2: Ditch Inflow=0.00 cfs 0.000 af

Primary=0.00 cfs 0.000 af

Total Runoff Area = 10.738 ac Runoff Volume = 0.565 af Average Runoff Depth = 0.63" 59.24% Pervious = 6.362 ac 40.76% Impervious = 4.376 ac

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 7


Summary for Subcatchment 1: Total Subcatchment 1 Area

Runoff = 3.32 cfs @ 12.14 hrs, Volume= 0.281 af, Depth= 0.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 1-Year Rainfall=2.93"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Good, HSG A					
*		44,830	63	Beach Sand	d, HSG A				
64,412 39 >75% Grass cover, Good, HSG A						ood, HSG A			
		20,338	98	Impervious	Surface, H	SG A			
*		22,688	98	Porous Pav	ement, HS	GA			
		52,292	98	Water Surfa	ace, HSG A	1			
*		6,010	96	Stone Dust, HSG A					
*		8,011	39	Permeable Playground Surfaces, Good, HSG A					
	2	31,818	69	Weighted A	verage				
136,500 58.88% Pervious Area									
95,318 41.12% Impervious Area						ea			
				-					
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)				
6.0						Direct Entry,			

Subcatchment 1: Total Subcatchment 1 Area



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 8


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 2.38 cfs @ 12.14 hrs, Volume= 0.213 af, Depth= 0.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 1-Year Rainfall=2.93"

_	Ar	ea (sf)	CN	Description				
	•	13,237	30	Brush, Goo	d, HSG A			
*	2	14,830	63	Beach San	d, HSG A			
	5	56,001	39	>75% Gras	s cover, Go	lood, HSG A		
	1	19,764	98	Impervious	Surface, H	HSG A		
*		1,800	98	Porous Pav	ement, HS	SG A		
	5	52,292	98	Water Surfa	ace, HSG A	A		
*		6,010	96	Stone Dust	, HSG A			
*		8,011	39	Permeable	Playground	nd Surface, Good, HSG A		
	20)1,945	67	Weighted A	verage			
	12	28,089		63.43% Per	rvious Area	a		
	7	73,856		36.57% Impervious Area				
				_				
	Tc	Length	Slop	e Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)			
	6.0					Direct Entry		

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Page 9

2020.10.06 Proposed - Arlington Res Atlas Plus

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 0.96 cfs @ 12.13 hrs, Volume= 0.072 af, Depth= 1.26"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 1-Year Rainfall=2.93"

	Area (sf)	CN	Description					
	8,411	39	>75% Gras	s cover, Go	Good, HSG A			
	574	98	Impervious	mpervious Surface, HSG A				
*	20,888	98	Porous Pav	Porous Pavement, HSG A				
	29,873	81	Weighted A	Weighted Average				
	8,411			28.16% Pervious Area				
	21,462		71.84% Imp	71.84% Impervious Area				
	Tc Length	Slop	,	Capacity	•			
(m	nin) (feet)	(ft/f	t) (ft/sec)	(cfs)				
	6.0				Direct Entry,			

Subcatchment 1B: Area Draining to Parking Lot



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 10

Printed 12/30/2020

Summary for Subcatchment 2: Subcatchment 2


[45] Hint: Runoff=Zero

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 1-Year Rainfall=2.93"

A	rea (sf)	CN E	escription					
	4,115	39 >	39 >75% Grass cover, Good, HSG A					
	4,115	1	100.00% Pervious Area					
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



NRCC 24-hr D 1-Year Rainfall=2.93"

Prepared by Woodard Curran

Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 11

Summary for Pond P1: Porous Pavement

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 1.26" for 1-Year event

Inflow = 0.96 cfs @ 12.13 hrs, Volume= 0.072 af

Outflow = 0.96 cfs @ 12.13 hrs, Volume= 0.072 af, Atten= 0%, Lag= 0.0 min

Discarded = 0.96 cfs @ 12.13 hrs, Volume= 0.072 af Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.40' @ 12.13 hrs Surf.Area= 21,411 sf Storage= 0 cf

Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 0.0 min (872.1 - 872.1)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surf.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
			L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.13 hrs HW=161.40' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)


1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 12

Pond P1: Porous Pavement



Printed 12/30/2020

Page 13

Summary for Link DP-1: Reservoir and Swimming Area

Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 0.48" for 1-Year event


Inflow = 2.38 cfs @ 12.14 hrs, Volume= 0.213 af

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Primary = 2.38 cfs @ 12.14 hrs, Volume= 0.213 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 14

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.00" for 1-Year event

Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res Atlas Plus

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 12/30/2020 Page 15

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Total Subcatchment1 Runoff Area=231,818 sf 41.12% Impervious Runoff Depth=1.04"

Tc=6.0 min CN=69 Runoff=5.88 cfs 0.461 af

Subcatchment1A: Subcatchment1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=0.93"

Tc=6.0 min CN=67 Runoff=4.47 cfs 0.359 af

Subcatchment1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=1.82"

Tc=6.0 min CN=81 Runoff=1.40 cfs 0.104 af

Subcatchment2: Subcatchment2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.02"

Tc=6.0 min CN=39 Runoff=0.00 cfs 0.000 af

Pond P1: Porous Pavement Peak Elev=161.40' Storage=37 cf Inflow=1.40 cfs 0.104 af

Discarded=1.19 cfs 0.104 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.104 af

Link DP-1: Reservoir and Swimming Area Inflow=4.47 cfs 0.359 af

Primary=4.47 cfs 0.359 af

Link DP-2: Ditch Inflow=0.00 cfs 0.000 af

Primary=0.00 cfs 0.000 af

Total Runoff Area = 10.738 ac Runoff Volume = 0.924 af Average Runoff Depth = 1.03" 59.24% Pervious = 6.362 ac 40.76% Impervious = 4.376 ac

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 16


Summary for Subcatchment 1: Total Subcatchment 1 Area

Runoff = 5.88 cfs @ 12.14 hrs, Volume= 0.461 af, Depth= 1.04"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 2-Year Rainfall=3.64"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Goo	Brush, Good, HSG A				
*		44,830	63	Beach Sand	d, HSG A				
		64,412	39	>75% Gras	s cover, Go	ood, HSG A			
		20,338	98	Impervious	Surface, H	SG A			
*		22,688	98	Porous Pav	ement, HS	GA			
		52,292	98	Water Surfa	ace, HSG A	1			
*		6,010	96	Stone Dust	, HSG A				
*		8,011	39	Permeable	Playground	d Surfaces, Good, HSG A			
	2	31,818	69	Weighted A	verage				
	1	36,500		58.88% Per	vious Area				
		95,318		41.12% Imp	ervious Ar	ea			
				•					
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)	•			
	6.0					Direct Entry,			

Subcatchment 1: Total Subcatchment 1 Area



Printed 12/30/2020

Page 17

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff 4.47 cfs @ 12.14 hrs, Volume= 0.359 af, Depth= 0.93"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 2-Year Rainfall=3.64"

_	Α	rea (sf)	CN	Description	ı					
_		13,237	30	Brush, Goo	Brush, Good, HSG A					
*		44,830	63	Beach San	d, HSG A					
		56,001	39	>75% Gras	s cover, Go	lood, HSG A				
		19,764	98	Impervious	Surface, H	HSG A				
*		1,800	98	Porous Pav	ement, HS	SG A				
		52,292	98	Water Surfa	ace, HSG A	A				
*		6,010	96	Stone Dust	, HSG A					
*	•	8,011	39	Permeable	Playground	d Surface, Good, HSG A				
_	2	201,945	67	Weighted A	verage					
	1	28,089		63.43% Pervious Area						
		73,856		36.57% Impervious Area						
	Tc	Length	Slop	e Velocity	Capacity	Description				
_	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)					
	6.0					Direct Entry				

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 18


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 1.40 cfs @ 12.13 hrs, Volume= 0.104 af, Depth= 1.82"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 2-Year Rainfall=3.64"

	Aı	rea (sf)	CN	Description					
		8,411	39	>75% Gras	s cover, Go	Good, HSG A			
		574	98	Impervious	mpervious Surface, HSG A				
*		20,888	98	Porous Pavement, HSG A					
		29,873	81	Weighted Average					
		8,411		28.16% Pervious Area					
		21,462		71.84% Impervious Area					
	_								
	Tc	Length	Slope	,	Capacity	•			
	(min)	(feet)	(ft/ft) (ft/sec)	(cfs)				
	6.0					Direct Entry,			

Subcatchment 1B: Area Draining to Parking Lot



2020.10.06 Proposed - Arlington Res Atlas Plus

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 19

Printed 12/30/2020


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af, Depth= 0.02"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 2-Year Rainfall=3.64"

 Α	rea (sf)	CN I	Description					
	4,115	39	75% Grass cover, Good, HSG A					
	4,115		100.00% Pervious Area					
 Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



NRCC 24-hr D 2-Year Rainfall=3.64" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 20

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=595)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 1.82" for 2-Year event

Inflow = 1.40 cfs @ 12.13 hrs, Volume= 0.104 af

Outflow = 1.19 cfs @ 12.16 hrs, Volume= 0.104 af, Atten= 14%, Lag= 1.4 min

Discarded = 1.19 cfs @ 12.16 hrs, Volume= 0.104 af Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Peak Elev= 161.40' @ 12.17 hrs Surf.Area= 21,411 sf Storage= 37 cf

Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 0.1 min (858.5 - 858.4)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surt.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.16 hrs HW=161.40' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)


1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 21

Pond P1: Porous Pavement



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 22

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 0.81" for 2-Year event

Inflow = 4.47 cfs @ 12.14 hrs, Volume= 0.359 af

Primary = 4.47 cfs @ 12.14 hrs, Volume= 0.359 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



2020.10.06 Proposed - Arlington Res Atlas Plus

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 12/30/2020 Page 23

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.02" for 2-Year event

Inflow = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af

Primary = 0.00 cfs @ 24.01 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res Atlas Plus

NRCC 24-hr D 10-Year Rainfall=5.79"

Prepared by Woodard Curran

Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 24

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Total Subcatchment1 Runoff Area=231,818 sf 41.12% Impervious Runoff Depth=2.55"

Tc=6.0 min CN=69 Runoff=15.13 cfs 1.131 af

Subcatchment1A: Subcatchment1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=2.37"

Tc=6.0 min CN=67 Runoff=12.22 cfs 0.917 af

Subcatchment1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=3.69"

Tc=6.0 min CN=81 Runoff=2.79 cfs 0.211 af

Subcatchment2: Subcatchment2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.39"

Tc=6.0 min CN=39 Runoff=0.01 cfs 0.003 af

Pond P1: Porous Pavement Peak Elev=161.49' Storage=748 cf Inflow=2.79 cfs 0.211 af

Discarded=1.19 cfs 0.211 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.211 af

Link DP-1: Reservoir and Swimming Area Inflow=12.22 cfs 0.917 af

Primary=12.22 cfs 0.917 af

Link DP-2: Ditch Inflow=0.01 cfs 0.003 af

Primary=0.01 cfs 0.003 af

Total Runoff Area = 10.738 ac Runoff Volume = 2.261 af Average Runoff Depth = 2.53" 59.24% Pervious = 6.362 ac 40.76% Impervious = 4.376 ac

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 25


Summary for Subcatchment 1: Total Subcatchment 1 Area

Runoff = 15.13 cfs @ 12.13 hrs, Volume= 1.131 af, Depth= 2.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 10-Year Rainfall=5.79"

	Α	rea (sf)	CN	Description						
		13,237	30	Brush, Goo	Brush, Good, HSG A					
*		44,830	63	Beach San	d, HSG A					
		64,412	39	>75% Gras	s cover, Go	ood, HSG A				
		20,338	98	Impervious	Surface, H	SG A				
*		22,688	98	Porous Pav	ement, HS	G A				
		52,292	98	Water Surfa	Water Surface, HSG A					
*		6,010	96	Stone Dust	, HSG A					
*		8,011	39	Permeable Playground Surfaces, Good, HSG A						
	231,818 69 Weighted Average									
	136,500 58.88% Pervious Area									
		95,318		41.12% Imp	ervious Ar	ea				
	Тс	Length	Slop	e Velocity	Capacity	Description				
	(min)	(feet)	(ft/f	t) (ft/sec)	(cfs)					
	6.0					Direct Entry,				

Subcatchment 1: Total Subcatchment 1 Area



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 26


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 12.22 cfs @ 12.13 hrs, Volume= 0.917 af, Depth= 2.37"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 10-Year Rainfall=5.79"

	Α	rea (sf)	CN	Description					
		13,237	30	Brush, Good, HSG A					
*		44,830	63	Beach Sand	d, HSG A				
		56,001	39	>75% Gras	s cover, Go	ood, HSG A			
		19,764	98	Impervious	Surface, H	SG A			
*		1,800	98	Porous Pav	ement, HS	GA			
		52,292	98	Water Surfa	Water Surface, HSG A				
*		6,010	96	Stone Dust, HSG A					
*		8,011	39	Permeable Playground Surface, Good, HSG A					
	2	01,945	67	Weighted A	verage				
	1	28,089		63.43% Per	vious Area				
		73,856		36.57% Imp	ervious Ar	ea			
				•					
	Tc	Length	Slop	e Velocity	Capacity	Description			
	(min)	(feet)	(ft/ft	(ft/sec)	(cfs)	•			
	6.0	•				Direct Entry,			

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 27


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff = 2.79 cfs @ 12.13 hrs, Volume= 0.211 af, Depth= 3.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 10-Year Rainfall=5.79"

	Area (sf)	CN	Description					
	8,411	39	>75% Gras	s cover, Go	Good, HSG A			
	574	98	Impervious	mpervious Surface, HSG A				
*	20,888	98	Porous Pav	Porous Pavement, HSG A				
•	29,873	81	Weighted A	Weighted Average				
	8,411		28.16% Per	28.16% Pervious Area				
	21,462		71.84% lmp	pervious Ar	vrea			
Tc (min)	9	Slop (ft/ff	,	Capacity (cfs)	•			
6.0					Direct Entry,			

Subcatchment 1B: Area Draining to Parking Lot



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 28


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.01 cfs @ 12.34 hrs, Volume= 0.003 af, Depth= 0.39"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 10-Year Rainfall=5.79"

	Α	rea (sf)	CN E	Description					
		4,115	39 >	>75% Grass cover, Good, HSG A					
_		4,115	1	100.00% Pervious Area					
	_				_				
	Tc	Length	Slope	Velocity	Capacity	Description			
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	6.0	•			•	Direct Entry			

Subcatchment 2: Subcatchment 2



Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 29

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=575)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 3.69" for 10-Year event

Inflow = 2.79 cfs @ 12.13 hrs, Volume= 0.211 af

Outflow = 1.19 cfs @ 12.10 hrs, Volume= 0.211 af, Atten= 57%, Lag= 0.0 min

Discarded = 1.19 cfs @ 12.10 hrs, Volume= 0.211 af Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Peak Elev= 161.49' @ 12.25 hrs Surf.Area= 21,411 sf Storage= 748 cf

Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 1.8 min (833.9 - 832.2)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surt.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

urt.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	(sq-ft) (%) 21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	·		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.10 hrs HW=161.43' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)


1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 12/30/2020 Page 30

Pond P1: Porous Pavement



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 31

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 2.07" for 10-Year event

Inflow = 12.22 cfs @ 12.13 hrs, Volume= 0.917 af

Primary = 12.22 cfs @ 12.13 hrs, Volume= 0.917 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 32

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.39" for 10-Year event

Inflow = 0.01 cfs @ 12.34 hrs, Volume= 0.003 af

Primary = 0.01 cfs @ 12.34 hrs, Volume= 0.003 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res Atlas Plus

NRCC 24-hr D 25-Year Rainfall=7.48" Printed 12/30/2020

Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 33

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Total Subcatchment1 Runoff Area=231,818 sf 41.12% Impervious Runoff Depth=3.91"

Tc=6.0 min CN=69 Runoff=23.23 cfs 1.735 af

Subcatchment1A: Subcatchment1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=3.69"

Tc=6.0 min CN=67 Runoff=19.13 cfs 1.427 af

Subcatchment1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=5.25"

Tc=6.0 min CN=81 Runoff=3.90 cfs 0.300 af

Subcatchment2: Subcatchment2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=0.95"

Tc=6.0 min CN=39 Runoff=0.06 cfs 0.007 af

Pond P1: Porous Pavement Peak Elev=161.59' Storage=1,616 cf Inflow=3.90 cfs 0.300 af

Discarded=1.19 cfs 0.300 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.300 af

Link DP-1: Reservoir and Swimming Area Inflow=19.13 cfs 1.427 af

Primary=19.13 cfs 1.427 af

Link DP-2: Ditch Inflow=0.06 cfs 0.007 af Primary=0.06 cfs 0.007 af

Total Runoff Area = 10.738 ac Runoff Volume = 3.469 af Average Runoff Depth = 3.88" 59.24% Pervious = 6.362 ac 40.76% Impervious = 4.376 ac

NRCC 24-hr D 25-Year Rainfall=7.48" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 34


Summary for Subcatchment 1: Total Subcatchment 1 Area

Runoff = 23.23 cfs @ 12.13 hrs, Volume= 1.735 af, Depth= 3.91"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 25-Year Rainfall=7.48"

_	Are	ea (sf)	CN	Description			
	1	3,237	30	Brush, Goo	d, HSG A		
*	4	4,830	63	Beach San	d, HSG A		
	6	34,412	39	>75% Gras	s cover, Go	ood, HSG A	
	2	20,338	98	Impervious	Surface, H	ISG A	
*	2	2,688	98	Porous Pav	ement, HS	SG A	
	5	2,292	98	Water Surfa	ace, HSG A	4	
*		6,010	96	Stone Dust	, HSG A		
*		8,011	39	Permeable	Playground	d Surfaces, Good, HSG A	
	23	231,818 69 Weighted Average					
136,500			58.88% Pervious Area				
	9	95,318 41.12% Impervious Area				rea	
	Tc	Length	Slope	e Velocity	Capacity	Description	
_	(min)	(feet)	(ft/ft) (ft/sec)	(cfs)		
	6.0					Direct Entry	

Subcatchment 1: Total Subcatchment 1 Area



NRCC 24-hr D 25-Year Rainfall=7.48" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 35


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff = 19.13 cfs @ 12.13 hrs, Volume= 1.427 af, Depth= 3.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 25-Year Rainfall=7.48"

	Area ((sf) C	N D	escription				
	13,2	237 3	30 B	Brush, Good, HSG A				
*	44,8	30 6	33 B	Beach Sand, HSG A				
	56,0	01 3	39 >	>75% Grass cover, Good, HSG A				
	19,7	'64 S	98 Ir	Impervious Surface, HSG A				
*	1,8	300 9	98 P	orous Pav	ement, HS	SG A		
	52,2	292 9	98 V	Water Surface, HSG A				
*	6,0)10 9	96 S	Stone Dust, HSG A				
*	8,0)11 3	39 P	Permeable Playground Surface, Good, HSG A				
	201,9	945 6	67 V	Veighted A	verage			
	128,089		28,089 63.43% Pervi			a		
	73,8	356	3	6.57% Imp	ervious Ar	rea		
	Tc Ler	ngth S	Slope	Velocity	Capacity	Description		
	(min) (f	eet)	(ft/ft)	(ft/sec)	(cfs)			
	6.0					Direct Entry.		

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Printed 12/30/2020 HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 36


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff 3.90 cfs @ 12.13 hrs, Volume= 0.300 af, Depth= 5.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 25-Year Rainfall=7.48"

	Area	(sf)	CN	Description				
8,411 39 >75% Grass cover, Good, HSG A								
574 98 Impervious Surface, HSG A								
*	20,	888	98	Porous Pavement, HSG A				
	29,	873	81	Weighted Average				
	8,	411		28.16% Pervious Area				
	21,	462		71.84% Impervious Area				
			01			5		
		ength	Slope	,	Capacity	Description		
(1	min) ((feet)	(ft/ft)	(ft/sec)	(cfs)			
	6.0					Direct Entry,		

Subcatchment 1B: Area Draining to Parking Lot



NRCC 24-hr D 25-Year Rainfall=7.48"

Prepared by Woodard Curran

Printed 12/30/2020 Page 37

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC


Summary for Subcatchment 2: Subcatchment 2

Runoff = 0.06 cfs @ 12.15 hrs, Volume= 0.007 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 25-Year Rainfall=7.48"

A	rea (sf)	CN [Description					
	4,115	39 >	>75% Grass cover, Good, HSG A					
	4,115	1	100.00% Pervious Area					
Tc (min)	Length (feet)	Slope (ft/ft)	Slope Velocity Capacity Description (ft/ft) (ft/sec) (cfs)					
6.0					Direct Entry,			

Subcatchment 2: Subcatchment 2



NRCC 24-hr D 25-Year Rainfall=7.48" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 38

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=554)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 5.25" for 25-Year event

Inflow = 3.90 cfs @ 12.13 hrs, Volume= 0.300 af

Outflow = 1.19 cfs @ 12.04 hrs, Volume= 0.300 af, Atten= 69%, Lag= 0.0 min

Discarded = 1.19 cfs @ 12.04 hrs, Volume= 0.300 af Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.59' @ 12.31 hrs Surf.Area= 21,411 sf Storage= 1,616 cf

Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 4.8 min (824.0 - 819.2)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Elevation	Surt.Area	Inc.Store	Cum.Store
(feet)	(sq-ft)	(cubic-feet)	(cubic-feet)
161.40	21,411	0	0
162.23	21,411	17,771	17,771

c-feet)
0
2,141
4,261

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 12.04 hrs HW=161.43' (Free Discharge) **3=Exfiltration** (Exfiltration Controls 1.19 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)


1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 12/30/2020 Page 39

Pond P1: Porous Pavement



NRCC 24-hr D 25-Year Rainfall=7.48" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 40

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 3.22" for 25-Year event

Inflow = 19.13 cfs @ 12.13 hrs, Volume= 1.427 af

Primary = 19.13 cfs @ 12.13 hrs, Volume= 1.427 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



NRCC 24-hr D 25-Year Rainfall=7.48" Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 41

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 0.95" for 25-Year event

Inflow = 0.06 cfs @ 12.15 hrs, Volume= 0.007 af

Primary = 0.06 cfs @ 12.15 hrs, Volume= 0.007 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch



2020.10.06 Proposed - Arlington Res Atlas PlusNRCC 24-hr D 100-Year Rainfall=10.35" Prepared by Woodard Curran Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Printed 12/30/2020 Page 42

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment1: Total Subcatchment1 Runoff Area=231,818 sf 41.12% Impervious Runoff Depth=6.41"

Tc=6.0 min CN=69 Runoff=37.63 cfs 2.841 af

Subcatchment1A: Subcatchment1 Runoff Area=201,945 sf 36.57% Impervious Runoff Depth=6.14"

Tc=6.0 min CN=67 Runoff=31.54 cfs 2.371 af

Subcatchment1B: Area Draining to Runoff Area=29,873 sf 71.84% Impervious Runoff Depth=7.99"

Tc=6.0 min CN=81 Runoff=5.79 cfs 0.456 af

Subcatchment2: Subcatchment2 Runoff Area=4,115 sf 0.00% Impervious Runoff Depth=2.28"

Tc=6.0 min CN=39 Runoff=0.21 cfs 0.018 af

Pond P1: Porous Pavement Peak Elev=161.80' Storage=3,457 cf Inflow=5.79 cfs 0.456 af

Discarded=1.19 cfs 0.456 af Primary=0.00 cfs 0.000 af Outflow=1.19 cfs 0.456 af

Link DP-1: Reservoir and Swimming Area Inflow=31.54 cfs 2.371 af

Primary=31.54 cfs 2.371 af

Link DP-2: Ditch Inflow=0.21 cfs 0.018 af

Primary=0.21 cfs 0.018 af

Total Runoff Area = 10.738 ac Runoff Volume = 5.686 af Average Runoff Depth = 6.35" 59.24% Pervious = 6.362 ac 40.76% Impervious = 4.376 ac

Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 43


Summary for Subcatchment 1: Total Subcatchment 1 Area

Runoff 37.63 cfs @ 12.13 hrs, Volume= 2.841 af, Depth= 6.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 100-Year Rainfall=10.35"

_	Are	ea (sf)	CN	Description				
	1	3,237	30	Brush, Good, HSG A				
*	4	4,830	63	Beach Sand, HSG A				
	6	34,412	39	>75% Grass cover, Good, HSG A				
	2	20,338	98	Impervious Surface, HSG A				
*	2	2,688	98	Porous Pav	ement, HS	SG A		
	5	2,292	98	Water Surface, HSG A				
*		6,010	96	Stone Dust	, HSG A			
*		8,011	39	Permeable Playground Surfaces, Good, HSG A				
	23	31,818	69	Weighted A	verage			
	13	6,500		58.88% Per	rvious Area	a a constant of the constant o		
	95,318		95,318 41.1		41.12% Impervious Area			
	Tc	Length	Slope	e Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft) (ft/sec)	(cfs)			
	6.0					Direct Entry		

Subcatchment 1: Total Subcatchment 1 Area



Page 44


Summary for Subcatchment 1A: Subcatchment 1 Minus Parking Lot

Runoff 31.54 cfs @ 12.13 hrs, Volume= 2.371 af, Depth= 6.14"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 100-Year Rainfall=10.35"

	Area (sf) C	N D	escription		
	13,2	237 3	30 B	rush, Goo	d, HSG A	
*	44,8	30 6	33 B	each Sand	d, HSG A	
	56,0	01 3	39 >	75% Grass	s cover, Go	ood, HSG A
	19,7	'64 9	98 Ir	npervious	Surface, H	HSG A
*	1,8	800 9	98 P	orous Pav	ement, HS	SG A
	52,2	92 9	98 V	Vater Surfa	ice, HSG A	A
*	6,0	10 9	96 S	tone Dust,	HSG A	
*	8,0	11 3	Permeable Playground Surface, Good, HSG A			
	201,9	945 6	67 V	Veighted A	verage	
	128,0	89	6	3.43% Per	vious Area	a
	73,8	356	3	6.57% Imp	ervious Ar	rea
			Slope	Velocity	Capacity	Description
	(min) (f	eet)	(ft/ft)	(ft/sec)	(cfs)	
	6.0					Direct Entry.

Subcatchment 1A: Subcatchment 1 Minus Parking Lot



Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 45


Summary for Subcatchment 1B: Area Draining to Parking Lot

Runoff 5.79 cfs @ 12.13 hrs, Volume= 0.456 af, Depth= 7.99"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 100-Year Rainfall=10.35"

	rea (sf)	CN	Description			
	8,411	39	>75% Gras	s cover, Go	ood, HSG A	
	574	98	Impervious	Surface, H	SG A	
*	20,888	98	Porous Pav	ement, HS	G A	
	29,873 81 Weighted Average					
	8,411		28.16% Pei	vious Area	1	
	21,462	,	71.84% lmp	ervious Ar	ea	
Tc (min)	Length (feet)	Slope (ft/ft)	,	Capacity (cfs)	Description	
6.0					Direct Entry,	

Subcatchment 1B: Area Draining to Parking Lot



Prepared by Woodard Curran

Printed 12/30/2020

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 46


Summary for Subcatchment 2: Subcatchment 2

Runoff 0.21 cfs @ 12.14 hrs, Volume= 0.018 af, Depth= 2.28"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs NRCC 24-hr D 100-Year Rainfall=10.35"

A	rea (sf)	CN E	Description			
	4,115	39 >	39 >75% Grass cover, Good, HSG A			
	4,115	1	100.00% Pervious Area			
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
6.0					Direct Entry,	

Subcatchment 2: Subcatchment 2



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 47

Summary for Pond P1: Porous Pavement

[87] Warning: Oscillations may require smaller dt or Finer Routing (severity=510)

Inflow Area = 0.686 ac, 71.84% Impervious, Inflow Depth = 7.99" for 100-Year event

Inflow 5.79 cfs @ 12.13 hrs, Volume= 0.456 af

Outflow 1.19 cfs @ 11.96 hrs, Volume= 0.456 af, Atten= 79%, Lag= 0.0 min

1.19 cfs @ 11.96 hrs, Volume= 0.456 af Discarded = 0.00 cfs @ 0.00 hrs, Volume= Primary 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Peak Elev= 161.80' @ 12.41 hrs Surf.Area= 21,411 sf Storage= 3,457 cf

Flood Elev= 164.00' Surf.Area= 42,822 sf Storage= 11,383 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)

Center-of-Mass det. time= 12.9 min (817.1 - 804.2)

Volume	Invert	Avail.Storage	Storage Description
#1	161.40'	7,099 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
			17,771 cf Overall - 23 cf Embedded = 17,749 cf x 40.0% Voids
#2	162.23'	4,261 cf	Custom Stage Data (Prismatic)Listed below (Recalc)
#3	161.73'	23 cf	4.0" Round Pipe Storage Inside #1
			L= 258.0'

11,383 cf Total Available Storage

Surf.Area	Inc.Store	Cum.Store
(sq-ft)	(cubic-feet)	(cubic-feet)
21,411	0	0
21,411	17,771	17,771
	(sq-ft) 21,411	(sq-ft) (cubic-feet) 21,411 0

Surf.Area	Voids	Inc.Store	Cum.Store
(sq-ft)	(%)	(cubic-feet)	(cubic-feet)
21,411	0.0	0	0
21,411	40.0	2,141	2,141
21,411	30.0	2,120	4,261
	(sq-ft) 21,411 21,411	(sq-ft) (%) 21,411 0.0 21,411 40.0	(sq-ft) (%) (cubic-feet) 21,411 0.0 0 21,411 40.0 2,141

Device	Routing	Invert	Outlet Devices
#1	Primary	162.15'	12.0" Round Culvert
	•		L= 20.0' CPP, mitered to conform to fill, Ke= 0.700
			Inlet / Outlet Invert= 162.15' / 162.05' S= 0.0050 '/' Cc= 0.900
			n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	161.73'	4.0" Vert. Orifice/Grate C= 0.600
#3	Discarded	161.40'	2.410 in/hr Exfiltration over Surface area

Discarded OutFlow Max=1.19 cfs @ 11.96 hrs HW=161.43' (Free Discharge) **T—3=Exfiltration** (Exfiltration Controls 1.19 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=161.40' TW=0.00' (Dynamic Tailwater)


-1=Culvert (Controls 0.00 cfs)

²⁼Orifice/Grate (Controls 0.00 cfs)

Page 48

Prepared by Woodard Curran
HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Pond P1: Porous Pavement



Prepared by Woodard Curran

HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 49

Summary for Link DP-1: Reservoir and Swimming Area


Inflow Area = 5.322 ac, 41.12% Impervious, Inflow Depth = 5.35" for 100-Year event

2.371 af Inflow 31.54 cfs @ 12.13 hrs, Volume=

31.54 cfs @ 12.13 hrs, Volume= 2.371 af, Atten= 0%, Lag= 0.0 min Primary

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-1: Reservoir and Swimming Area



HydroCAD® 10.00-21 s/n 01204 © 2018 HydroCAD Software Solutions LLC

Page 50

Summary for Link DP-2: Ditch


Inflow Area = 0.094 ac, 0.00% Impervious, Inflow Depth = 2.28" for 100-Year event

Inflow 0.21 cfs @ 12.14 hrs, Volume= 0.018 af

0.21 cfs @ 12.14 hrs, Volume= 0.018 af, Atten= 0%, Lag= 0.0 min **Primary**

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link DP-2: Ditch





APPENDIX E: OPERATIONS & MAINTENANCE PLAN

STORMWATER MANAGEMENT SYSTEM OPERATION & MAINTENANCE PLAN

This Stormwater Management System Operations & Maintenance Plan (the Plan) outlines measures that are essential for maintaining an effective stormwater management system at the Arlington Reservoir, located at 210 Lowell Street in Arlington, Massachusetts (the Site). Periodic and scheduled inspections and maintenance measures are recommended to prevent deficiencies and for proper performance of the stormwater management system. Failure to implement these measures can reduce the hydraulic capacity and the pollutant removal efficiency of stormwater measures resulting in a poor quality of stormwater runoff discharging from the Site.

RESPONSIBLE PARTY & ESTIMATED ANNUAL BUDGET

The party responsible for implementing this Plan and identifying the source of necessary funds is as follows:

Town of Arlington, Massachusetts – Department of Public Works 51 Grove Street Arlington, MA 02476 Telephone: (781) 316-3301

GOOD HOUSEKEEPING

The Site will be maintained as clean and orderly. Routine inspections of the Site for debris and sediment accumulations shall be performed. Debris and sediment shall be disposed of in accordance with local and State requirements.

INSPECTIONS & MAINTENANCE MEASURES

Stormwater management is provided by porous pavement sections, as illustrated on the Site Plans. Routine inspections and maintenance of the stormwater management system shall be performed in accordance with this Operation & Maintenance Plan. These measures are recommended to prevent deficiencies within the system that may result in poor quality of stormwater runoff.

A sample Inspection Form is attached and is recommended for use during inspections of the stormwater management system. The form includes a table that outlines specific inspection and maintenance measures, in addition to the following information that can be recorded by the inspector during the inspection. Completed Inspections Forms shall be kept at the Site to enable both Department of Public Works staff members and regulatory agencies to ensure that operation of the system is in compliance with this Operation & Maintenance Plan.

SOLID WASTE CONTAINMENT

Trash and recycling receptacles will be provided throughout the Site, as necessary. Receptacles should remain covered to prevent exposure with stormwater and to ensure waste will remain inside the receptacle. Waste collection must be performed regularly.

LANDSCAPE MANAGEMENT

Lawn and landscaped areas shall be inspected for patches of dead vegetation and erosion. If these conditions are observed, affected areas shall be stabilized and replanted with vegetation to prevent sediment from entering the stormwater management system.

The following measures shall be followed to minimize the potential for stormwater runoff pollution due to overwatering, dead vegetation and erosion, direct disposal of lawn clippings, and over-application of materials such as fertilizers and pesticides.

Lawn Mowing

The following mowing practices are recommended:

Maintain sharp mower blades.

- Typically, avoid cutting grass shorter than 2 to 3 inches in height, to minimize weed growth. Grass can be cut lower in the spring and fall to stimulate root growth but should not be cut shorter than 11/2 inches.
- Do not dispose of grass clippings within the stormwater management system.
- Employ practices to minimize the potential for grass clippings to enter the stormwater management system.

Fertilizers & Pesticides

Use of pesticides and fertilizers should be minimized to the extent practicable. Application of these materials may degrade the quality of stormwater runoff and should therefore be applied cautiously. In addition, fertilizers and pesticides shall not be applied prior to rain events. These materials should be stored under cover to prevent their exposure to stormwater.

PERVIOUS AREA MANAGEMENT

Winter Operations

Remove accumulated snow after winter storm events to keep the site's parking lots open for operations and maintenance activities. Snow shall not be stored within pervious areas.

Plows with poly cutting blades are required for snow removal. With their use, no alterations to typical snow removal activities are required. Sand will prematurely clog the porous pavement system and should not be used for deicing. Magnesium Chloride is an alternative material that can be used for deicing, if necessary. Snow melts faster on porous pavement than traditional pavement, as melting water does not remain on the surface to insulate the remaining ice.

Pervious Pavement

The pervious pavement system shall be monitored for permeability and maintained with a regenerative air sweeper at least twice a year or more frequently, as needed. The frequency of cleanings will vary depending on Site conditions including frequency of traffic, local climate, and surrounding environment but should be performed once in the Spring and once in the Fall (after leaves have fallen but before the first snow fall) to assure the pavement's long function life.

Damage to the surface of the porous pavement can be repaired by using a concrete saw to remove the damaged area and installing new porous pavement in its place.

STORMWATER MANAGEMENT SYSTEM INSPECTION FORM

Town of Arlington, Massachusetts
Arlington Reservoir
210 Lowell Street
Arlington, MA 02474

Name of Inspector:			
Date/Time:			
Weather:			
Date of Last Inspection:			
Items Inspected (refer to Table 1	and provide additional s	heets if necessary):	
	_		
Comments & Corrective Actions	Taken (provide additiona	nl sheets if necessary):	
	_		
	_		

Table 1 – Operations & Maintenance Measures

	Porous Pavement					
Objective: Maintain the i	nfiltration and storage capacity of the porous pavement section.					
Frequency	Measure					
Ongoing/As Needed	 Monitor the surface of the porous pavement to proper drainage is achieved during storm events. 					
Quarterly	Remove sediment and organic debris on the porous pavement surface using a vacuum sweeper.					
Bi-Annually (once in Spring and once in Fall)	 Inspect the surface of the porous pavement for deterioration or clogging. Assess the infiltration capacity of the porous pavement sections. 					
Additional Comments	 Do not stockpile snow on porous pavement surface. This will require additional maintenance and vacuuming. Do not sand over porous pavement surface. 					

October 2020444 of 479



APPENDIX F: STORMWATER POLLUTION PREVENTION PLAN



APPENDIX G: MASSDEP CHECKLIST FOR STORMWATER REPORT



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.





A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the Massachusetts Stormwater Handbook. The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals. This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

	ormwater Checklist is accurate and that the information presented in the effects conditions at the site as of the date of this permit application.
Registered Professional Engine	er Block and Signature
	Signature and Date
	Checklist
Project Type: Is the application redevelopment?	for new development, redevelopment, or a mix of new and
□ Redevelopment	
☐ Mix of New Development ar	nd Redevelopment



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

env	rironmentally sensitive design and LID Techniques were considered during the planning and design of project:
	No disturbance to any Wetland Resource Areas
	Site Design Practices (e.g. clustered development, reduced frontage setbacks)
\boxtimes	Reduced Impervious Area (Redevelopment Only)
\boxtimes	Minimizing disturbance to existing trees and shrubs
	LID Site Design Credit Requested:
	☐ Credit 1
	☐ Credit 2
	☐ Credit 3
\boxtimes	Use of "country drainage" versus curb and gutter conveyance and pipe
	Bioretention Cells (includes Rain Gardens)
	Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
	Treebox Filter
	Water Quality Swale
	Grass Channel
	Green Roof
	Other (describe):
Sta	ndard 1: No New Untreated Discharges
\boxtimes	No new untreated discharges
	Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
	Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued) Standard 2: Peak Rate Attenuation Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding. Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm. Calculations provided to show that post-development peak discharge rates do not exceed predevelopment rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24hour storm. Standard 3: Recharge Soil Analysis provided. Required Recharge Volume calculation provided. Required Recharge volume reduced through use of the LID site Design Credits. Sizing the infiltration, BMPs is based on the following method: Check the method used. Static Simple Dynamic Dynamic Field¹ Runoff from all impervious areas at the site discharging to the infiltration BMP. Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume. Recharge BMPs have been sized to infiltrate the Required Recharge Volume. Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason: Site is comprised solely of C and D soils and/or bedrock at the land surface Solid Waste Landfill pursuant to 310 CMR 19.000 Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable. Calculations showing that the infiltration BMPs will drain in 72 hours are provided. Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Cł	necklist (continued)
Sta	ndard 3: Recharge (continued)
	The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
	Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.
Sta	ndard 4: Water Quality
The	B Long-Term Pollution Prevention Plan typically includes the following: Good housekeeping practices; Provisions for storing materials and waste products inside or under cover; Vehicle washing controls; Requirements for routine inspections and maintenance of stormwater BMPs; Spill prevention and response plans; Provisions for maintenance of lawns, gardens, and other landscaped areas; Requirements for storage and use of fertilizers, herbicides, and pesticides; Pet waste management provisions; Provisions for operation and management of septic systems; Provisions for solid waste management; Snow disposal and plowing plans relative to Wetland Resource Areas; Winter Road Salt and/or Sand Use and Storage restrictions; Street sweeping schedules; Provisions for prevention of illicit discharges to the stormwater management system; Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL; Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan; List of Emergency contacts for implementing Long-Term Pollution Prevention Plan. A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent. Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge: is within the Zone II or Interim Wellhead Protection Area
	is near or to other critical areas
	is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
	involves runoff from land uses with higher potential pollutant loads.
	The Required Water Quality Volume is reduced through use of the LID site Design Credits.
	Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Cł	necklist (continued)
Sta	andard 4: Water Quality (continued)
	The BMP is sized (and calculations provided) based on:
	☐ The ½" or 1" Water Quality Volume or
	☐ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
	The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
	A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.
Sta	ndard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)
	The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report. The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted <i>prior</i> to the discharge of stormwater to the post-construction stormwater BMPs.
\boxtimes	The NPDES Multi-Sector General Permit does <i>not</i> cover the land use.
	LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
	All exposure has been eliminated.
	All exposure has <i>not</i> been eliminated and all BMPs selected are on MassDEP LUHPPL list.
	The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.
Sta	ndard 6: Critical Areas
	The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
\boxtimes	Critical areas and BMPs are identified in the Stormwater Report.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

The project is subject to the Stormwater Management Standards only to the maximum Extent

Practicable as a:
☐ Limited Project
 Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area. Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
☐ Bike Path and/or Foot Path
□ Redevelopment Project
Redevelopment portion of mix of new and redevelopment.
Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report. The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.
- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands Program

Checklist for Stormwater Report

Checklist (continued) Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued) The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has not been included in the Stormwater Report but will be submitted **before** land disturbance begins. The project is **not** covered by a NPDES Construction General Permit. The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report. ☐ The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins. Standard 9: Operation and Maintenance Plan The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information: Name of the stormwater management system owners; Party responsible for operation and maintenance; Schedule for implementation of routine and non-routine maintenance tasks; ☐ Plan showing the location of all stormwater BMPs maintenance access areas; Description and delineation of public safety features; Estimated operation and maintenance budget; and Operation and Maintenance Log Form. The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions: A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs; A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions. Standard 10: Prohibition of Illicit Discharges ☐ The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges; An Illicit Discharge Compliance Statement is attached;

NO Illicit Discharge Compliance Statement is attached but will be submitted *prior to* the discharge of

any stormwater to post-construction BMPs.



woodardcurran.com commitment & integrity drive results



Town of Arlington, Massachusetts

Request for Determination of Applicability

Summary:

Request for Determination of Applicability: 59 Lowell Street

Arlington File #A21.1

8:30pm The project proposes to construct an above-ground exercise swim spa partially within the Wetlands 100-ft Buffer and Adjacent Upload Resource Area (AURA) of No Name Brook.

ATTACHMENTS:

	Туре	File Name	Description
۵	Request for Determination of Applicability	59_Lowell_Street_RDA_WPA_Form_1.pdf	59 Lowell St RDA WPA Form 1
۵	Request for Determination of Applicability	59_Lowell_Street_RDA.pdf	59 Lowell St RDA
ם	Request for Determination of Applicability	59_Lowell_Street_RDA_Photos.pdf	59 Lowell St RDA Site Photos



Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return

key.

Massachusetts Department of Environmental Protection Bureau of Resource Protection - Wetlands

Arlington City/Town

WPA Form 1- Request for Determination of Applicability

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

A. General Information

Kathleen Moriarty	kathleen mo	riarty.ietf@gmail.com
Name	E-Mail Address	
59 Lowell Street		
Mailing Address		
Arlington	MA	02476
City/Town	State	Zip Code
617-583-0846 Phone Number	Fax Number (if	applicable)
	r ax rramber (ii	арриодыю
Representative (if any):		
Firm		
Contact Name	E-Mail Address	, /
Mailing Address		
City/Town	State	Zip Code
and the second periods of the second periods	The state of the state of the	. 4.
Phone Number	Car Niveshaa //6	
	rax Number (ii	applicable)
I request the make the following of make the following of a. whether the area depicted on plan(s) and/or map(s) references	determination(s). Check any that app
I request the make the following of Conservation Commission	determination(s erenced below i). Check any that app s an area subject to
I request the make the following of make the following of a. whether the area depicted on plan(s) and/or map(s) refer jurisdiction of the Wetlands Protection Act. Description	determination(s erenced below i n plan(s) and/o). Check any that app s an area subject to r map(s) referenced
I request the Conservation Commission a. whether the area depicted on plan(s) and/or map(s) refer jurisdiction of the Wetlands Protection Act. b. whether the boundaries of resource area(s) depicted on below are accurately delineated. c. whether the work depicted on plan(s) referenced below is d. whether the area and/or work depicted on plan(s) referenced of any municipal wetlands ordinance or bylaw of:	determination(s erenced below in n plan(s) and/o s subject to the enced below is s). Check any that app s an area subject to r map(s) referenced Wetlands Protection A
 a. whether the area depicted on plan(s) and/or map(s) refer jurisdiction of the Wetlands Protection Act. b. whether the boundaries of resource area(s) depicted on below are accurately delineated. c. whether the work depicted on plan(s) referenced below is d. whether the area and/or work depicted on plan(s) referenced 	determination(s erenced below in n plan(s) and/o s subject to the enced below is s). Check any that app s an area subject to r map(s) referenced Wetlands Protection A



Massachusetts Department of Environmental ProtectionBureau of Resource Protection - Wetlands

Arlington City/Town

WPA Form 1- Request for Determination of Applicability Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

C. F	>ro	iect	Desc	ri	ptio	n
------	-----	------	------	----	------	---

gradient state of the	59 Lowell Street Arlingto	n , 🗼 🚎		1000
	Street Address City/Town			
	Assessors Map/Plat Number Parcel/Lo	t Number		. ,
7.00 s	b. Area Description (use additional paper, if necessary):			
	,	erio. Para Para Para	** 	
	* ***			
		essentino.	· .	
	plane attac	ho		
	nlans attac	he		
	plans attac	he	d	
	plans attac	he	ed	
	plans attac	he	d	
	plans attac	he	d	
		he	d	
e tak	c. Plan and/or Map Reference(s):	he		nber 2020
		he		nber 2020
* 15 a v	c. Plan and/or Map Reference(s): Survey with included propopsed spa (hot tub) Title	he	4 Decem	nber 2020 nber 2020
	c. Plan and/or Map Reference(s): Survey with included propopsed spa (hot tub)	he	4 Decem	
	c. Plan and/or Map Reference(s): Survey with included propopsed spa (hot tub) Title Conservation Land plot with protected land identified	he	4 Decem Date 4 Decem Date	

and the result of the first of the confidency specification of the production of the confidence of the

Add a portable swim spa to yard for exercise purposes. Add a bush to offset imprevious land addition.



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands

Arlington
City/Town

WPA Form 1- Request for Determination of Applicability

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

b. Identify provisions of the Wetlands Protection Act or regulations which may exempt the applicant from having to file a Notice of Intent for all or part of the described work (use additional paper, if necessary).

3.	 If this application is a Request for Determination of Scope of Alternatives for v Riverfront Area, indicate the one classification below that best describes the proje 	
	Single family house on a lot recorded on or before 8/1/96	
	Single family house on a lot recorded after 8/1/96	
	Expansion of an existing structure on a lot recorded after 8/1/96	
	Project, other than a single-family house or public project, where the applican before 8/7/96	t owned the lot
	New agriculture or aquaculture project	
	Public project where funds were appropriated prior to 8/7/96	
	Project on a lot shown on an approved, definitive subdivision plan where there restriction limiting total alteration of the Riverfront Area for the entire subdivision	
	Residential subdivision; institutional, industrial, or commercial project	
	Municipal project	
	District, county, state, or federal government project	
	Project required to evaluate off-site alternatives in more than one municipality Environmental Impact Report under MEPA or in an alternatives analysis purs application for a 404 permit from the U.S. Army Corps of Engineers or 401 W Certification from the Department of Environmental Protection.	uant to an
	 b. Provide evidence (e.g., record of date subdivision lot was recorded) supportir above (use additional paper and/or attach appropriate documents, if necessary.) 	ng the classification
	Documentation from 1997 (house survey from previous owners incl	uded. House bui



Massachusetts Department of Environmental Protection

Bureau of Resource Protection - Wetlands

Name and address of the property owner:

Arlington City/Town

WPA Form 1- Request for Determination of Applicability

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40


D. Signatures and Submittal Requirements

I hereby certify under the penalties of perjury that the foregoing Request for Determination of Applicability and accompanying plans, documents, and supporting data are true and complete to the best of my knowledge.

I further certify that the property owner, if different from the applicant, and the appropriate DEP Regional Office were sent a complete copy of this Request (including all appropriate documentation) simultaneously with the submittal of this Request to the Conservation Commission.

Failure by the applicant to send copies in a timely manner may result in dismissal of the Request for Determination of Applicability.

Kathleen M Moriarty		Substitution of the	St. 😽	
Name 59 Lowell Street				N. A. S.
Mailing Address Arlington		1 (4)		
City/Town MA		. N		02476
State			7	Zip Code
				ocal newspaper at my expense Act regulations.
accordance with Section		f the Wetlands	Protection /	
accordance with Section	10.05(3)(b)(1) o	f the Wetlands	Protection /	Act regulations. December 2020
accordance with Section	10.05(3)(b)(1) o	f the Wetlands	Protection A	Act regulations. December 2020
Signature of Applicant	10.05(3)(b)(1) o	f the Wetlands	Protection A	Act regulations. December 2020 Date



Adam's Quality Masonry

53 Fairmount Ave Wakefield, MA 01880 US +1 5086417989 adam@adamsqualitymasonry.com



Estimate

ADDRESS

Kathleen Moriarty

ESTIMATE # 1111-172 DATE 12/15/2020


Payment Schedule		TOTAL		\$5	,000.00
Landscaping	Brin loan in and grade yard	· · · · · · · · · · · · · · · · · · ·		500.00	500.00
Masonry	Excavate dirt and haul it away. concrete level about 8' x 15' wit		1	4,500.00	4,500.00
SERVICE	DESCRIPTION		QTY	RATE	AMOUNT

Payment Schedule 1/2 deposit 1/2 upon completion

Fully licensed with CSL and HIC Fully insured

Accepted By

Accepted Date




Additional view of yard facing bike path/brook.



Other side of the porch from where the spa would be located.

Challenger 15 D


Elite Performance, Airless VIP, Programmable Speed*



The Challenger 15 D features a large uninhibited area that is perfect for swimming, exercise, and family fun. The Airless VIP Technology enhances swim jet performance, and a variable speed system* allows you to custor the pace. Plus, when it comes to hydrotherapy, rehabilitation, and relaxat nothing compares to the Xtreme Therapy Seat and Xtreme Therapy Cove The smallest footprint of any Challenger model, it's ideal for small backya

Dimensions	180" x 94" (457 cm x 239 cm)	ENE
Depth	60" (153 cm)	
Water Capacity	1,930 Gallons (7 306 L)	Market Market Combined to Company of the Company of
Weight: Dry/Full	2,530 lbs. (1 148 kg) / 19,555 lbs. (8 870 kg)	terminal america menteralis de la companya de la c
Propulsion System	Airless VIP Technology	
Power Requirement	50 Amp System	
Pumps	3	articularity facilities in management of the defect of the particular the contract of the cont
Stainless Steel Jets	45 (Including 6 VIP Jets)	(control of the Section Control of the Sectio
Water Features	5	mana kali mystanina (panyadangana panua 🖛 k
Ozone System	Standard	a Addison di Linthin Malamania
Filtration	EcoPur® Charge	al calego (part) May and and provide a children and
LED Lighting	Waterline	
Exclusive Features	AquaSpeed VSP™ * StressRelief Neck and Shoulder Seat™ Master Force™ Bio-Magnetic Therapy System	
Exclusive Accessories	H2Xercise™ Fitness System	n menuhu diamban-diampi menuhu-mbana
Premium Options	Fusion Air Sound System Wi-Fi Module Mast3rPur™ Water Management System SoftTread™ Nonslip, Comfort Floor System by Swim Wave Light Package	Dek®
Listing Number	9915	

^{*}For International Challenger swim spas, the AquaSpeed VSP system is currently not available. Instead, 3 high flow pumps create a strong, deep, and wide water current from a combination of 7 available speeds.




Datasets Products Cart		A STATE OF THE STA
		Trainer -
Select products below and then hit "Search Products"	Show M	ap Index
Area of Interest: Map Extent/Deametry	」	ngton, M X Q
▶Advanced Search		190011/111 /
Мар		The state of the s
□ U\$ Topo	New	
☐ Historical Topographic Maps	Coverage Sch	
Data	Printe Che worth	NOW ST.
☐ Boundaries - National Boundary Dataset	And the second of the second o	th many
☐ Elevation Products (3DEP)	MASSACHUSETIS AM	
☐ Elevation Source Data (3DEP) - Lidar, IfSAR	©	A. Land
Hydrography (NHDPlus HR, NHD, WBD)	PAUL NEVERO NO	O'MIEST.
☐ Imagery - NAIP Plus (1 meter to 1 foot)	THE PROPERTY OF THE PROPERTY O	
☐ Map Indices		
☐ Names - Geographic Names Information System (GNIS)		- 130 - 130
☐ Small-scale Datasets	Germane V 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	
☐ Structures - National Structures Dataset	Section 1	
☐ Topo Map Data and Topo Stylesheet		
☐ Transportation	· ·	
☐ Woodland Tint		
☐ Elevation - Topobathy		

National Land Cover Database (NLCD) data can be downloaded at the MRLC website.

-71.187424°, 42.427486°

^

600 ft



I HEREBY CERTIFY THAT THE BUILDING IS LOCATED AS SHOWN.

CLIPPORD E. ROBER

CLIFFORD E. ROBER, PLS


THIS PLAN MAY HAVE BEEN ALTERED IF THE SIGNATURE IS NOT SIGNED IN BLUE. OWNER: KATHLEEN MORIARTY

> PROPOSED PLOT PLAN #59 LOWELL STREET

> > ARLINGTON, MA (MIDDLESEX COUNTY)

SCALE: 1"= 30"

DATE: 9/22/2020



ROBER SURVEY

1072A MASSACHUSETTS AVENUE ARLINGTON, MA 02476 (781) 648-5533

4542PP3.DWG

466 of 479



Office of the Board of Assessors Robbins Memorial Town Hall Arlington, MA 02476 (781) 316-3050 Assessors@town.arlington.ma.us

Abutters List

Date: December 08, 2020


Subject Property Address: 59 LOWELL ST Arlington, MA

Subject Property ID: 58-6-9

Search Distance: 100 Feet - Conservation

The Board of Assessors certifies the names and addresses of requested parties in interest, all abutters to a single parcel within 100 feet.

Board of Assessors



Prop Location: 1 WATERMILL PL UNIT 519 Arlington, MA

Owner: MCSWEENEY MICHAEL & JUDITH

Co-Owner: Mailing Address: 1 WATERMILL PL #519 ARLINGTON, MA 02476

Prop ID: 58.C-1-520

Prop Location: 1 WATERMILL PL UNIT 520 Arlington, MA

Owner: LEE TSENG-CHUNG ETAL /TRUSTEES Co-Owner: TSENG-CHUNG LEE TRUST &

Mailing Address: 24 FAIRLAWN LN LEXINGTON, MA 02420

Prop ID: 58.C-1-521

Prop Location: 1 WATERMILL PL UNIT 521 Arlington, MA

Owner: ONE WATERMILL PLACE LLC

Co-Owner: Mailing Address: 70 STONE ROAD WALTHAM, MA 02453

Prop ID: 58.C-1-522

Prop Location: 1 WATERMILL PL UNIT 522 Arlington, MA

Owner: GUTIERREZ SONIA

Co-Owner:
Mailing Address:
1 WATERMILL PL #522
ARLINGTON, MA 02476

Prop ID: 58.C-1-523

Prop Location: 1 WATERMILL PL UNIT 523 Arlington, MA

Owner: DOYLE DANIEL K

Co-Owner: Mailing Address: 25 HUCKLEBERRY HILL RD LINCOLN, MA 01773

Prop ID: 58.C-1-524

Prop Location: 1 WATERMILL PL UNIT 524 Arlington, MA

Owner: MARSHALL EDWARD & JAMIE

Co-Owner: Mailing Address: 1 WATERMILL PL #524 ARLINGTON, MA 02476

Prop ID: 58.C-1-525

Prop Location: 1 WATERMILL PL UNIT 525 Arlington, MA

Owner: LYONS JACQUELINE

Co-Owner: Mailing Address: 1 WATERMILL PL #525 ARLINGTON, MA 02476

Prop ID: 58.C-1-526

Prop Location: 1 WATERMILL PL UNIT 526 Arlington, MA

Owner: DOWNEY ELIZABETH

Co-Owner: Mailing Address: 1 WATERMILL PL #526 ARLINGTON, MA 02476 Prop ID: 58.C-1-527

Prop Location: 1 WATERMILL PL UNIT 527 Arlington, MA

Owner: TONG ZHEN

Co-Owner: Mailing Address: 1 WATERMILL PL #527 ARLINGTON, MA 02474

Prop ID: 58.C-1-528

Prop Location: 1 WATERMILL PL UNIT 528 Arlington, MA

Owner: MOHAN PASUPATHICOIL RAMASWAMY

Co-Owner: MOHAN RADHIKA

Mailing Address:

1 WATERMILL PL #528 ARLINGTON, MA 02474

Prop ID: 59-1-12

Prop Location: 30 PARK AVE Arlington, MA

Owner: 30 PARK AVE ASSOC LLP

Co-Owner: Mailing Address: PO BOX 288

ARLINGTON, MA 02476

Prop ID: 59-1-19

Prop Location: 50 LOWELL ST Arlington, MA Owner: 30 PARK AVE ASSOCIATES LLC

Co-Owner: Mailing Address: PO BOX 288

ARLINGTON, MA 02476

Prop ID: 59-3-12.A

Prop Location: 78 BOW ST Arlington, MA Owner: ZERVOGLOS ANTHONY N--ETAL

Co-Owner: STRATKIS GEORGE

Mailing Address: 16 BRISCOE ST WOBURN, MA 01801

Prop ID: 59-3-13

Prop Location: 67-69 LOWELL ST Arlington, MA

Owner: KAPOOR KALPANA

Co-Owner: Mailing Address: 67 LOWELL ST

ARLINGTON, MA 02476

Prop ID: 59-3-4.A

Prop Location: 1-6 VIKING CT Arlington, MA Owner: JOHNSON SANDRA A-TR--ETAL Co-Owner: JOHNSON RICHARD A

Mailing Address:

1026 MASS AVENUE SUITE 1 ARLINGTON, MA 02476

469 of 479

Prop Location: 1 WATERMILL PL UNIT 430 Arlington, MA

Owner: BLACKSTONE BARBARA A

Co-Owner: Mailing Address:

1 WATERMILL PL #430 ARLINGTON, MA 02476

Prop ID: 58.C-1-500

Prop Location: 1 WATERMILL PL UNIT 500 Arlington, MA

Owner: CAFFREY PATRICIA

Co-Owner: Mailing Address: 1 WATERMILL PL #500 ARLINGTON, MA 02474

Prop ID: 58.C-1-501

Prop Location: 1 WATERMILL PL UNIT 501 Arlington, MA

Owner: DORAN MARY E

Co-Owner: Mailing Address:

1 WATERMILL PL #501 ARLINGTON, MA 02476

Prop ID: 58.C-1-502

Prop Location: 1 WATERMILL PL UNIT 502 Arlington, MA

Owner: YEE NORMAN N

Co-Owner: Mailing Address: 1 WATERMILL PL #502

ARLINGTON, MA 02476

Prop ID: 58.C-1-504

Prop Location: 1 WATERMILL PL UNIT 504 Arlington, MA

Owner: SO OI YIN CHEUNG

Co-Owner: Mailing Address: 21 PATTERSON RD LEXINGTON, MA 02421

Prop ID: 58.C-1-505

Prop Location: 1 WATERMILL PL UNIT 505 Arlington, MA

Owner: MARINI DONALD

Co-Owner: Mailing Address: 39 WORCESTER ST #3 BOSTON, MA 02118

Prop ID: 58.C-1-506

Prop Location: 1 WATERMILL PL UNIT 506 Arlington, MA

Owner: DONNELLY TIMOTHY G

Co-Owner: Mailing Address:

1 WATERMILL PL # 506 ARLINGTON, MA 02476

Prop ID: 58.C-1-507

Prop Location: 1 WATERMILL PL UNIT 507 Arlington, MA

Owner: LYLE JAMES E

Co-Owner: Mailing Address:

1 WATERMILL PL #507 ARLINGTON, MA 02476 Prop ID: 58.C-1-508

Prop Location: 1 WATERMILL PL UNIT 508 Arlington, MA

Owner: PATEL ALRIK

Co-Owner: Mailing Address:

1 WATERMILL PL APT 508 ARLINGTON, MA 02476

Prop ID: 58.C-1-509

Prop Location: 1 WATERMILL PL UNIT 509 Arlington, MA

Owner: LUDWIG SUSAN B/TRUSTEE

Co-Owner: SUSAN B LUDWIG LIVING TRUST

Mailing Address:

1 WATERMILL PL #509 ARLINGTON, MA 02476

Prop ID: 58.C-1-510

Prop Location: 1 WATERMILL PL UNIT 510 Arlington, MA

Owner: METALLIDES CYNTHIA/TRUSTEE Co-Owner: 1 WATERMILL PLACE UNIT 510

Mailing Address: 1 WATERMILL PL #510 ARLINGTON, MA 02476

Prop ID: 58.C-1-512

Prop Location: 1 WATERMILL PL UNIT 512 Arlington, MA

Owner: FENDELANDER LAHN M

Co-Owner: Mailing Address: 88 BUSH ST UNIT 4114

SAN JOSE, CA 95126

Prop ID: 58.C-1-514

Prop Location: 1 WATERMILL PL UNIT 514 Arlington, MA

Owner: O REGAN LYNNE A

Co-Owner: Mailing Address: 1 WATERMILL PL #514 ARLINGTON, MA 02476

Prop ID: 58.C-1-516

Prop Location: 1 WATERMILL PL UNIT 516 Arlington, MA

Owner: GARDINI ORNELLA

Co-Owner: Mailing Address: 1 WATERMILL PL #516 ARLINGTON, MA 02476

Prop ID: 58.C-1-517

Prop Location: 1 WATERMILL PL UNIT 517 Arlington, MA

Owner: MARVIT MARIAN

Co-Owner: Mailing Address: 1 WATERMILL PL #517 ARLINGTON, MA 02476

Prop ID: 58.C-1-518

Prop Location: 1 WATERMILL PL UNIT 518 Arlington, MA

470 of 479

Owner: FLEMING ROBERT P Co-Owner: MASSARO MARK

Mailing Address:

1 WATERMILL PL #518 ARLINGTON, MA 02476

Prop Location: 1 WATERMILL PL UNIT 410 Arlington, MA

Owner: FLAMM BARRY E

Co-Owner: Mailing Address:

1 WATERMILL PL #410 ARLINGTON, MA 02476

Prop ID: 58.C-1-412

Prop Location: 1 WATERMILL PL UNIT 412 Arlington, MA

Owner: JOYCE MARY TARA

Co-Owner: Mailing Address: 675 LAKE ST APT 223 OAK PARK, IL 60301

Prop ID: 58.C-1-414

Prop Location: 1 WATERMILL PL UNIT 414 Arlington, MA

Owner: LYNCH RICHARD T

Co-Owner: Mailing Address: 1 WATERMILL PL #414 ARLINGTON, MA 02476

Prop ID: 58.C-1-415

Prop Location: 1 WATERMILL PL UNIT 415 Arlington, MA

Owner: MORELAND RHOMANCE E TRUSTEE

Co-Owner: REM REALTY TRUST

Mailing Address:

1 WATERMILL PL #415 ARLINGTON, MA 02476

Prop ID: 58,C-1-416

Prop Location: 1 WATERMILL PL UNIT 416 Arlington, MA

Owner: BOUDREAU LORRAINE

Co-Owner: Mailing Address: 1 WATERMILL PL #416 ARLINGTON, MA 02474

Prop ID: 58.C-1-417

Prop Location: 1 WATERMILL PL UNIT 417 Arlington, MA

Owner: PRENDERGAST MICHAEL D ETAL

Co-Owner: TRS/ PRENDERGAST FAMILY TRUST

Mailing Address: 785 S GAYLORD ST DENVER, CO 80209-4629

Prop ID: 58.C-1-418

Prop Location: 1 WATERMILL PL UNIT 418 Arlington, MA

Owner: MC DERMOTT MARIAN D

Co-Owner:
Mailing Address:
1 WATERMILL PL #418
ARLINGTON, MA 02476

Prop ID: 58.C-1-419

Prop Location: 1 WATERMILL PL UNIT 419 Arlington, MA

Owner: TOSTI ALLAN & BARBARA A

Co-Owner: Mailing Address:

1 WATERMILL PL #419 ARLINGTON, MA 02476 Prop ID: 58.C-1-420

Prop Location: 1 WATERMILL PL UNIT 420 Arlington, MA

Owner: KIM DAVID E TRUSTEE

Co-Owner: PARK CHRISTINE H TRUSTEE

Mailing Address:

28631 BRECKENRIDGE DRIVE LAGUNA NIGUEL, CA 92677

Prop ID: 58.C-1-421

Prop Location: 1 WATERMILL PL UNIT 421 Arlington, MA

Owner: JABR REEM Z

Co-Owner: Mailing Address:

1 WATERMILL PL # 421 ARLINGTON, MA 02476

Prop ID: 58.C-1-423

Prop Location: 1 WATERMILL PL UNIT 423 Arlington, MA

Owner: SCHNEIDER MARJORIE L

Co-Owner: Mailing Address:

1 WATERMILL PL #423 ARLINGTON, MA 02476

Prop ID: 58.C-1-424

Prop Location: 1 WATERMILL PL UNIT 424 Arlington, MA

Owner: LIN YAN-TING Co-Owner: CHEN YIAN Mailing Address:

1 WATERMILL PL UNIT 424 ARLINGTON, MA 02476

Prop ID: 58.C-1-425

Prop Location: 1 WATERMILL PL UNIT 425 Arlington, MA

Owner: STACK MARY

Co-Owner: HOCHMUTH CHARLES

Mailing Address: 16 LOCKE ST

ARLINGTON, MA 02476

Prop ID: 58.C-1-426

Prop Location: 1 WATERMILL PL UNIT 426 Arlington, MA

Owner: GOPALAN MADHAVAN S

Co-Owner: Mailing Address: 3104 ARGENT PATH ELLICOTT CITY, MD 21043

Prop ID: 58.C-1-427

Prop Location: 1 WATERMILL PL UNIT 427 Arlington, MA

Owner: GERSHMAN RACHEL E

Co-Owner: Mailing Address: 1 WATERMILL PL #427 ARLINGTON, MA 02476

Prop ID: 58.C-1-428

Prop Location: 1 WATERMILL PL UNIT 428 Arlington, MA

Owner: OLSZEWSKI ANGELA M

Co-Owner: Mailing Address:

1 WATERMILL PL #428 ARLINGTON, MA 02476 471 of 479

Prop Location: 1 WATERMILL PL UNIT 320 Arlington, MA

Owner: HENIZE BEATRIX

Co-Owner: Mailing Address:

1 WATERMILL PL #320 ARLINGTON, MA 02476

Prop ID: 58.C-1-321

Prop Location: 1 WATERMILL PL UNIT 321 Arlington, MA

Owner: KARGER EVA R

Co-Owner: Mailing Address: 1 WATERMILL PL #321

ARLINGTON, MA 02476

Prop ID: 58.C-1-322

Prop Location: 1 WATERMILL PL UNIT 322 Arlington, MA

Owner: GRIFFIN BONNIE M

Co-Owner: Mailing Address:

1 WATERMILL PL #322 ARLINGTON, MA 02476

Prop ID: 58.C-1-323

Prop Location: 1 WATERMILL PL UNIT 323 Arlington, MA

Owner: LEFEBVRE LEONARD S

Co-Owner: Mailing Address:

1 WATERMILL PL #323 ARLINGTON, MA 02476

Prop ID: 58.C-1-324

Prop Location: 1 WATERMILL PL UNIT 324 Arlington, MA

Owner: WHALEN FRANCIS T

Co-Owner: Mailing Address:

1 WATERMILL PL #324 ARLINGTON, MA 02476

Prop ID: 58.C-1-325

Prop Location: 1 WATERMILL PL UNIT 325 Arlington, MA

Owner: MAKKI SALMAN MUHYEDIN ETAL Co-Owner: TRS/ MAKKIS LIVING TRUST

Mailing Address: 347 CALLE PUEBLO SAN CLEMENTE, CA 92672

Prop ID: 58.C-1-326

Prop Location: 1 WATERMILL PL UNIT 326 Arlington, MA

Owner: MOJAHED SHAHRIYAR

Co-Owner: Mailing Address: 8 THORNBERRY RD WINCHESTER, MA 01890

Prop ID: 58.C-1-328

Prop Location: 1 WATERMILL PL UNIT 328 Arlington, MA

Owner: BUSA DARLENE A

Co-Owner: Mailing Address:

1 WATERMILL PL #328 ARLINGTON, MA 02476 Prop ID: 58.C-1-330

Prop Location: 1 WATERMILL PL UNIT 330 Arlington, MA

Owner: SULLIVAN TERRANCE

Co-Owner: Mailing Address:

1 WATERMILL PL #330 ARLINGTON, MA 02476

Prop ID: 58.C-1-401

Prop Location: 1 WATERMILL PL UNIT 401 Arlington, MA

Owner: SERADERIAN VATCHE

Co-Owner: Mailing Address: 1 SCHOOLHOUSE LN LEXINGTON, MA 02421

Prop ID: 58.C-1-402

Prop Location: 1 WATERMILL PL UNIT 402 Arlington, MA

Owner: FEHLAN MAUREEN E

Co-Owner: Mailing Address:

1 WATERMILL PL #402 ARLINGTON, MA 02476

Prop ID: 58.C-1-404

Prop Location: 1 WATERMILL PL UNIT 404 Arlington, MA

Owner: MATSUI HISAKO

Co-Owner: Mailing Address:

1 WATERMILL PL #404 ARLINGTON, MA 02476

Prop ID: 58.C-1-405

Prop Location: 1 WATERMILL PL UNIT 405 Arlington, MA

Owner: ODONNELL LORRAINE

Co-Owner: Mailing Address:

1 WATERMILL PL #405 ARLINGTON, MA 02476

Prop ID: 58.C-1-406

Prop Location: 1 WATERMILL PL UNIT 406 Arlington, MA

Owner: LIARDONI ALBERT L

Co-Owner: Mailing Address: 1 WATERMILL PL #406

ARLINGTON, MA 02476

Prop ID: 58.C-1-407

Prop Location: 1 WATERMILL PL UNIT 407 Arlington, MA

Owner: OSOFSKY DAVID

Co-Owner: Mailing Address: 1 WATERMILL PL #407 ARLINGTON, MA 02476

Prop ID: 58.C-1-409

Prop Location: 1 WATERMILL PL UNIT 409 Arlington, MA

Owner: ZASLAVSKY PAUL/ LIFE ESTATE Co-Owner: SHPIRT ANNA/ LIFE ESTATE

Mailing Address:

472 of 479 1 WATERMILL PL #409

ARLINGTON, MA 02476

Prop Location: 1 WATERMILL PL UNIT 302 Arlington, MA

Owner: HOCHMUTH CHARLES H Co-Owner: STACK MARY G

Mailing Address: 16 LOCKE ST

ARLINGTON, MA 02476

Prop ID: 58.C-1-304

Prop Location: 1 WATERMILL PL UNIT 304 Arlington, MA

Owner: TOBIN ALICE P

Co-Owner: Mailing Address: 1 WATERMILL PL UNIT 304

ARLINGTON, MA 02476

Prop ID: 58.C-1-305

Prop Location: 1 WATERMILL PL UNIT 305 Arlington, MA

Owner: BUSH ARTHUR H/ TRUSTEE Co-Owner: ARTHUR H BUSH TRUST

Mailing Address:

1 WATERMILL PL #305 ARLINGTON, MA 02476

Prop ID: 58.C-1-306

Prop Location: 1 WATERMILL PL UNIT 306 Arlington, MA

Owner: LENNOX MIRIAN C

Co-Owner: WORTHINGTON ANNABEL S

Mailing Address:

1 WATERMILL PL #306 ARLINGTON, MA 02476

Prop ID: 58.C-1-307

Prop Location: 1 WATERMILL PL UNIT 307 Arlington, MA

Owner: GAVIN TERRI M

Co-Owner: Mailing Address:

1 WATERMILL PL #307 ARLINGTON, MA 02476

Prop ID: 58.C-1-308

Prop Location: 1 WATERMILL PL UNIT 308 Arlington, MA

Owner: PETERSON JORDAN G

والمراقع المراقع المرا

Co-Owner: Mailing Address:

1 WATERMILL PL UNIT 308 ARLINGTON, MA 02476

Prop ID: 58.C-1-309

Prop Location: 1 WATERMILL PL UNIT 309 Arlington, MA

Owner: PRESSMAN PEGGY E

Co-Owner: Mailing Address: 1 WATERMILL PL #309 ARLINGTON, MA 02476

Prop ID: 58.C-1-310

Prop Location: 1 WATERMILL PL UNIT 310 Arlington, MA

Owner: LERMAN SCOTT M

Co-Owner: Mailing Address: 1 WATERMILL PL #310 ARLINGTON, MA 02476 Prop ID: 58.C-1-311

Prop Location: 1 WATERMILL PL UNIT 311 Arlington, MA

Owner: BACZKOWSKI DANIEL & ROSEMARIE

Co-Owner: Mailing Address: 1 WATERMILL PL #311 ARLINGTON, MA 02476

Prop ID: 58.C-1-312

Prop Location: 1 WATERMILL PL UNIT 312 Arlington, MA

Owner: BOYLE BARBARA

Co-Owner: Mailing Address: 109 GRAY STREET ARLINGTON, MA 02476

Prop ID: 58.C-1-314

Prop Location: 1 WATERMILL PL UNIT 314 Arlington, MA

Owner: QUIGLEY MARY A

Co-Owner: Mailing Address:

1 WATERMILL PL #314 ARLINGTON, MA 02476

Prop ID: 58.C-1-315

Prop Location: 1 WATERMILL PL UNIT 315 Arlington, MA

Owner: OREILLY PETER J

Co-Owner: Mailing Address: 1 WATERMILL PL #315

ARLINGTON, MA 02476

Prop ID: 58.C-1-316

Prop Location: 1 WATERMILL PL UNIT 316 Arlington, MA

Owner: FISHER CHRISTINA/ TRUSTEE

Co-Owner: ANNE M DIMAURO IRREVOCABLE TR

Mailing Address:

1 WATERMILL PL #316 ARLINGTON, MA 02476

Prop ID: 58.C-1-317

Prop Location: 1 WATERMILL PL UNIT 317 Arlington, MA

Owner: SINGER BETH

Co-Owner: Mailing Address: 1 WATERMILL PL #317 ARLINGTON, MA 02476

Prop ID: 58.C-1-318

Prop Location: 1 WATERMILL PL UNIT 318 Arlington, MA

Owner: COOK MELISSA K

Co-Owner: Mailing Address: 1 WATERMILL PL #318 ARLINGTON, MA 02476

Prop ID: 58.C-1-319

Prop Location: 1 WATERMILL PL UNIT 319 Arlington, MA

Owner: KEELER MARY L

Co-Owner: Mailing Address:

95 CLARKS FARM RD 473 of 479

CARLISLE, MA 01741

Prop Location: 1 WATERMILL PL UNIT 215 Arlington, MA

Owner: FREINER KENNETH OLIVER JR

Co-Owner: FREINER HOLLY T

Mailing Address:

1 WATERMILL PL #215 ARLINGTON, MA 02474

Prop ID: 58.C-1-216

Prop Location: 1 WATERMILL PL UNIT 216 Arlington, MA

Owner: SCHRAMM ALLAN N & MARGARET

Co-Owner: Mailing Address: 1 WATERMILL PL #216

ARLINGTON, MA 02476

Prop ID: 58.C-1-217

Prop Location: 1 WATERMILL PL UNIT 217 Arlington, MA

Owner: LAPORTA CARMEN G

Co-Owner: LAPORTA MONAGHAN JOAN

Mailing Address: 1 WATERMILL PL #217 ARLINGTON, MA 02476

Prop ID: 58.C-1-218

Prop Location: 1 WATERMILL PL UNIT 218 Arlington, MA

Owner: VOZZELLA EMMA L

Co-Owner: Mailing Address: 1 WATERMILL PL #218 ARLINGTON, MA 02476

Prop ID: 58.C-1-219

Prop Location: 1 WATERMILL PL UNIT 219 Arlington, MA

Owner: GAVRILLES BESSIE Co-Owner: LIFE ESTATE

Mailing Address:

1 WATERMILL PL #219 ARLINGTON, MA 02476

Prop ID: 58.C-1-220

Prop Location: 1 WATERMILL PL UNIT 220 Arlington, MA

Owner: BUNTROCK REBECCA M/TRUSTEE Co-Owner: MARK BUNTROCK REALTY TRUST

Mailing Address: 1 WATERMILL PL #220 ARLINGTON, MA 02476

Prop ID: 58.C-1-221

Prop Location: 1 WATERMILL PL UNIT 221 Arlington, MA

Owner: LIEPKALNS ERIKA A

Co-Owner:
Mailing Address:
1 WATERMILL PL #221
ARLINGTON, MA 02476

Prop ID: 58.C-1-222

Prop Location: 1 WATERMILL PL UNIT 222 Arlington, MA

Owner: PATKI ABHAY H

Co-Owner: Mailing Address:

1 WATERMILL PL #222 ARLINGTON, MA 02476 Prop ID: 58.C-1-223

Prop Location: 1 WATERMILL PL UNIT 223 Arlington, MA

Owner: CHAO ALAN I

Co-Owner: Mailing Address: 1 WATERMILL PL #223 ARLINGTON, MA 02476

Prop ID: 58.C-1-224

Prop Location: 1 WATERMILL PL UNIT 224 Arlington, MA

Owner: BEAUCHESNE DIANE L

Co-Owner:
Mailing Address:
219 LOWELL ST
METHUEN, MA 01844

Prop ID: 58.C-1-225

Prop Location: 1 WATERMILL PL UNIT 225 Arlington, MA

Owner: MENSAH ROBERT D

Co-Owner: Mailing Address:

1 WATERMILL PL #225 ARLINGTON, MA 02476

Prop ID: 58.C-1-226

Prop Location: 1 WATERMILL PL UNIT 226 Arlington, MA

Owner: UCCELLO MICHAEL

Co-Owner:
Mailing Address:

1 WATERMILL PL #226 ARLINGTON, MA 02476

Prop ID: 58.C-1-228

Prop Location: 1 WATERMILL PL UNIT 228 Arlington, MA

Owner: SILVA THERESA/ TRUSTEE

Co-Owner: THERESA SILVA FAMILY TRUST

Mailing Address:

1 WATERMILL PL #228 ARLINGTON, MA 02476

Prop ID: 58.C-1-230

Prop Location: 1 WATERMILL PL UNIT 230 Arlington, MA

Owner: HARTIG DAVID

Co-Owner: Mailing Address:

1 WATERMILL PL UNIT 230 ARLINGTON, MA 02474

Prop ID: 58.C-1-3

Prop Location: 1 WATERMILL PL UNIT 3 Arlington, MA

Owner: BRADLEY VINCENT

Co-Owner: Mailing Address: 1 WATERMILL PL #3 ARLINGTON, MA 02476

Prop ID: 58.C-1-301

Prop Location: 1 WATERMILL PL UNIT 301 Arlington, MA

Owner: BILOW YAKOV

Co-Owner: Mailing Address:

1 WATERMILL PL #301 474 of 479

ARLINGTON, MA 02476

Prop Location: 1 WATERMILL PL UNIT 126 Arlington, MA

Owner: MIGAUSKY MARJORIE R

Co-Owner: Mailing Address:

1 WATERMILL PL #126 ARLINGTON, MA 02476

Prop ID: 58.C-1-128

Prop Location: 1 WATERMILL PL UNIT 128 Arlington, MA

Owner: MCKENZIE J STEWART & RICKI L/

Co-Owner: TRS/ MCKENZIE REVOCABLE TRUST

Mailing Address: 81 WILLOW AVE

SOMERVILLE, MA 02144

Prop ID: 58.C-1-130

Prop Location: 1 WATERMILL PL UNIT 130 Arlington, MA

Owner: STANLEY STEPHANIE M & WILLIAM

Co-Owner: Mailing Address:

1 WATERMILL PL #130 ARLINGTON, MA 02476

Prop ID: 58.C-1-2

Prop Location: 1 WATERMILL PL UNIT 2 Arlington, MA

Owner: O SULLIVAN COLIN/KATHERINE R

Co-Owner: Mailing Address: 1 WATERMILL PL #2 ARLINGTON, MA 02476

Prop ID: 58.C-1-201

Prop Location: 1 WATERMILL PL UNIT 201 Arlington, MA

Owner: COCONCEA PHILIP

Co-Owner: DAVIDSON CHARLOTTE

Mailing Address:

1 WATERMILL PL #201 ARLINGTON, MA 02476

Prop ID: 58.C-1-202

Prop Location: 1 WATERMILL PL UNIT 202 Arlington, MA

Owner: D SOUZA ERIC B/ TRUSTEE

Co-Owner: ERIC B D SOUZA 2011 REVOCABLE

Mailing Address: 80 RUBLEE STREET ARLINGTON, MA 02476

Prop ID: 58.C-1-204

Prop Location: 1 WATERMILL PL UNIT 204 Arlington, MA

Owner: FRATIC JOSEPH JR

Co-Owner: Mailing Address: 1 WATERMILL PL #204 ARLINGTON, MA 02474

Prop ID: 58.C-1-205

Prop Location: 1 WATERMILL PL UNIT 205 Arlington, MA

Owner: GIBBONS JOAN F/TRUSTEE

Co-Owner: JOAN F GIBBONS REVOCABLE TRUST

Mailing Address:

1 WATERMILL PL #205 ARLINGTON, MA 02476 Prop ID: 58.C-1-206

Prop Location: 1 WATERMILL PL UNIT 206 Arlington, MA

Owner: NARASIMHAN KAMALA

Co-Owner: Mailing Address:

31 CHATHAM STREET ARLINGTON, MA 02476

Prop ID: 58.C-1-207

Prop Location: 1 WATERMILL PL UNIT 207 Arlington, MA

Owner: DUBE CATHERINE/ TRUSTEE Co-Owner: DUBE LIVING TRUST

Mailing Address:

1 WATERMILL PL #207 ARLINGTON, MA 02476

Prop ID: 58.C-1-208

Prop Location: 1 WATERMILL PL UNIT 208 Arlington, MA

Owner: WINSTON JENNIFER L

Co-Owner: Mailing Address:

1 WATERMILL PL #208 ARLINGTON, MA 02476

Prop ID: 58.C-1-209

Prop Location: 1 WATERMILL PL UNIT 209 Arlington, MA

Owner: UCCELLO PAUL & MICHAEL/TRS

Co-Owner: WALNUT TERRACE PROPERTY TRUST

Mailing Address: 1 WATERMILL PL 209 ARLINGTON, MA 02474

Prop ID: 58.C-1-210

Prop Location: 1 WATERMILL PL UNIT 210 Arlington, MA

Owner: YANG SHENGYUAN & Co-Owner: LONG LIJUAN

Mailing Address:

1 WATERMILL PL #210 ARLINGTON, MA 02476

Prop ID: 58.C-1-211

Prop Location: 1 WATERMILL PL UNIT 211 Arlington, MA

Owner: GREENE SHERRY A

Co-Owner: Mailing Address: 1 WATERMILL PL #211 ARLINGTON, MA 02476

Prop ID: 58.C-1-212

Prop Location: 1 WATERMILL PL UNIT 212 Arlington, MA

Owner: WEBBER SUSAN D

Co-Owner: Mailing Address: 1 WATERMILL PL # 212

ARLINGTON, MA 02476

Prop ID: 58.C-1-214

Prop Location: 1 WATERMILL PL UNIT 214 Arlington, MA

Owner: LEAL RAFAELA

Co-Owner: Mailing Address:

1 WATERMILL PL # 214

475 of 479

ARLINGTON, MA 02476

Prop Location: 1 WATERMILL PL UNIT 109 Arlington, MA

Owner: SCIUCCO FIORE A

Co-Owner: Mailing Address:

1 WATERMILL PL #109 ARLINGTON, MA 02476

Prop ID: 58.C-1-110

Prop Location: 1 WATERMILL PL UNIT 110 Arlington, MA

Owner: BIRD DAVID G

Co-Owner: Mailing Address:

1 WATERMILL PL # 110 ARLINGTON, MA 02476

Prop ID: 58.C-1-111

Prop Location: 1 WATERMILL PL UNIT 111 Arlington, MA

Owner: FRENIER SARA A

Co-Owner: Mailing Address:

1 WATERMILL PL #111 ARLINGTON, MA 02476

Prop ID: 58.C-1-112

Prop Location: 1 WATERMILL PL UNIT 112 Arlington, MA

Owner: CHELIKANI RAHUL & Co-Owner: KOTAGIRI NAMRATA

Mailing Address:

1 WATERMILL PL #112 ARLINGTON, MA 02476

Prop ID: 58.C-1-114

Prop Location: 1 WATERMILL PL UNIT 114 Arlington, MA

Owner: HONTON STEPHEN P

Co-Owner: PETERSCHMITT MARIA JUDITH

Mailing Address: 49 PAYSON TERR BELMONT, MA 02478

Prop ID: 58.C-1-115

Prop Location: 1 WATERMILL PL UNIT 115 Arlington, MA

Owner: LECCACORVI KRISTEN Co-Owner: LOPEZ RICARDO

Mailing Address:

1 WATERMILL PL #115 ARLINGTON, MA 02474

Prop ID: 58.C-1-116

Prop Location: 1 WATERMILL PL UNIT 116 Arlington, MA

Owner: LYONS MARY T

Co-Owner: Mailing Address:

1 WATERMILL PL #116 ARLINGTON, MA 02476

Prop ID: 58.C-1-117

Prop Location: 1 WATERMILL PL UNIT 117 Arlington, MA

Owner: KOUL AJAY

Co-Owner: Mailing Address: 17 PHEASANT LN LEXINGTON, MA 02421 Prop ID: 58.C-1-118

Prop Location: 1 WATERMILL PL UNIT 118 Arlington, MA

Owner: LOPES MARIETTA

Co-Owner: Mailing Address:

1 WATERMILL PL #118 ARLINGTON, MA 02476

Prop ID: 58.C-1-119

Prop Location: 1 WATERMILL PL UNIT 119 Arlington, MA

Owner: DOHERTY JOHN J & ANN/LIFE ESTA

Co-Owner: Mailing Address: 1 WATERMILL PL #119 ARLINGTON, MA 02476

Prop ID: 58.C-1-120

Prop Location: 1 WATERMILL PL UNIT 120 Arlington, MA

Owner: RAUCHWARGER JUDITH

Co-Owner: Mailing Address:

1 WATERMILL PL #120 ARLINGTON, MA 02476

Prop ID: 58.C-1-121

Prop Location: 1 WATERMILL PL UNIT 121 Arlington, MA

Owner: BROOK REALTY LLC

Co-Owner: Mailing Address:

1 WATERMILL PL #121 ARLINGTON, MA 02476

Prop ID: 58.C-1-122

Prop Location: 1 WATERMILL PL UNIT 122 Arlington, MA

Owner: PETROWSKY JOAN

Co-Owner: Mailing Address:

1 WATERMILL PL #122 ARLINGTON, MA 02476

Prop ID: 58.C-1-123

Prop Location: 1 WATERMILL PL UNIT 123 Arlington, MA

Owner: GIAUQUE MICHAEL & ANN

Co-Owner: Mailing Address:

1 WATERMILL PL #123 ARLINGTON, MA 02476

Prop ID: 58.C-1-124

Prop Location: 1 WATERMILL PL UNIT 124 Arlington, MA

Owner: MUGNAI DONALD J

Co-Owner: Mailing Address: 1 WATERMILL PL #124 ARLINGTON, MA 02476

Prop ID: 58.C-1-125

Prop Location: 1 WATERMILL PL UNIT 125 Arlington, MA

Owner: KELLEHER MARIA D Co-Owner: ANTHONY REBECCA H

Mailing Address:

1 WATERMILL PL #125 ARLINGTON, MA 02476

476 of 479

Abutters List

Date: December 08, 2020

Subject Property Address: 59 LOWELL ST Arlington, MA

Subject Property ID: 58-6-9 Search Distance: 100 Feet

Prop ID: 58-6-9

Prop Location: 59 LOWELL ST Arlington, MA

Owner: MORIARTY KATHLEEN M

Co-Owner: Mailing Address: 59 LOWELL ST

ARLINGTON, MA 02476

Prop ID: 58-6-10

Prop Location: 61 LOWELL ST Arlington, MA Owner: MURRAY RICHARD & KATHERINE

Co-Owner: Mailing Address: 61 LOWELL ST

ARLINGTON, MA 02476

Prop ID: 58-6-11.A

Prop Location: 63 LOWELL ST Arlington, MA Owner: CHANEY BRIDGET M/TRUSTEE Co-Owner: BRIDGET CHANEY TRUST

Mailing Address:

13780 JULIAS WAY UNIT 1013 FORT MYERS, FL 33919

Prop ID: 58-6-5.A

Prop Location: 51 LOWELL ST Arlington, MA

Owner: SITTEL CORNELIA

Co-Owner: Mailing Address: 51 LOWELL ST

ARLINGTON, MA 02476

Prop ID: 58-6-6

Prop Location: 53 LOWELL ST Arlington, MA Owner: WHITE ALEKSANDR J & LAURA F

Co-Owner: Mailing Address: 53 LOWELL ST

ARLINGTON, MA 02476

Prop ID: 58-6-7

Prop Location: 57 LOWELL ST Arlington, MA

Owner: CALLAHAN DANIEL J IV Co-Owner: CALLAHAN ELIZABETH

Mailing Address: 57 LOWELL ST

ARLINGTON, MA 02476

Prop ID: 58.C-1-1

Prop Location: 1 WATERMILL PL UNIT 1 Arlington, MA

Owner: ALEXANDER FREDERICK J/TRUSTEE

Co-Owner: C.A. NOMINEE TRUST

Mailing Address: 1 WATERMILL PL #1 ARLINGTON, MA 02476 Prop ID: 58.C-1-101

Prop Location: 1 WATERMILL PL UNIT 101 Arlington, MA

Owner: SHEPARDSON KEVIN W & NINA E

Co-Owner: Mailing Address: 1 WATERMILL PL #101 ARLINGTON, MA 02476

Prop ID: 58.C-1-102

Prop Location: 1 WATERMILL PL UNIT 102 Arlington, MA

Owner: CUSICK PETER J

Co-Owner: Mailing Address: 1 WATERMILL PL #102 ARLINGTON, MA 02476

Prop ID: 58.C-1-104

Prop Location: 1 WATERMILL PL UNIT 104 Arlington, MA

Owner: RANGANATHAN RAJESHWARI Co-Owner: SRIRAMAN VENKATARAMAN

Mailing Address: 103 BRAND ST

ARLINGTON, MA 02474

Prop ID: 58.C-1-105

Prop Location: 1 WATERMILL PL UNIT 105 Arlington, MA

Owner: KEZERIAN KAREN A/TRUSTEE Co-Owner: MADDEN SUSAN M/TRUSTEE

Mailing Address:

1 WATERMILL PL #105 ARLINGTON, MA 02476

Prop ID: 58.C-1-106

Prop Location: 1 WATERMILL PL UNIT 106 Arlington, MA

Owner: MULLANE-ROBINSON KAREN Co-Owner: MULLANE THOMAS P

Mailing Address:

77 HERITAGE HILL RD WINDHAM, NH 03087

Prop ID: 58.C-1-107

Prop Location: 1 WATERMILL PL UNIT 107 Arlington, MA

Owner: MINSON RYAN T & JULIA

Co-Owner: Mailing Address: 22 LENNON RD

ARLINGTON, MA 02474

Prop ID: 58.C-1-108

Prop Location: 1 WATERMILL PL UNIT 108 Arlington, MA

Owner: REIS MANUEL R & TERESA C

Co-Owner: Mailing Address: 2 VINE BROOK WAY

UNIT 108

WOBURN, MA 01801

477 of 479

59 Lowell Street, Proposed Swim Spa



Blue tarp marks proposed spa location.



Yard facing brook



Additional view of yard facing bike path/brook.



Other side of the porch from where the spa would be located.